TELECOMMUNICATIONS INFRASTRUCTURE CABLING SYSTEM LEGEND

SYMBOL	DESCRIPTION	# OF CAT 6 CABLES/JACKS	# OF RG-6 COAX AND OUTLET	NOTES	PROVIDE 1-GANG BACKBOX	PROVIDE 2-GANG BACKBOX	PROVIDE 1-GANG PLASTER RING	PROVIDE 2-GANG PLASTER RING	PROVIDE (QTY/x") CONDUIT	NOTES
DDC	DDC NETWORK CONNECTION	(2)	---	PROVIDE TWO CAT6 CABLES TO LOCATION.		✓	✓		(1)/1"C. FOR COMM. CABLES.	HOMERUN 3/4" CONDUIT FROM OUTLET TO SERVING CLOSET. IN MECHANICAL ROOM, RUN CONDUIT TO FINAL LOCATION AS DIRECTED BY EQUIPMENT INSTALLER.
W	WALL-MOUNTED TELEPHONE OUTLET, MOUNTED 48" AFF	(1)	---	FOR EXTERIOR OUTLET LABELED 'WP', PROVIDE WEATHERPROOF ENCLOSURE	✓		✓		(1)/3/4"C. FOR COMM. CABLES.	SEE MOUNTING DETAIL. COORDINATE EXACT MOUNTING HEIGHT AND ELEVATION WITH ARCHITECTURAL ELEVATIONS AND PLANS.
N2	WALL MOUNTED COMMUNICATIONS OUTLET (CO), TYPE 'N2'.	(2)	---	RJ-45 JACKS WITH 568A CONFIGURATION. CAT 6 UTP CABLE		✓	✓		(1)/1"C. FOR COMM. CABLES.	SEE MOUNTING DETAIL.



KEY NOTES

1. PROVIDE WALL MOUNTED A/V JUNCTION BOX (8"x8"x4") FLUSH MOUNTED AT 18" A.F.F. FOR A/V PRESENTER'S STATION.
2. PROVIDE A/V JUNCTION BOX ABOVE CEILING (8"x8"x4").
3. PROVIDE ONE (1) SPARE 2" CONDUIT WITH PULL STRING FROM TOWER TO I.T. ROOM 113.

1 TELECOMMUNICATIONS SYSTEM PLAN
SCALE: 1/4"= 1'-0"

4' 0 4' 8'
GRAPHIC SCALE 1/4"=1'-0"

ADAMS CONSULTING ENGINEERING, INC.
3 West Garden Street • Suite 608 • Pensacola, Florida 32502
Office: 850-444-0095 • Fax: 850-444-0096 • E-mail: scott@adamscei.com
SCOTT A. ADAMS, P.E. FL LICENSE No. 57949 • CA No. 26311

100% RTA SUBMITTAL

BASKERVILLE-DONOVAN, INC.
Innovative Infrastructure Solutions
449 W. MAIN ST., PENSACOLA, FL 32502 (850)438-9661
ENGINEERING BUSINESS: EB-0000340
Pensacola - Panama City Beach - Tallahassee - Mobile - Brevard County - Tampa

This drawing is the property of BASKERVILLE-DONOVAN, INC. and is not to be reproduced in whole or in part. It is not to be used on any other project and is to be returned upon request.

SCOTT A. ADAMS, P.E.

OLF-X
PHASE II – AIRFIELD

NO.	DATE	APPR.	REVISION/ACTION TAKEN
001	02/13/18	SAA	ADDENDUM TO BID DOCUMENTS
003	02/23/18	SAA	ADDENDUM TO BID DOCUMENTS

NOT RELEASED FOR CONSTRUCTION BY DATE / /

PROJECT NO: 25898.03
DESIGNED BY: SAA
DRAWN BY: DAH
CHK'D BY: SAA
PROJ. MGR: –
DATE: FEBRUARY 2018

TELECOMMUNICATIONS SYSTEM PLAN

T-101

S:\2017\17118 OLF\17118-T101.dwg, Feb 23, 2018 - 12:53:21PM, Deborah