ROOM SIGNAGE SCHEDULE						
Mark	ROOM NUMBER	ROOM NAME	SIGN TYPE	TEXT	WALL	REMARKS
1	110	AGENT STOR.	BB4	-	WALL	-
2	101	APPARATUS BAY	BB4	-	WALL	-
3	105	DAY ROOM	BB4	-	WALL	-
4	103	OFFICE	BB4	-	WALL	-
5	104	OFFICE	BB4	-	WALL	-
6	114	HVAC	BB4	-	WALL	-
7	106	RECREATIONAL RM.	BB4	-	WALL	-
8	108	WOMEN'S	BB7	-	WALL	-
9	107	MEN'S	BB7	-	WALL	-
10	115	JAN. CLOSET	BB4		WALL	-
11	EXTERIOR		DD1	-	WALL	-
12	EXTERIOR		BH	-	WALL	-
13	EXTERIOR		DD1	-	WALL	-
14	EXTERIOR		DD1	-	WALL	-
15	EXTERIOR		DD1	-	WALL	-
16	EXTERIOR		DD1	-	WALL	-
17	EXTERIOR		DD1	-	WALL	-
18	EXTERIOR		BH	-	WALL	-

ROOM SIGNAGE COUNT
BB4
8
BB7
2
BN
2
DD1
6

SIGNAGE COMMENTS:

1. EXTERIOR BUILDING NUMBERS SHALL BE PREFINISHED ALUMINUM (1/8" THICK)
2. INTERIOR SIGNAGE SHALL BE ACRYLIC PLASTIC 0.080 INCH THICKNESS MIN. CONFORMING TO ANSI Z97.1
3. ALL INTERIOR SIGNAGE SHALL ADHERE OR BE CONCEALED FASTENED TO ADJACENT SURFACE.
4. PROVIDE COLOR PALLETE FOR FINAL APPROVAL TO OWNER.
5. PROVIDE WARRANTY AGAINST DEFECTS IN WORKMANSHIP AND MATERIAL FOR A PERIOD OF 2 YEARS.
6. RAISED LETTERS, BRAILLE AND NUMBER ON ALL SIGNS SHALL CONFORM TO 36 CFR 1191.
7. FONTS AND LETTER SIZES SHALL BE COORDINATED WITH OWNER FOR FINAL APPROVAL.



1 TYPE BB1/BB2/BB3/DD1

2'-8" 1'-4" 0" 2'-8" 5'-4"

SCALE: 3/8" = 1'-0"



4 SERVICE ID SIGN TYPE BB7

4" 8" 0" 4" 2"

SCALE: 3" = 1'-0"



2 TYPE BN

2'-8" 1'-4" 0" 2'-8" 5'-4"

SCALE: 3/8" = 1'-0"



5 TYPE BB6

4" 8" 0" 4" 2"

SCALE: 3" = 1'-0"



3 TYPE BN

8" 4" 0" 8" 1'-4"

SCALE: 1 1/2" = 1'-0"



6 OFFICE ID TYPE BB4

4" 2" 0" 4" 8"

SCALE: 3" = 1'-0"



7 REGULATION SIGN TYPE DD1

4" 2" 0" 4" 8"

SCALE: 3" = 1'-0"

BASIS OF DESIGN:
INTERIOR FINISH MATERIAL AND COLOR LEGEND

CODE	MATERIAL	MANUFACTURER	STYLE	COLOR	REMARKS
FLOORING					
CPT	CARPET TILE	BIGELOW	ELEMENTAL FACTOR	7861 NORTHWOODS	24x24
PCT	PORCELAIN TILE	DALTILE	KEYSTONES	D050 MOTTLED MEDIUM BROWN	2x2
VCT	VINYL COMPOSITION TILE	ARMSTRONG	IMPERIAL TEXTURE	51805 CAMEL BEIGE	12x12
SC	SEALED CONCRETE	TENNANT	WEARGUARD	420 CLEAR	
BASE					
PTB	PORCELAIN TILE BASE	DALTILE	CITY VIEW	CY05 NEIGHBORHOOD PARK	6x12 (COVE)
RB/TS	RUBBER BASE/ TRANSITION STRIP	FLEXCO		02 BARK	4" HIGH
WALLS - INTERIOR					
P-1	PAINT (INTERIOR WALLS)	SHERWIN WILLIAMS		6126 NAVAJO WHITE	EGGSHELL
P-2	PAINT (INTERIOR DOOR FRAMES)	SHERWIN WILLIAMS		6122 CAMELBACK	EGGSHELL
P-3	PAINT (RESTROOMS ONLY)	SHERWIN WILLIAMS		6126 NAVAJO WHITE	SEMI-GLOSS
WALLS - EXTERIOR					
P-5	PAINT (EXTERIOR DOORS)	SHERWIN WILLIAMS		MATCH: FED-STD #30140	SEMI-GLOSS
P-6	PAINT (EXTERIOR WALLS)	SHERWIN WILLIAMS		MATCH: FED-STD #36586	EGGSHELL
CEILINGS					
P-4	PAINT	SHERWIN WILLIAMS		7007 CEILING BRIGHT WHITE	FLAT
ACT	ACOUSTICAL TILE	ARMSTRONG	CORTEGA	WHITE - SQUARE LAY-IN	24x24
MISCELLANEOUS					
LCK	LOCKERS	GEAR GRID		TAN	SEE NOTE # 10
PL-1	PLASTIC LAMINATE	WILSONART		7122K-07 EMPIRE MAHOGANY	
PL-2	PLASTIC LAMINATE	WILSONART		7959K-78 HAMPTON WALNUT	
SS-1	SOLID SURFACE	CORIAN		THYME	1/2" THICK
SS-2	SOLID SURFACE	CORIAN		LINEN	1/2" THICK
SS-3	SOLID SURFACE	CORIAN		BISQUE	BOWL
MB	MINI BLINDS	HUNTER DOUGLAS		LIGHTLINES ANTIQUE WHITE	1"
GT	GROUT	CUSTOM BUILDING PRODUCTS		#382 BONE	
FRP	FIBER REINFORCED PANEL	MARLITE (INDURO FRP)		D354 DESIGNER WHITE	-
CG	CORNER GUARD	IPC		EGGSHELL	4' HIGH
MISCELLANEOUS - EXTERIOR PRODUCTS					
SSMR	STANDING SEAM METAL ROOF	ENGLERT MANUF. SERIES 1300		MATCH: FED-STD #30140	2" TALL
GLZ	LAMINATED GLAZING	PPG MANUFACTURER - SOLAR BAN 70XL		SOLAR BRONZE	IMPACT RESIST.
P-8	PAINT (BOLLARDS)	SHERWIN WILLIAMS		7040 SMOKEHOUSE	GLOSS

GENERAL NOTES:

1. ALL MANUFACTURERS LISTED ARE FOR INFORMATION ONLY.
2. FIBER REINFORCED PANEL TO BE INSTALLED IN FRONT OF CABINET BOTTOM OF RAISED COUNTERTOP IN KITCHEN AREA AND BEHIND JANITOR CLOSET FLOOR SINK, SEE INTERIOR ELEVATIONS AND FLOOR PLANS.
3. COORDINATE WITH USER ALL SIGNAGE ROOM AND OR OCCUPANT TITLES.
4. ALL WINDOWS TO RECEIVE MINI BLINDS, INSTALL PER MANUFACTURER INSTRUCTIONS.
5. INSTALL PORCELAIN TILE COVE BASE IN ALL RESTROOMS/SHOWER AREAS.
6. INSTALL BASE ON ALL CABINET BOTTOMS.
7. ALL INTERIOR PAINTS, COATING, SEALANTS AND ADHESIVES SHALL BE LOW VOC AND SHALL COMPLY WITH SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD) RULE #1168 LIMITS FOR VOLATILE ORGANIC COMPOUNDS (VOCs) LIMITS.
8. CONTRACTOR SHALL SUBMIT PRODUCT INFORMATION INCLUDING VOC INFORMATION, RECYCLED CONTENT AND REGIONAL MATERIAL USED IN ALL INTERIOR PRODUCTS.
9. CONTRACTOR SHALL SUBMIT ALL INTERIOR FINISH PRODUCT DATA FOR FINAL APPROVAL TO OWNER.
10. SET OF THREE (3) LOCKERS TO BE 12" DEEP X 62.5" WIDE X 83" TALL. PROVIDE FIVE (5) SETS. LOCKERS SHALL HAVE HANGING ROD, AND LOCKABLE TYPE. MOUNT LOCKER ON 6" CONCRETE CURB. SECURE LOCKER TO WALL.

100% RTA SUBMITTAL

BASKERVILLE-DONOVAN, INC.
Innovative Infrastructure Solutions
449 W. MAIN ST. PENSACOLA, FL 32502 (850)438-9661
ENGINEERING BUSINESS: EB-0000340
Pensacola - Panama City Beach - Tallahassee - Mobile - Brevard County - Tampa

This drawing is the property of BASKERVILLE-DONOVAN, INC. and is not to be reproduced in whole or in part. It is not to be used on any other project and is to be returned upon request.

OLF-X
PHASE II – AIRFIELD

NO.	DATE	APPR.	REVISION/ACTION TAKEN
003	02/23/18	YS	ADDENDUM TO BID DOCUMENTS

PROJECT NO: 25898.03
DESIGNED BY: DB
DRAWN BY: DB
CHK'D BY: SK
PROJ. MGR: –
DATE: FEBRUARY 2018

NOT RELEASED FOR CONSTRUCTION BY / DATE

SIGNAGE AND FINISH SELECTION

A-700

J:\2014prj\14073 BDI OLF Support Bldgs\Drwgs\WD\A-DWG\A-700.dwg, Feb 23, 2018 – 10:47:59AM, ysimon