

PLAN NORTH

1 FLOOR PLAN

4' 2' 0' 4' 8'

SCALE: 1/4" = 1'-0"

LEGEND

	METAL STUD PARTITION
	WOOD STUD PARTITION
FD	FLOOR DRAIN, SEE PLUMBING
FCO	FLOOR CLEAN OUT, SEE PLUMBING
CG-1	CORNER GUARD, SEE FINISH SCHEDULE
CG-2	END GUARD, SEE FINISH SCHEDULE
	2 HOUR RATED ASSEMBLY, SEE LIFE SAFETY PLAN
	DOTTED FURNITURE SHOWN FOR REFERENCE ONLY NOT IN CONTRACT
EWC	ELECTRIC WATER COOLER, SEE PLUMBING
DS/SB	PREFINISHED METAL DOWNSPOUT AND 2'-0" WIDE BY 3'-0" LONG SPLASH BLOCK
1	SIGNAGE REFER TO SHEET A-700
B	4'-0" TALL, 6" DIAMETER CONCRETE FILLED BOLLARD, SEE STRUCTURAL

KEYNOTES

1. PAVED AREA, REFER TO CIVIL PACKAGE
2. FLOOR SINK, SEE PLUMBING
3. PROVIDE 4'-0" WIDE BY 12" DEEP STAINLESS STEEL SHELVING WITH MOP HOLDER
4. PREFINISHED STEEL LOCKERS, SEE SHEET A-700
5. PROVIDE WALL BLOCKING AT THIS LOCATION FOR FUTURE WALL MOUNTED EQUIPMENT.
6. EYE WASH STATION, SEE PLUMBING DRAWINGS
7. TRENCH DRAIN, SEE PLUMBING DRAWINGS
8. OIL AND WATER SEPARATOR COVER, SEE PLUMBING DRAWINGS
9. 40" WIDE BY 40" TALL FIBER REINFORCED WALL PANEL, SEE PRODUCT INFORMATION ON SHEET A-700
10. UL RATED ALUMINUM THRESHOLD FOR INSTALLATION ON 1 1/2 HR RATED DOOR ASSEMBLY. INSTALL ON FULL BED OF SEALANT.
11. PROVIDE 6" MINIMUM CLEARANCE BETWEEN FACE OF STUD AND CMU WALL. SEE WALL SECTIONS ON SHEET A-310.
12. RUN FLOORING UNDERNEATH SINK, SEE DETAIL 3/A-420

WALL TYPES (SEE A-510)

- A — 5/8" GYPSUM WALLBOARD ON 2X4 WOOD STUDS @ 16" O.C., EXTEND 6" ABOVE FINISH CEILING.
- B — 5/8" GYPSUM WALLBOARD ON 2X4 WOOD STUDS @ 16" O.C., EXTEND TO UNDERSIDE OF WOOD DECKING
- C — 5/8" GYPSUM WALLBOARD ON 2X4 WOOD STUDS @ 16" O.C. INFILL WITH 1 1/2" ACOUSTICAL BATT INSULATION, EXTEND TO UNDERSIDE OF WOOD DECKING
- D — 5/8" GYPSUM WALLBOARD ON 2X6 WOOD STUDS @ 16" O.C. INFILL WITH 1 1/2" ACOUSTICAL BATT INSULATION, EXTEND TO UNDERSIDE OF WOOD DECKING

GENERAL NOTES

1. CONTRACTOR SHALL COORDINATE WITH OTHER TRADES, IF CONFLICTS ARISE CONTACT ARCHITECT.
2. THE CONTRACTOR SHALL PROVIDE REINFORCING BLOCKING BEHIND WALL MOUNTED AND CEILING EQUIPMENT. COORDINATE WITH A/V, DATA, FIRE ALARM AND ELECTRICAL DRAWINGS.
3. CONTRACTOR SHALL COORDINATE WORK WITH MECHANICAL, ELECTRICAL AND PLUMBING DRAWINGS.
4. REFER TO FINISH SCHEDULE ON SHEET A-600 FOR SURFACE FINISHES.

100% RTA SUBMITTAL

BASKERVILLE-DONOVAN, INC.
Innovative Infrastructure Solutions
449 W. MAIN ST., PENSACOLA, FL 32502 (850)438-9661
ENGINEERING BUSINESS: EB-0000340
Pensacola - Panama City Beach - Tallahassee - Mobile - Brevard County - Tampa

This drawing is the property of BASKERVILLE-DONOVAN, INC. and is not to be reproduced in whole or in part. It is not to be used on any other project and is to be returned upon request.

OLF-X
PHASE II – AIRFIELD

NO.	DATE	APPR.	REVISION/ACTION TAKEN
003	02/23/18	YS	ADDENDUM TO BID DOCUMENTS

NOT RELEASED FOR CONSTRUCTION BY DATE /

PROJECT NO: 25898.03
DESIGNED BY: YS
DRAWN BY: YS
CHK'D BY: CR
PROJ. MGR: –
DATE: FEBRUARY 2018

FLOOR PLAN

A-121

J:\2014prj\14073 BDI OLF Support Bldgs\Drwgs\WD\A-DWG\A-121.dwg, Feb 23, 2018 - 9:54:14AM, ysimon