

**BOARD OF COUNTY COMMISSIONERS
ESCAMBIA COUNTY, FLORIDA
OFFICE OF PURCHASING**

213 PALAFOX PLACE, 2nd Floor
P.O. BOX 1591

PENSACOLA, FL 32591-1591

TELEPHONE (850) 595-4980

(SUNCOM) 695-4980

(850) 595-4805

<http://www.myescambia.com/solicitations>



CLAUDIA SIMMONS
Purchasing Manager

November 1, 2016

To: All Known Prospective Bidders

ADDENDUM NUMBER 2:

Re: McNeal & Thompson Road Dirt Road Paving
Specification Number PD 16-17.001

Bidders:

This Addendum #2 for the following:

- 1. Remove the Bid Sheet provided with Addendum #1 and Replace with the Bid Form attached to and provided in Addendum #2.**

The attached Bid Form for Addendum #2 provides for the following changes.

Item #21, Revised Item Description and changed the Unit from EA to LS

Items #22 – Delete - Stricken out on Bid Form

Items #23 – Delete - Stricken out on Bid Form

Items #24 – Delete - Stricken out on Bid Form

Items #25 – Delete - Stricken out on Bid Form

Items #26 – Delete - Stricken out on Bid Form

Item 47 – Revised Item Description to Require Class 200 Pipe

Item 48 – Revised Item description from 1" water service to ¾" water service and added the requirement for brass saddles

This Addendum Number 2 is furnished to all known prospective bidders. Please sign and return one copy of this Addendum, with original signature, with your bid as an acknowledgement of your having received same. You may photo copy for your record.

Sincerely,

A handwritten signature in blue ink that reads "Claudia Simmons".

Claudia Simmons, Manager
Office of Purchasing

SIGNED: _____

COMPANY:

CS/lk

Addendum 2
16-17.001

PAY ITEMS - MCNEAL-THOMPSON ROAD

Addendum #2

Item No.	Item Description	Quantity	Units	Unit Price	Extension
1	Performance Bond	1	Per \$1000		
2	Mobilization, 0 - 15 Miles	1	EA		
3	Clearing and Grubbing, per County Specifications 2230 (Includes All Tree Removals), Estimated Quantity of 15494 sy	1	LS		
4	Relocate existing standard mailbox	8	EA		
5	Earthwork Excavate, Haul, and Install, On-site	34551	CY		
6	Earthwork Borrow, FDOT Specification 120-2.2.2	3240	CY		
7	3" Top Soil	35337	SY		
8	Stabilization Mat Type R-1	9142	SY		
9	2" County Spec 2500 Type SP 12.5 Asphalt, over 1500sy	20897	SY		
10	1 1/4" County Spec 2500 Type SP 12.5 Asphalt (Driveways) in place, includes compacted subgrade	673	SY		
11	12" Stabilized Subgrade, County Spec 2300, over 1000sy	22806	SY		
12	Prime Coat, over 1000sy	22409	SY		
13	8" Graded aggregate Base "Min. LBR 100 at 100% Modified Proctor", County Spec 2400, over 1000sy	1250	SY		
14	4" Sand Clay Base (Driveways), less than 1000sy	673	SY		
15	8" Sand-Clay Base, County Spec 2460, over 1000sy	22408	SY		
16	Thermoplastic 4" Double Solid Stripe, White or Yellow	8688	LF		
17	Thermoplastic Stop Bar	53	LF		
18	Stop Sign, R1-1	4	EA		
19	Black on Orange Warning Sign	16	EA		
20	Regulatory Sign Black on White Metal Sign	9	EA		
21	Develop and provide an approved MOT traffic safety plan both map type and written type by a Certified Work Zone Safety Traffic Supervisor. MOT shall include, but not limited to, message boards, temporary signs, cones, flag man, etc	1	LS		
22	Variable Message Sign	0	EA/Day		
23	Flag Man	4	EA/Day		
24	Black on Orange Warning Sign	0	EA/Day		
25	R1-1 Stop Metal Sign	4	EA/Day		
26	20" or Larger Reflective Striped Cone	109	EA/Day		
27	Fiber Reinforced Concrete Ditch Paving w/ Weep Holes, FDOT Index 281, Min 3" thick	13760	SY		
28	Misc. Concrete	15	CY		
29	Ditch Bottom Inlet Top with Single Traversable Slot, Type D	2	EA		
30	5' X 7' Structure Bottom, FDOT Index 200, 0-6' depth	2	EA		
31	18" RCP Pipe, 0'-6' depth	115	LF		
32	14" X 23" ERCP Pipe, 0'-6' depth	585	LF		
33	19" X 30" ERCP Pipe, 0'-6' depth	50	LF		
34	34" X 53" ERCP Pipe, 0'-6' depth	115	LF		
35	18" RCP Cross Drain MES, FDOT Index 272, 280	6	EA		
36	14" X 23" ERCP Side Drain MES, FDOT Index 273, 280	25	EA		
37	19" X 30" ERCP Cross Drain MES, FDOT Index 272, 280	2	EA		
39	Class I Concrete for Endwalls (steel included)	14	CY		
40	4' x12' Precast FDOT Box Culvert	50	LF		
41	Cast-in-Place Box Culvert Headwall (steel included)	30	CY		
42	Bedding Stone for Box Culvert, under 1000sy	30	CY		
43	Pipe Removal, 6"-24"	109	LF		

PAY ITEMS - MCNEAL-THOMPSON ROAD

Addendum #2

Item No.	Item Description	Quantity	Units	Unit Price	Extension
44	Pipe Removal, 30" and larger	136	LF		
45	Remove Existing Sand Bag Headwall, 6"-24" Pipe	3	EA		
46	Remove Existing Sand Bag Headwall, 30" and Larger	4	EA		
47	6" PVC Waterline, 0'-6' depth (Class 200)	6341	LF		
48	3/4" Water Service Line - Short with Brass Saddles	45	LF		
49	6" x 6" Tapping Sleeve w/Valve	1	EA		
50	6" x 6" x 6" Tee Fitting	3	EA		
51	6" Elbow, 22.5°, 45°, 90°	11	EA		
52	6" Gate Valve w/ Box	2	EA		
53	6" PVC Stub-out and cap	1	EA		
54	Relocate Water Meter	8	EA		
55	Re-connect Fire Hydrant	2	EA		
56	Centipede Sod, Staked, over 1000sy	35336	SY		
57	18" Depth Rip Rap Rubble w/ 4" Bedding Stone and Geotextile	105	SY		
58	Silt Fence Type III, over 500lf	16752	LF		
59	Establish, quantify, and submit an approved erosion control plan prepared by a certified technician.	1	EA		
60	NPDES Construction General Permit, NOI, and NOT (including SWPPP and monitoring), for use only with disturbed areas over 1.0 acre	1	EA		
61	4' Wire Fence	3215	LF		
62	Wood Split Rail Fence	280	LF		
63	Remove Wood Split Rail Fence	280	LF		
64	Remove Existing Wire Fence	3215	LF		
65	End/Pull Post, Wood Post, 4' Wire Fence	20	EA		
66	Waterproof Jobsite Storage Board Container/Tube for project information, permits, SWPPP plans, etc.	1	EA		
Subtotal:					