

BOARD OF COUNTY COMMISSIONERS

ESCAMBIA COUNTY, FLORIDA

OFFICE OF PURCHASING

213 PALAFOX PLACE, 2nd Floor

P.O. BOX 1591

PENSACOLA, FL 32591-1591

TELEPHONE (850) 595-4980

(SUNCOM) 695-4980

(850) 595-4805

<http://www.myescambia.com/solicitations>



CLAUDIA SIMMONS
Purchasing Manager

December 8, 2016

To: All Known Prospective Bidders

ADDENDUM NUMBER 5:

Re: Muscogee Road (CR297 A and US29) Widening and Drainage Improvements
Specification Number PD 16-17.010


Bidders:

This Addendum #5 for the following:

1. **Remove** the BID FORM. ADDENDUM #1 and **Replace** with the BID FORM ADDENDUM #5 attached to this Addendum #5 for the following changes:
 - a. Line item 19 was added – Asphalt lateral patch
 - b. Line item 21 was revised to remove relocation of camera pole, cabinet, sensors at sta 256+00.
2. **DELETE FILE "Muscogee Ph 1 11-30-2016.pdf" AND DO NOT USE**
3. **DOWNLOAD FROM THE WEBSITE AND REFER TO FILE "Muscogee Ph 1 12-05-2016.pdf" FOR THIS BID containing the following changes:**
 - a. Sheet 7 was revised to reflect removal of the scale sensors, camera pole, and cabinet at sta 256+00 as per FDOT direction. Sheet 13 and 29 were revised to remove replacement language for those items.
 - b. The conflict matrix on sheet 4 was revised to show removal of the sensors, camera pole, and cabinet.
 - c. Sheet 40 was modified to show 2" asphalt instead of 1.5" asphalt over the lateral patch

This Addendum Number 5 is furnished to all known prospective bidders. Please sign and return one copy of this Addendum, with original signature, with your bid as an acknowledgement of your having received same. You may photo copy for your record.

Sincerely,


Claudia Simmons, Manager
Office of Purchasing

SIGNED:
COMPANY:
CS/lk

Addendum 5
16-17.010

ADDENDUM #5 BID TAB

PD 16-17.010 MUSCOGEE ROAD (CR297A to US29) WIDENING AND DRAINAGE IMPROVEMENTS

Bid 1 - Muscogee Road (CR297A to Hwy 29) Road Widening and Drainage Improvements

Bid Item No.	Bid Item Description	Quantity	Unit	Unit Price	Extension
1-1	Mobilization	1	LS		
1-2	Prepare & Implement Maintenance of Traffic Plan (Must include Variable Message Board, Plan, Layout, and all appurtenances for MOT)	1	LS		
1-3	Clearing and Grubbing (Including but not limited to Removal of Debris, Trees, Landscaping, Hardscaping, Fences, Curb & Gutter, Concrete / Asphalt Driveways, Saw Cutting Concrete & Asphalt, Asphalt/Base/Subgrade, Inlet and Storm Pipe Removal, Guard Rails, Conc. Ditches, water mains, Etc) per Specification Section 2230. This bid item is all inclusive of items identified to be removed on the plans or as required to facilitate construction.	1	LS		
1-4	12" Forcemain (Existing 8" Forcemain Adjustment)	1	LS		
1-5	Fire Hydrant Relocation	2	EA		
1-6	Gas Valve Adjustment	13	EA		
1-7	Manhole Adjustment	11	EA		
1-8	6' Chain Link Fence	50	LF		
1-9	20' Wide 6' Chain Link Fence Gate (Double 10')	1	EA		
1-10	Water Valve Adjustment	4	EA		
1-11	4" Water Line Adjustment	1	LS		
1-12	12" Water Line Adjustment	1	LS		
1-13	Water Service Adjustments	1	LS		
1-14	Earthwork, Cut & Fill	1	LS		
1-15	Remove and Replace Unsuitable Materials	1000	CY		
1-16	Remove & Replace Standard and/or Brick Mailboxes with FDOT Approved Heavy Plastic Mailbox with Rear Door and Post	7	EA		
1-17	Establish, quantify, and submit an approved erosion control plan prepared by a certified technician (Must include Implementation of Plans, Installation and Replacement, NOI and NOT).	1	LS		
1-18	6" Concrete Lateral Patch, Per County Specifications	45	SY		
1-19	Asphalt Lateral Patch	1	LS		
1-20	Mill Existing Asphalt	11824	SY		
1-21	Signing and Pavement Markings. Must include Implementation of Plans, Approved Layout, installation of temporary and permanent striping, temporary and permanent RPM's, road signs, wheel stops, etc. This bid item is all inclusive of items identified on the plans or as required to facilitate signing and pavement marking needs.	1	LS		
1-22	Signalization. (Including but not limited to removal/replacement/installation of pedestrian crossings). This bid item is all inclusive of items identified on the plans or as required to facilitate signalization needs.	1	LS		
1-23	1.5" SP 12.5 Asphalt Driveway w/6" Stabilized Subgrade	27	SY		
1-24	2" SP 12.5 Asphalt, 8" Graded Aggregate Base, and 12" Stabilized Subgrade	4059	SY		
1-25	4.0" FDOT Type SP 12.5 Asphalt	20975	SY		
1-26	4" Type B 12.5 Base Course <u>OR</u> Optional 6" Graded Aggregate Base (Widening and Taper Construction) and 12" Stabilized Subgrade	9151	SY		
1-27	Type F Curb, to include Tapers/Transitions	336	LF		
1-28	6" Thick Concrete Driveway w/4" Stabilized Subgrade	108	SY		
1-29	Grass Ditch / Swale Grading	4340	LF		
1-30	6' Concrete Sidewalk	114	LF		
1-31	5' Concrete Sidewalk	129	LF		
1-32	Curb Ramp (Includes Detectable Warning Mat)	4	EA		
1-33	24" x 38" ERCP Pipe	46	LF		
1-34	19" x 30" ERCP Pipe	94	LF		
1-35	14" x 23" ERCP Pipe	310	LF		
1-36	18" RCP Pipe	16	LF		
1-37	18" HDPE Pipe	417	LF		
1-38	30" RCP Pipe	164	LF		
1-39	24" HDPE Pipe	400	LF		
1-40	Type D Inlet w/bottom and traversable slot(s)	3	EA		
1-41	Type V Inlet w/bottom	2	EA		
1-42	Type 2 Curb Inlet w/bottom	2	EA		
1-43	Junction Box w/5'x8" bottom	1	EA		

ADDENDUM #5 BID TAB

PD 16-17.010 MUSCOGEE ROAD (CR297A to US29) WIDENING AND DRAINAGE IMPROVEMENTS

1-44	Conflict Structure	2	EA		
1-45	18" Depth Rip Rap Rubble w/4" Bedding Stone and Geotextile	30	SY		
1-46	Waterproof Jobsite Storage Board Container/Tube for Project Information, Permits, SWPPP Plans, Etc.)	1	EA		
1-47	Concrete Flume	1	EA		
1-48	Adjust Inlet	1	EA		
1-49	Modify Inlet - Install Slot	1	EA		
1-50	14" x 23" Mitered End Section (Single Pipe)	6	EA		
1-51	19" x 30" Mitered End Section (Single Pipe)	3	EA		
1-52	30" Double Straight Concrete Endwall	1	EA		
1-53	Concrete Collar / Grout Connection to Existing Pipe	2	EA		
1-54	Sod, Pinned (Must match existing sod type)	14000	SY		

Bid Tab 1 Total = \$

Bid 2 - US 29 Signal Improvements (Morris, Muscogee, Tree)

Bid Item No.	Bid Item Description	Quantity	Unit	Unit Price	Extension
2-1	Mobilization	1	LS		
2-2	Maintenance Of Traffic	1	LS		
2-3	Conduit (Open Trench)	45	LF		
2-4	Pull & Splice Box (13" X 24" - Cover Size)	5	EA		
2-5	Electrical Power Service (Overhead) (No Meter)	2	AS		
2-6	Electrical Power Service (Remove) (Overhead)	2	AS		
2-7	Electrical Service Wire	230	LF		
2-8	Electrical Service Wire (Remove)	257	LF		
2-9	Electrical Service Disconnect (Pole Mount)	2	EA		
2-10	Electrical Service Disconnect (Remove) (Pole To Remain)	2	EA		
2-11	Prestressed Concrete Pole (Type P-11 Service Pole)	2	EA		
2-12	Vehicle Detection System - Video (Cabinet Equipment)	3	EA		
2-13	Vehicle Detection System - Video (Above Ground Equipment)	3	EA		
2-14	Traffic Controller Assembly (Atc) (None)	1	AS		
2-15	Traffic Controller Assembly (Atc) (One Preemption)	1	AS		
2-16	Traffic Controller Assembly (Modify)	1	AS		
2-17	Traffic Controller Assembly (Remove Controller & Cabinet)	2	AS		
2-18	Traffic Controller Without Cabinet (2070)	1	EA		
2-19	Managed Field Ethernet Switch	3	EA		
2-20	Wireless Communication Device (Ethernet Subscriber Unit)	6	EA		

Bid Tab 2 Total = \$

Bid 3 - Muscogee Road Pedestrian Access Route

Bid Item No.	Bid Item Description	Quantity	Unit	Unit Price	Extension
3-1	Design-Build a Pedestrian Access Route, see Scope of Work for additional information	1	LS		

Bid Tab 3 Total = \$

Project Total = \$