

Bauer Road Paved Shoulders

02/27/2019



Location	Length	Const Cost	CEI Cost	Funding Source	
Between Gulf Beach Highway & Sorrento Road	3,100 ft	\$443,970	\$46,302	FDOT LAP	\$ 428,381
				LOST	\$ 61,891

District 2

Bauer Road Shoulder Widening project will primarily consist of the addition of a 5' paved shoulder on the east and west sides of Bauer Road from Gulf Beach Highway to the south approach of the existing bridge for a length of approximately .5 miles. The project will also include the installation of curb cut ramps at Gulf Beach Highway, shoulder grading and sodding for the length of the project, minor utility adjustments and modifications to existing side streets and driveways to tie into the newly constructed paved shoulder.