





Location	Length	Const. Cost	CEI Cost	Funding Source	
	2,600 LF	\$1.2 Million	\$136K	FDOT LAP	\$ 531K
between the Jackson Creek Bridge/Culvert and				LOST	\$ 805K
Jackson Street					



This project involves the construction of sidewalk and drainage improvements along the eastern right-of-way of CR 295A (North Old Corry Field Road), between the Jackson Creek Bridge/Culvert and CR 298A (West Jackson Street). The intent of the drainage improvements is to replace the existing roadside open ditch and side drain system with a new roadside closed inlet and pipe system.

The project will consist construction of shallow roadside swales, ditch bottom and curb inlets, approximately 2,600 LF of sidewalk, curb and gutter, and new driveways. The project will also include the relocation/installation of a 6" water main and appurtenances.