



Board of County Commissioners • Escambia County, Florida

Paul R. Nobles/Purchasing Manager
Office of Purchasing

January 5, 2018

To: All Known Prospective Bidders

ADDENDUM NUMBER 3:

Re: PD 17-18.012 4-H Multipurpose Livestock Facility

All:

We recently sent you an Invitation to Bid on the above-mentioned specification.

This Addendum Number 3 provides for the updates which follow on the next page.

This Addendum Number 3 is furnished to all known prospective bidders. Please sign and return one copy of this Addendum, with original signature, with your bid as an acknowledgement of your having received same. You may photo copy this form for your records.

Sincerely,

A handwritten signature in blue ink, appearing to read "Jeffrey Lovingood", is written over a blue circular stamp.

Jeffrey Lovingood
Purchasing Specialist

Acknowledgement of Receipt of Addendum:

SIGNED: _____

COMPANY: _____

JDL

Question 1: The yard hydrants shown on sheet E102 can't be located there because that location will be taken by downspout adaptors as shown on sheet A104 and revised C401.

Answer 1: *The wall hydrants on E102 are on the inside face of the column. The downspouts are on the outside face.*

Question 2: Concerning the shade that is reference in Addendum 2, there are no details regarding size or location, and nothing to indicate what the labor might be to install it.

Answer 2: *Enclosed with this addendum is a quote from Gothic Arch Greenhouses that identifies the sizes and components of the shade cloth system. Detail C/A104 shows the location of the shade cloth, hardware, and tracks.*

Question 3: The plans call for vented ridge while specs call for 10' ridge ventilators. Which is correct?

Answer 3: *The vented ridge shown on the plans is correct.*

Question 4: Plans show exposed fastener screw down roof profile, while specs call for both standing seam and exposed fastener screw down roof panels.

Answer 4: *The exposed fastener screw down roof shown on the plans is correct.*

Question 5: Is there a weathertightness warranty for exposed fastener screwing down the roof?

Answer 5: *Please delete specification Section 13341, Item 1.6B.*

Question 6: Is the roof insulation shown under roof panels for the main building or only required at the enclosed area?

Answer 6: *The roof insulation shown under roof panels is required throughout the building, not just under enclosed areas.*

Question 7: Dektite EPDM pipe flashing is specified. Can steel crick at VTR be omitted?

Answer 7: *The steel cricket at VTR can be eliminated.*

Question 8: Detail 3/A104 shows metal wall panels at column line 1 inside face of wall behind the plywood. Is this correct?

Answer 8: *½" plywood on both inside and outside faces of enclosed areas are called for in both details 2 & 3 of A104. This is correct.*

Question 9: Is there a panel face on the back wall on 3/A102?

Answer 9: *No panel face is called for on the inside face of this wall.*

Question 10: Do studs frame the wall on 3/A104 behind the purlin line?

Answer 10: *The upper portions of exterior walls of enclosed areas are framed with metal building wall girts.*

Question 11: Is door 001A and 002A insulated or not? Section 3/A104 shows that it is, but the door schedule does not.

Answer 11: *The sectional door is insulated as called for in specification section 08360, sectional doors item 2.2.A.1.d.*

Question 12: Are we installing deadmen to keep the two (2) 7,000-gallon tanks shown on sheet C301 from floating when we have high amounts of rainfall?

Answer 12: *The design calls for the tanks to be installed at a minimum depth of five (5) feet. Calculations show the weight of the soil above the tank should be enough to counteract the anticipated buoyancy uplift.*

Question 13: What is the surface for the parking spaces?

Answer 13: *The HCAP parking stall is concrete per detail 2 on C401. The other delineated stalls will be just grass parking.*

-- End Addendum Number 3 --



P. O. Box 1564 Mobile, AL 36633
 Phone: 1-800-531-4769 Fax: 251-471-5465
 E-mail: gothicarch@comcast.net
<http://www.gothicarchgreenhouses.com>

Quote # JS121736B

Date:	21-Dec-17
Sales Rep:	Jennifer Sellers
Payment Terms:	Upon Order
Quote Valid:	30 Days

SHIP TO:
Mike Marshall
Sam Marshall Architecture
325 S Palafox Street
Pensacola, FL 32502
(850)433-7842
mike@sammarshallarch.com

BILL TO:

Description	Unit Price	UOM	Quantity	Total
10'4" x 48' Manual Roll- Up Curtain System • 2 each - 1 on each sidewall	\$1,198.000	Set	1	\$1,198.00
System Includes: <ul style="list-style-type: none"> • Wire-Lock Base Extrusion • Side Clasp Roll-up Bar, 2" OD with Wirelock Groove in side. Includes splice & Tek screws • Zig-Zag Wire insert • Wind control AND gear guide pipe at operator ends • Wind Post - Bracket assembly w/ top & bottom brackets and 1.315" x 12' pipe & Tek screws • Gear Crank 13:1 gear box w/ 4 guide wheels & internal brake and crank input loop • Roll Bar Adapter 1/2" square shaft, to fit SCRB aluminum roll-bar • Crank Handle 72" long 				
50% White Shade Cloth • 2 Each @ 12' x 50'	\$0.24	SF	1200	\$288.00
				\$0.00
				\$0.00
Lead Time Approximately 2 - 3 Weeks				
Term: Return of Merchandise: A 15% cancellation fee may be applied to orders cancelled within 10 days of order. A 20% cancellation fee may be applied to orders cancelled after 10 days Freight: Customer is responsible for the offloading of all material from truck. Lift gate option is available for attritional cost. (Please inquire with your sales representative for cost) Sales Tax: Sales tax will apply to all orders originating in the state of Alabama unless proof of tax exemption is submitted with order.	Sub-Total			\$1,486.00
	Sales Tax			\$0.00
	Freight			\$230.00
	Total			\$1,716.00