DRC Chairman Signatu

### SITE CONSTRUCTION DOCUMENTS

## FOR

SITE ADDRESS: 8448 N. PALAFOX STREET PROPERTY REFERENCE NUMBER: 21-1S-30-1101-003-068, PREPARED FOR

**ENSLEY CRA** 


221 PALAFOX PLAZA, SUITE 420 PENSACOLA, FLORIDA 32502

# **ENSLEY GATEWAY**

- 100070185

ENSLEY GATEWAY

**PROJECT** LOCATION



Approved ESCAMBIA COUNTY DRC PLAN REVIEW

This document has been reviewed in accordance with the requirements

of applicable Escambia County Regulations and Ordinances, and does

Order (DO) must be obtained through the Development Review Process prior to the commencement of construction. This DO approval does not

constitute approval by any other agency. All additional state/federal permits shall be provided to the county prior to approval of a final plat or the issuance of state/federal permits shall be provided to the county prior

to approval of a final plat or the issuance of a building permit.

not in any way relieve the submitting Architect, Engineer, Surveyor or other signatory from responsibility of details as drawn. A Development

1-6-33

**ESCAMBIA COUNTY SEC. 21 T1S R30W** 

VICINITY MAP

N.T.S

BOARD OF COUNTY COMMISSIONERS - CRA BOARD OF DIRECTORS

DISTRICT 1 JEFF BERGOSH (VICE-CHAIRMAN)

DOUG UNDERHILL LUMON MAY DISTRICT 3

DISTRICT 4 ROBERT BENDER (CHAIRMAN)

DISTRICT 5 STEVEN BARRY

### Index of Sheets

Sheet #	Sheet Title	Issued Date	Rev.	Revised Date
C0.00	Cover Sheet	2021//	-	//
C0,01	General Notes	2021//	-	//
C0.02	General Notes	2021//	_	//
l of l	Topographic Survey	2021//	_	//
C1.01	Site Plan	2021//	-	//
C2.01	Grading & Drainage Plan	2021//	_ ·	//
C3.01	Utility Adjustments	2021//	- "	//
C8.01	Hardscape Details	2021//		//
C8.02	Hardscape & Drainage Details	2021//	- "	//
C8,03	Drainage Details	2021//	-	//
C8,04	Erosion Control Details	2021//	-	//
C9.01	Storm Water Pollution Prevention Plan	2021//	-	//
C9.02	Erosion Control Plan	2021//		//
L1.01	Landscape Plan	2021//	-	//
L2.01	Landscape & Irrigation Notes	2021//	-	//
L2.02	Landscape Schedule & Details	2021//		//

**ATKINS** 

PENSACOLA, FLORIDA 32504 PHONE NO. 850.478,9844 CERTIFICATE OF AUTHORIZATION NO. 24

October 2021

THIS DOCUMENT HAS BEEN DIGITAL SIGNED AND SEALED BY William H Telford 2021.11.02 10:45:15

ESIGNED BY: DMH снескед ну: ЈВР APPROVED BY: WHT 100070185

**FINAL PLANS** NOT RELEASED FOR CONSTRUCTION

### GENERAL NOTES:

- ALL SITE WORK MATERIALS AND CONSTRUCTION METHODS SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE FLORIDA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, UNLESS NOTED OTHERWISE IN THE CONSTRUCTION DOCUMENTS.
- CONTRACTOR SHALL ADHERE TO RULES CONCERNING SAFETY OF ESCAMBIA COUNTY, AND OTHER AUTHORITIES HAVING JURISDICTION.
- THE CONTRACTOR IS REQUIRED TO VISIT THE SITE AND FAMILIARIZE HIMSELF WITH THE PROJECT PRIOR TO BIDDING.
- AT THE PRE-CONSTRUCTION MEETING THE CONTRACTOR SHALL DESIGNATE A REPRESENTATIVE WHO SHALL BE CAPABLE OF BEING REACHED 24 HOURS A DAY, 7 DAYS A WEEK.
- HORIZONTAL AND VERTICAL CONTROL HAS BEEN PROVIDED FOR THE CONTRACTOR PER THE SURVEY INFORMATION PROVIDED ON THE SHEETS INCLUDED IN THIS SET. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING THE SURVEY CONTROLS THROUGHOUT THE DURATION OF CONSTRUCTION AND/OR SETTING ADDITIONAL CONTROLS IF REQUIRED DUE TO MEANS AND METHODS FOR CONSTRUCTION OF THE IMPROVEMENTS.
- CONTRACTOR IS TO NOTIFY ESCAMBIA COUNTY AND ENGINEER OF RECORD 72 HOURS PRIOR TO BEGINNING CONSTRUCTION.
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE PLANS AND WRITTEN SPECIFICATIONS, NO SUBSTITUTIONS SHALL BE MADE WITHOUT PRIOR WRITTEN APPROVAL BY THE OWNER OR THE
- EROSION AND SEDIMENTATION CONTROLS WILL BE PROVIDED AND MAINTAINED BY THE CONTRACTOR 8. AT ALL TIMES AS PER COUNTY AND STATE AGENCY REQUIREMENTS
- THE CONTRACTOR SHALL ARRANGE WITH THE COUNTY AN INSPECTION OF THE EROSION AND SEDIMENT CONTROL DEVICES PRIOR TO CONSTRUCTION, UNDERGROUND DRAINAGE STRUCTURES PRIOR TO BURIAL, AND THE FINAL INSPECTION OF THE ENTIRE PROJECT UPON COMPLETION
- 10. THE CONTRACTOR SHALL TAKE WHATEVER STEPS NECESSARY TO PREVENT AND CONTROL EROSION AND SEDIMENTATION. MEASURES FOR EROSION CONTROL DEPICTED IN THE PLANS ARE MINIMUM SUGGESTIONS ONLY AND DO NOT RELIEVE THE CONTRACTOR OF ANY RESPONSIBILITY TO PREVENT AND CONTROL EROSION AND SEDIMENTATION. THESE CONTROLS SHALL BE ADDED TO OR REINFORCED AS CONDITIONS DICTATE.
- 11. CLEAR AND GRUB ONLY AS NECESSARY TO COMPLETE NEW CONSTRUCTION.
- 12. BURNING SHALL NOT BE PERMITTED ONSITE.
- 13. SEDIMENT SHALL BE RETAINED ON THE SITE OF DEVELOPMENT. REMOVE SEDIMENT AT APPROPRIATE TIME AND PRIOR TO THE END OF CONSTRUCTION.
- FALL FROM TRUCKS HAULING MATERIAL TO OR AWAY FROM SITE, INCLUDING MATERIAL FALLING FROM TIRES. SHOULD THE STATE OR COUNTY REQUIRE SWEEPING AND CLEANING OF ROADWAYS DUE TO THE ABOVE, THE SAME SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ANY FINES DUE TO THE ABOVE
- 15. SHOULD THE CONTROL OF DUST AT THE SITE BE NECESSARY, THE SITE WILL BE SPRINKLED UNTIL THE SURFACE IS WET, TEMPORARY VEGETATION COVER SHALL BE ESTABLISHED OR MULCH SHALL BE APPLIED IN ACCORDANCE WITH STANDARDS FOR FROSION CONTROL.
- 16. ALL SOIL WASHED, DROPPED, SPILLED OR TRACKED OUTSIDE THE LIMITS OF DISTURBANCE OR ONTO PUBLIC RIGHT-OF-WAY WILL BE REMOVED IMMEDIATELY.
- 17. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY EROSION OR SEDIMENTATION THAT MAY OCCUR BELOW STORMWATER OUTFALLS OR OFF SITE AS A RESULT OF CONSTRUCTION OF THE
- 18. ALL SOIL STOCKPILES ARE TO BE TEMPORARILY STABILIZED IN ACCORDANCE WITH SOIL EROSION AND SEDIMENT CONTROL NOTE NUMBER 16 (ABOVE).
- 19. THE SITE SHALL AT ALL TIMES BE GRADED AND MAINTAINED SUCH THAT ALL STORM WATER RUNOFF IS DIVERTED TO SOIL EROSION AND SEDIMENT CONTROL FACILITIES.
- 20. ALL SEDIMENTATION STRUCTURES SHALL BE INSPECTED AND MAINTAINED REGULARLY.
- 21. CONTRACTOR SHALL NOTIFY SUNSHINE 811 TWO (2) FULL BUSINESS DAYS IN ADVANCE PRIOR TO DIGGING WITHIN R/W: 1-800-432-4770.
- CONTRACTOR TO COORDINATE WITH LOCAL UTILITY COMPANIES FOR REMOVAL AND RELOCATION OF 42. EXISTING UTILITY POLES, AERIAL LINES, WATER LINES, GAS LINES, AND OTHER UTILITIES AS
- 23. THESE DRAWINGS REPRESENT KNOWN STRUCTURES AND UTILITIES LOCATED IN THE PROJECT AREA. THE CONTRACTOR IS CAUTIONED THAT OTHER STRUCTURES AND UTILITIES, ABOVE OR BELOW GROUND, MAY BE ENCOUNTERED DURING THE COURSE OF THE PROJECT. THE CONTRACTOR SHOULD NOTIFY THE PROJECT ENGINEER IMMEDIATELY UPON ENCOUNTERING ANY UNEXPECTED STRUCTURE, UTILITY LINE, OR OTHER UNUSUAL CONDITION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE EXACT LOCATION AND DEPTH OF EXISTING UTILITIES AND TO DETERMINE IF OTHER UTILITIES WILL BE ENCOUNTERED DURING THE COURSE OF THE WORK AND TAKE WHATEVER STEPS NECESSARY TO PROVIDE FOR THEIR PROTECTION.
- FAILURE OF THE PLANS TO SHOW THE EXISTENCE OF ANY UNDERGROUND UTILITY, STRUCTURES, 24. ETC., SHALL NOT RELIEVE THE CONTRACTOR FROM THE RESPONSIBILITY OF LOCATING, PRESERVING AND PROTECTING SAID UTILITY OR STRUCTURE
- ADEQUATE PROVISIONS SHALL BE MADE FOR FLOW OF SEWERS, DRAINS, AND WATER COURSES ENCOUNTERED DURING CONSTRUCTION. ALL EARTHWORK SHALL BE ACCOMPLISHED TO KEEP WATER FLOW AND DRAINAGE WITHIN THE CONFINES OF THE EXISTING CURBS.
- 26. THE CONTRACTOR SHALL COMPLY WITH ANY TESTING REQUIRED BY THE LOCAL GOVERNING AGENCY IN ADDITION TO THE TESTING REQUIREMENTS OUTLINED IN THE CONSTRUCTION DOCUMENTS. TESTING SHALL BE PAID FOR BY THE CONTRACTOR AND THE COUNTY SHALL APPROVE OF TESTING LAB CHOSEN. CONTRACTOR SHALL COORDINATE AND ASSIST TESTING LABORATORIES WITH TESTING. ANY NECESSARY RE-TESTING SHALL BE PAID FOR BY THE CONTRACTOR.

- 27. ALL DEMOLITION MATERIALS AND EXCESS SOIL MATERIAL EXCAVATED AND NOT USED AS FILL SHALL 46. BE REMOVED FROM THE SITE AND DISPOSED OF OFF-SITE IN A LEGAL AND RESPONSIBLE MANNER BY THE CONTRACTOR, CONCRETE AND ANY OTHER DEBRIS SHALL BE REMOVED AND HAULED OFF THE SAME DAY
- 28. THE CONTRACTOR SHALL NOTIFY THE COUNTY OF ANY CONFLICTS BETWEEN VENDOR DRAWINGS, EXISTING CONDITIONS. AND THE CONSTRUCTION DOCUMENTS
- ALL WORK SHALL BE CONFINED TO WITHIN THE PROJECT R/W OR PROPERTY LIMITS. ALL REMOVAL OF DEBRIS AND DELIVERY OF PLANT MATERIALS AND SOILS BY HEAVY VEHICLES SHALL BE DONE IN SUCH A WAY AS TO PROTECT THE EXISTING CURB AND GUTTER FROM CRACKING AND
- 30. CONTRACTOR SHALL COORDINATE HIS WORK AND COOPERATE WITH OTHER CONTRACTORS WORKING AROUND THE PROJECT AREA
- 31. SHOULD CONTRACTOR ELECT TO USE ONSITE EXCAVATION AS FILL, HE IS CAUTIONED NO ADDITIONAL TIME OR COST WILL BE ALLOWED SHOULD MATERIAL BECOME WET AND UNWORKABLE. F NECESSARY, CONTRACTOR WILL BE REQUIRED TO BRING IN OFFSITE FILL MATERIAL MEETING
- THE CONTRACTOR SHALL FLUSH AND CLEAN ALL EXISTING AND NEW STORMWATER PIPES AND STRUCTURES IMPACTED BY THE PROJECT AT END OF CONSTRUCTION AFTER ALL DISTURBED AREAS HAVE REEN STABILIZED.
- 33. NO SITE WORK ACTIVITIES SHALL TAKE PLACE WITHOUT COUNTY SITE REVIEW/APPROVAL OF PROPOSED EROSION CONTROL MEASURES, AND ADVANCED NOTIFICATION OF THE REQUESTED INSPECTION IS REQUIRED.
- 34. THE CONTRACTOR SHALL PROVIDE CONTINUED MAINTENANCE OF TRAFFIC TO PUBLIC/PRIVATE PROPERTY IN A SAFE AND FEASIBLE MANNER IN AREAS IMPACTED BY THE PROJECT CONSTRUCTION UNTIL ALL SUCH ACCESS CAN BE RESTORED PERMANENTLY. ALL MAINTENANCE OF TRAFFIC PLANS MUST BE SUBMITTED TO THE COUNTY FOR APPROVAL A MINIMUM OF FIVE (5) CALENDAR DAYS PRIOR TO IMPLEMENTING ANY PROPOSED MEASURES AND COORDINATION WITH IMPACTED RESIDENTS AND/OR PROPERTY OWNERS (OR OWNER REPRESENTATIVES) MAY BE REQUIRED OF THE CONTRACTOR AS PART OF THE MAINTENANCE OF TRAFFIC PLAN, ALL COST FOR SUCH REVISED. MAINTENANCE OF TRAFFIC PLANS AND MEASURES SHALL BE COVERED/INCLUDED IN THE
- 35. THE CONTRACTOR SHALL PLACE AND MAINTAIN ADEQUATE BARRICADES, CONSTRUCTION SIGNS, FLASHING LIGHTS, AND GUARDS DURING PROGRESS OF CONSTRUCTION WORK AND UNTIL IT IS SAFE FOR BOTH PEDESTRIAN AND VEHICULAR TRAFFIC
- 36. THE CONTRACTOR SHALL NOT BLOCK OR OBSTRUCT ANY ROADS OR DRIVES WITHOUT FIRST RECEIVING PERMISSION FROM THE COUNTY TO DO SO.
- PROPERTY OBSTRUCTIONS WHICH ARE TO REMAIN IN PLACE, SUCH AS SEWER, DRAINS, WATER OR GAS PIPES, ELECTRICAL, CONDUITS, POLES, ETC., ARE TO BE CAREFULLY PROTECTED AND ARE NOT TO BE DISPLACED UNLESS NOTED ON PLANS.
- 38. CONTRACTOR SHALL CLEANUP ENTIRE SITE INCLUDING STAGING AREAS AT LEAST TWO TIMES PER WEEK. THIS SHALL INCLUDE LOCATING TRASH/SCRAP RECEPTACLES AT APPROPRIATE LOCATIONS AROUND THE SITE. CONTRACTOR SHALL PICK UP ALL ROCKS, METAL, PIPE, NAILS, NUTS, BOLTS BOARDS, PAPER, TRASH, ETC., AT LEAST TWICE A WEEK AT NO ADDITIONAL COST TO THE COUNTY
- CONTRACTOR SHALL RESTORE ALL STAGING AREAS TO AS GOOD AS OR BETTER CONDITION THAN EXISTED PRIOR TO CONSTRUCTION. THIS INCLUDES IRRIGATION AND SOD REPLACEMENT IF NECESSARY, ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 20 DAYS, AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, WILL IMMEDIATELY RECEIVE A TEMPORARY SEEDING. IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER, THE DISTURBED AREAS WILL BE MULCHED WITH STRAW, OR EQUIVALENT MATERIAL, AT A RATE OF TWO (2) TONS PER ACRE
- 40. ANY AREAS USED FOR THE CONTRACTOR'S STAGING, INCLUDING BUT NOT LIMITED TO, TEMPORARY STORAGE OF STOCKPILED MATERIALS (E.G. CRUSHED STONE, QUARRY PROCESS STONE, SELECT FILL, EXCAVATED MATERIALS, ETC.) SHALL BE ENTIRELY PROTECTED BY A SILT FENCE ALONG THE LOW ELEVATION SIDE TO CONTROL SEDIMENT RUNOFF.
- 41. ALL ITEMS OF PRIVATE PROPERTY LOCATED WITHIN THE COUNTY R/W SHALL BE PROTECTED AND/OR RELOCATED TO THE COUNTY'S SATISFACTION AS PART OF THE PROJECT, SUCH ITEMS SHALL INCLUDE, BUT NOT BE LIMITED TO, IRRIGATION SYSTEMS, MAIL BOXES, SIGNS, LANDSCAPE, PLANTER BEDS/BOXES, YARD DRAINS, BENCHES, ETC., AND SHALL BE COORDINATED AND ADDRESSED IN A TIMELY AND PROFESSIONAL MANNER. ITEMS REQUIRING REPLACEMENT SHALL BE OF EQUAL OR BETTER QUALITY.
- THE LOCATION OF THE CONTRACTOR'S MATERIAL AND EQUIPMENT LAY-DOWN AREA SHALL BE APPROVED BY THE COUNTY PRIOR TO SECURING SUCH ARRANGEMENTS, AS DIRECTLY RELATED TO THE PROJECT. THE LAY-DOWN AREA SHALL BE COMPLETELY SECURED UTILIZING TEMPORARY 6' CHAIN-LINK CONSTRUCTION FENCING WITH LOCKED GATES AND PROPER FROSION CONTROL BARRIER, AS NECESSARY, AND SHALL BE KEPT IN A NEAT AND UNIFORM MANNER AT ALL TIMES, AS DETERMINED BY THE COUNTY, ONLY MATERIALS AND EQUIPMENT DIRECTLY REQUIRED TO FACILITATE THE CURRENT PROGRESS OF THE PROJECT CONSTRUCTION SHALL BE STORED IN THE LAY-DOWN AREA AT ANY GIVEN TIME AND ALL OTHER MATERIALS AND EQUIPMENT SHALL BE IMMEDIATELY REMOVED AT THE REQUEST OF THE CITY. CONTRACTOR IS RESPONSIBLE FOR LAY-DOWN AREAS.
- 43. THE CONTRACTOR'S PROPOSED SCHEDULE OF WORK FOR BOTH STANDARD (M-F, 7AM-4PM) AND NON-STANDARD HOURS SHALL BE REVIEWED AND APPROVED BY THE COUNTY AND SUBMITTED FOR REVIEW IN WRITING A MINIMUM OF SEVEN (7) CALENDAR DAYS PRIOR TO COMMENCEMENT OF THE PROPOSED WORK, THE COUNTY RESERVES THE RIGHT TO DENY WORK ON ANY PROPOSED DAY IF CERTAIN PUBLIC EVENTS, ENVIRONMENTAL CONDITIONS, NEIGHBORHOOD CIRCUMSTANCES, ETC., REQUIRE SUCH ACTION. THE CONTRACTOR SHALL ACKNOWLEDGE ULTIMATE RESPONSIBILITY OF THE JOB SITE DURING CONSTRUCTION (24 HRS/DAY) FOR THE ENTIRE DURATION OF THE PROJECT. REGARDLESS OF APPROVED WORK SCHEDULES AND HOURS OF OPERATION.
- THE CONTRACTOR SHALL SUBMIT A POST-CONSTRUCTION CERTIFICATION AND REPRODUCIBLE RECORD DRAWINGS TO THE COUNTY PRIOR TO INSPECTION AND ACCEPTANCE. THE RECORD DRAWINGS SHALL BE PREPARED AND CERTIFIED BY A FLORIDA PROFESSIONAL SURVEYOR.
- BENCHMARK ELEVATIONS SHOWN ON THE PLANS ARE NORTH AMERICAN VERTICAL DATUM OF 1983 (NAVD 83).

ALL SURVEY INFORMATION WAS OBTAINED FROM A LICENSED FLORIDA PROFESSIONAL SURVEYOR AND MAPPER AND UTILIZED AS SUPPORTING DATA IN THE PRODUCTION OF DESIGN PLANS AND FOR CONSTRUCTION ON SUBJECT PROJECT. THE PROFESSIONAL SURVEYOR AND MAPPER OF RECORD IS

JOSEPH BARRETT, P.S.M. P.S.M. NO: 6260 ENGINEERING DEPARTMENT, ESCAMBIA COUNTY, FLORIDA 3363 W. PARK PLACE PENSACOLA, FLORIDA 32505 CERTIFICATE OF AUTHORIZATION NO: LB 7918

- 47. THE LOCATION(S) OF THE UTILITIES SHOWN IN THE PLANS (INCLUDING THOSE DESIGNATED VV, Vh, AND VVh) ARE BASED ON LIMITED INVESTIGATION TECHNIQUES AND SHOULD BE CONSIDERED APPROXIMATE ONLY. THE VERIFIED LOCATIONS/ELEVATIONS APPLY ONLY AT THE POINTS SHOWN, INTERPOLATIONS BETWEEN THESE POINTS HAVE NOT BEEN VERIFIED.
- WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. THE CONTRACTOR SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB. THE OWNER'S REPRESENTATIVE SHALL BE NOTIFIED OF ANY VARIATION FROM THE DIMENSIONS AND CONDITIONS SHOWN ON THE PLANS.
- THE CONTRACTOR SHALL NOT BRING ANY HAZARDOUS MATERIALS ONTO THE PROJECT SITE 49. SHOULD THE CONTRACTOR REQUIRE SUCH FOR PERFORMING CONTRACTED WORK, THE CONTRACTOR SHALL REQUEST, IN WRITING, PERMISSION FROM THE OWNER'S REPRESENTATIVE IN ADVANCE. THE CONTRACTOR SHALL PROVIDE THE OWNER'S REPRESENTATIVE WITH A COPY OF THE MATERIAL SAFETY DATA SHEET (MSDS) FOR EACH HAZARDOUS MATERIAL PROPOSED FOR USE. THE OWNER'S REPRESENTATIVE SHALL COORDINATE WITH THE COUNTY PRIOR TO ISSUING WRITTEN APPROVAL TO THE CONTRACTOR. BECAUSE STATE LAW DOES NOT TREAT PETROLEUM PRODUCTS THAT ARE PROPERLY CONTAINERIZED AND INTENDED FOR EQUIPMENT USE AS A HAZARDOUS MATERIAL, SUCH PRODUCTS DO NOT NEED A MSDS SUBMITTAL. ANY KNOWN OR SUSPECTED HAZARDOUS MATERIAL FOUND ON THE PROJECT BY THE CONTRACTOR SHALL BE IMMEDIATELY REPORTED TO THE OWNER'S REPRESENTATIVE, WHO SHALL DIRECT THE CONTRACTOR TO PROTECT THE AREA OF KNOWN OR SUSPECTED CONTAMINATION FROM FURTHER ACCESS. THE OWNER'S REPRESENTATIVE IS TO NOTIFY THE COUNTY OF THE DISCOVERY, THE COUNTY WILL ARRANGE FOR INVESTIGATION. IDENTIFICATION AND REMEDIATION OF THE HAZARDOUS MATERIAL. THE CONTRACTOR SHALL NOT RETURN TO THE AREA OF CONTAMINATION UNTIL APPROVAL IS PROVIDED BY THE OWNER'S REPRESENTATIVE.
- 50. THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR ATTENDING A PRE-CONSTRUCTION MEETING DURING WHICH INSTALLATION SPECIFICATIONS, INSTALLATION REQUIREMENTS, SCHEDULES, AND MAINTENANCE REQUIREMENTS WILL BE DISCUSSED.

GATEN

THIS DOCUMENT HAS BEEN DIGITALLY SIGHED AND SEALED BY William H Telford 2021.11.02 10:45:56

-04'00'

48 HOURS

BEFORE YOU DIG

1-800-432-4770

AVOID DAMAGE TO

NDERGROUND FACILITIES

ATKIHS HORTH AMERICA, IHC., 482 S. KELLER ROAD ORLANDO, IT 32810 (407) 647-7275 CERTIFICATE OF AUTHORIZATION: 24 WILLIAM H. TELFORD, P.S. NO. 32067

No 32067 STATE OF STONAL

ENGINEER OF RECORD

WILLIAM II TELFORD

DRAWNBY; HIL CALL SUNSHINE ESIGNED BY: DMH

> CHECKED BY: 1747 APPROVED BY; WHT

10007018 C0.01

### SPECIAL NOTES:

1. CONTRACTOR SHALL NOTE THAT THE PROJECT IS A LUMP SUM PROJECT BUT SEPARATE UNIT COST FOR EACH BID ITEM ARE REQUIRED TO BE SUBMITTED IN THE BID.

- 1. CONTRACTOR IS TO INCLUDE ANY COSTS FOR TEMPORARY MEASURES AND SUPPORT TO ACCESS SITE IN THE COST FOR MOBILIZATION IN HIS BID. CONTRACTOR SHALL REPAIR ANY DAMAGE TO EXISTING FACILITIES TO THE SATISFACTION OF THE COUNTY AT NO ADDITIONAL COST.
- 2. CONTRACTOR IS TO INCLUDE COST OF WATER FOR PLANT ESTABLISHMENT AND MAINTENANCE OF LANDSCAPING AND GRASSING IN THE UNIT PRICE FOR LANDSCAPING.
- 3. PROTECTION OF EXISTING ELECTRICAL POLE(S), WILL BE INCLUDED IN THE COST FOR DEMOLITION.
- COST FOR ANY IMPORTED TOPSOIL OR AMENDMENTS TO EXISTING TOPSOIL ON SITE SHALL BE INCLUDED IN THE COST FOR SODDING/LANDSCAPING.

### ESCAMBIA COUNTY NOTES:

- > 1. THE PROJECT ENGINEER (ENGINEER OF RECORD) SHALL PROVIDE TO ESCAMBIA COUNTY "AS-BUILT" RECORD DRAWINGS FOR VERIFICATION AND APPROVAL BY ESCAMBIA COUNTY ONE WEEK PRIOR TO REQUESTING A FINAL INSPECTION AND CERTIFICATE OF OCCUPANCY, OR PROVIDE "AS-BUILT" CERTIFICATION THAT THE PROJECT CONSTRUCTION ADHERES TO THE PERMITTED PLANS AND SPECIFICATIONS. THE "AS-BUILT CERTIFICATION OR THE "AS-BUILT" RECORD DRAWINGS MUST BE SIGNED, SEALED AND DATED BY A REGISTERED FLORIDA PROFESSIONAL ENGINEER.
- ALL ASPECTS OF THE STORMWATER/DRAINAGE COMPONENTS AND/OR TRANSPORTATION COMPONENTS SHALL BE COMPLETED PRIOR TO ISSUANCE OF FINAL CERTIFICATE OF OCCUPANCY.
- NO DEVIATIONS OR REVISIONS FROM THESE PLANS BY THE CONTRACTOR SHALL BE ALLOWED WITHOUT PRIOR APPROVAL FROM BOTH THE DESIGN ENGINEER AND THE ESCAMBIA COUNTY. ANY DEVIATIONS MAY RESULT IN DELAYS IN OBTAINING A CERTIFICATE OF OCCUPANCY.
- 4. THE CONTRACTOR SHALL INSTALL PRIOR TO THE START OF CONSTRUCTION AND MAINTAIN DURING CONSTRUCTION ALL SEDIMENT CONTROL MEASURES AS REQUIRED TO RETAIN ALL SEDIMENTS ON THE SITE. IMPROPER SEDIMENT CONTROL MEASURES MAY RESULT IN CODE ENFORCEMENT VIOLATION.
- RETENTION/DETENTION AREAS SHALL BE SUBSTANTIALLY COMPLETE PRIOR TO ANY CONSTRUCTION ACTIVITIES THAT MAY INCREASE STORMWATER RUNOFF RATES. THE CONTRACTOR SHALL CONTROL STORMWATER DURING ALL PHASES OF CONSTRUCTION AND TAKE ADEQUATE MEASURES TO PREVENT THE EXCAVATED POND FROM BLINDING DUE TO SEDIMENTS.
- 6. ALL DISTURBED AREAS WHICH ARE NOT PAVED SHALL BE STABILIZED WITH SEEDING, FERTILIZER AND MULCH, HYDROSEED AND/OR SOD.
- 7. DEVELOPER/CONTRACTOR SHALL RESHAPE PER PLAN SPECIFICATIONS, CLEAN OUT ACCUMULATED SILT, AND STABILIZE RETENTION/DETENTION POND(S) AT THE END OF CONSTRUCTION WHEN ALL DISTURBED AREAS HAVE BEEN STABILIZED AND PRIOR TO REQUEST FOR INSPECTION.
- 8. CONTRACTOR SHALL MAINTAIN RECORD DRAWINGS DURING CONSTRUCTION WHICH SHOW "AS-BUILT" CONDITIONS OF ALL WORK INCLUDING PIPING, DRAINAGE STRUCTURES, TOPO OF POND(S), OUTLET STRUCTURES, DIMENSIONS, ELEVATIONS, GRADING ETC. RECORD DRAWINGS SHALL BE PROVIDED TO THE ENGINEER OF RECORD PRIOR TO REQUESTING FINAL INSPECTION.
- 9. THE OWNER OR HIS AGENT SHALL ARRANGE/SCHEDULE WITH THE COUNTY A FINAL INSPECTION OF THE DEVELOPMENT UPON COMPLETION AND ANY INTERMEDIATE INSPECTIONS AT (850) 595-3472. AS-BUILT CERTIFICATION IS REQUIRED PRIOR TO REQUEST FOR FINAL INSPECTION/APPROVAL
- ₹|>10. NOTIFY SUNSHINE UTILITIES 48 HOURS IN ADVANCE PRIOR TO DIGIING WITHIN R/W; 1-800-432-4770.
- 11. ANY DAMAGE TO EXISTING ROADS DURING CONSTRUCTION WILL BE REPAIRED BY THE DEVELOPER PRIOR TO FINAL "AS-BUILT" SIGN OFF FROM THE COUNTY.
- 212. THE SUBJECT PROPERTY AS SHOWN HEREON IS LOCATED IN FLOOD ZONE X, (MINIMUM RISK AREAS OUTSIDE THE 1-PERCENT AND .2-PERCENT-ANNUAL-CHANCE FLOODPLAINS. NO BFES OR BASE FLOOD DETHIS ARE SHOWN WITHIN THESE ZONES), AS DETERMINED FROM THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP OF ESCAMBIA COUNTY, FLORIDA, COMMUNITY 120080, FIRM MAP PANEL NUMBERS 12033C0295G, MAP REVISION DATED SEPTEMBER 29, 2006.

<b>Ensley Gateway Park</b>	
Escambia County	

### Hility Owners

Othity Owners						
Company	Contact Person	Contact Number	Email Address			
AT&T Florida (Distribution)	Tim Edgar	(850) 293-3780	te1810@att.com			
CenturyLink / Level 3 (National)	Jimmy Young	(352) 303-2430	james.young2@lumen.com			
Emerald Coast Utilities Authority (ECUA)	Brandon Knight	(850) 969-6650	brandon.knight@ecua.fl.gov			
Escambia County	Jim Hagon	(850) 595-3404	jlhagon@myescambia.com			
Gulf Power Company (Distribution)	Chad Swails	(850) 723-7852	chad.swails@nexteraenergy.com			
Pensacola Energy	Diane Moore	(850) 474-5319	dmoore@cityofpensacola.com			
Sprint Communications	Steve Thompson	(678) 852-2726	steve.r.thompson@t-mobile.com			

	APPROVED BY					
	BYTE	8/25/2021				
oment.	REVISIONS	REV 1 - DRC COMMENTS				
	NUMBER	∢				

NOTES GATEW

MH. TELL No 32067 STATE OF LORIDONAL EN

ENGINEER OF RECORD


WILLIAM H TELFORD FL# 32067


DRAWN BY: HIL ESIGNED BY: DMH CHECKED BY: TRP


APPROVED BY: WHT 100070185 DRAWING C0.02


THIS DOCUMENT HAS BEEN DIGITALLY SIGNED AND SEALED BY William H Telford 2021.11.02 10:46:24 -04'00'


ATRINS HORTH AMERICA, INC. 482 S. KELLER ROAD ORIAMOD, FL 32610 (401) 647-7215 CERTIFICATE OF AUTHORIZATION: 24 WILLIAM H. TELFORD, P.E. NO. 32067 48 HOURS BEFORE YOU DIG CALL SUNSHINE 1-800-432-4770 AVOID DAMAGE TO UNDERGROUND FACILITIES




























DIMENSIONS, MATERIALS AND REINFORCEMENT ARE BASED ON FDOT STANDARD PLANS INDEX 425-061 FOR A TYPE II CLOSED FLUME INLET, MODIFIED TO PROVIDE A CLOSED FLUME BOX WITH 7" RISE AND 2'-0" SPAN, ENDWALL EACH END AND OVERALL WALL LENGTH OF 21' FOR THE WEST SWALE CROSSING AND 18' FOR THE EAST SWALE CROSSING.

THIS DOCUMENT HAS BEEN DIGITALLY SIGNED AND SEALED BY William H Telford 2021.11.02 10:48:29 -04'00' ON THE DATE ADJACENT TO THE SEA

STONAL CONTRACTOR


HARDSCAPE & DRAINAGE DETAILS


ENSLEY GATEWAY


DESIGNED BY: DMH

снескей ву: ЈВР APPROVED BY: WHT


100070185 C8.02














### SPECIFIC APPLICATION

THIS METHOD OF INLET PROTECTION IS APPLICABLE AT CURB INLETS WHERE PONDING IN FRONT OF THE STRUCTURE IS NOT LIKELY TO CAUSE INCONVENIENCE OR DAMAGE TO ADJACENT STRUCTURES AND UNPROTECTED AREAS.












3. STAPLE FILTER MATERIAL TO





NOTE: INSTALL IN ACCORDANCE WITH SILT FENCE DETAIL, EXCEPT AS NOTED ABOVE.





C8.04

CONSTRUCTION ENTRANCE / EXIT PLAN VIEW

EROSION CONTROL DETAILS

ENSLEY GATEWAY

STATE O

DRAWN BY: HIL DESIGNED BY: DMH

снескео ву: ЈВР APPROVED BY: WHT

100070185 NUMBER DRAWING C8.04

1.0 SITE DESCRIPTION

1.A. NATURE OF CONSTRUCTION ACTIVITY:

THE PROJECT SITE IS THE VACANT LAND AT THE NE CORNER OF THE N. PALAFOX STREET AND E. JOHNSON AVENUE INTERSECTION IN ESCAMBIA COUNTY, FL. THIS PROJECT INVOLVES CONSTRUCTION OF SIDEWALKS, DRY ROCK BED SWALE, LANDSCAPE IMPROVEMENTS, AND RE-GRADING OF THE SITE.

THE MAIN CONSTRUCTION ITEMS TO BE ADDRESSED INCLUDE, BUT ARE NOT LIMITED TO THE FOLLOWING:

- SITE GRADING
- DRAINAGE IMPROVEMENTS
- LANDSCAPE IMPROVEMENTS

1,B SEQUENCE OF MAJOR SOIL DISTURBING ACTIVITIES:

MOST OF THE DISTURBANCE WILL BE AS A CONSEQUENCE OF NEW GRADING, SIDEWALKS, AND LANDSCAPE. A DETAILED SEQUENCE OF CONSTRUCTION FOR ALL CONSTRUCTION ACTIVITIES IS TO BE PROVIDED BY THE CONTRACTOR FOR ALL CONSTRUCTION ACTIVITIES DESCRIBED BELOW, THAT IS EQUAL

FOR EACH CONSTRUCTION PHASE, INSTALL PERIMETER CONTROLS AFTER CLEARING AND GRUBBING NECESSARY FOR INSTALLATION OF CONTROLS BUT BEFORE BEGINNING OTHER WORK FOR THE CONSTRUCTION PHASE. REMOVE PERIMETER CONTROLS ONLY AFTER ALL UPSTREAM AREAS ARE

- CLEARING AND GRUBBING, AND EARTHWORK.
   EARTHWORK ASSOCIATED WITH THE CONSTRUCTION OF CURB AND SIDEWALK.

TOTAL SITE AREA: TOTAL AREA TO BE DISTURBED:

1 15 ACRES 1.15 ACRES

1.D. RUNOFF DATA:

RUNOFF COEFFICIENTS:

VARIES FROM 0.25 TO 0.47

SOIL DATA: THE SOILS CONSIST OF ENTIRELY BONIFAY LOAMY SAND, 0 TO 5 PERCENT SLOPES,

THERE IS ONE OUTFALL IN THE SUBJECT AREA.

#1 DESCRIPTION: EXISTING CURB INLET ON EAST PROPERTY LINE ON E. JOHNSON AVE, WHICH IS PART OF EXISTING STORM SEWER SYSTEM THAT DRAINS SOUTHEASTERLY AND DISCHARGES INTO EXISTING JOHNSON POND (LATITUDE 30' 31' 02.4" N, LONGITUDE 87' 15' 48.2" W).

LOCATION: LATITUDE 30" 31' 10.2" N, LONGITUDE 87" 15' 57.3" EST. DRAINAGE AREA SIZE: 3.13 ACRES (INCLUDES 1.98 ACRES OF OFFSITE DRAINAGE AREA) RECEIVING WATER NAME: JOHNSON POND

THE CONSTRUCTION PLANS ARE BEING USED AS THE SITE MAPS, THE LOCATION OF THE REQUIRED INFORMATION IS DESCRIBED BELOW:

- DRAINAGE PATTERNS: THE DRAINAGE BASIN DIVIDES AND FLOW DIRECTIONS ARE SHOWN ON THE GRADING & DRAINAGE PLAN SHEET INCLUDED IN THE CONSTRUCTION PLANS.
- APPROXIMATE SLOPES: THE SLOPES OF THE SITE CAN BE SEEN IN THE GRADING & DRAINAGE
- AREAS OF SOIL DISTURBANCE: ESSENTIALLY THE WHOLE PROJECT WILL BE DISTURBED DURING
- LOCATIONS OF TEMPORARY CONTROLS: THESE ARE SHOWN ON THE EROSION CONTROL SHEET
- LOCATIONS OF PERMANENT CONTROLS: TWO DRY ROCK BED SWALES ARE THE PRIMARY PERMANENT STORMWATER MANAGEMENT CONTROLS, THESE ARE SHOWN ON THE GRADING & DRAINAGE
- AREAS TO BE STABILIZED: THE PROJECT WILL BE EITHER PAVED OR GRASS AREAS WILL BE
- SURFACE WATERS: NOT APPLICABLE.
- DISCHARGE POINTS TO SURFACE WATERS: NOT APPLICABLE.

SEE ITEM 1.D. FOR THE OUTFALL LOCATIONS AND RECEIVING WATER NAMES, THERE ARE NO WETLAND AREAS ON THE PROJECT SITE.

- 2.A. EROSION AND SEDIMENT CONTROLS:

IN THE SEDIMENT AND EROSION CONTROL PLAN, THE CONTRACTOR SHALL DESCRIBE THE PROPOSED STABILIZATION AND STRUCTURAL PRACTICES BASED ON THE PROPOSED TEMPORARY TRAFFIC CONTROL (TTC) PLAN. THE FOLLOWING RECOMMENDED GUIDELINES ARE BASED ON THE TEMPORARY TRAFFIC CONTROL PLAN OUTLINED IN THE CONSTRUCTION PLANS. WHERE FOLLOWING THE TEMPORARY TRAFFIC

THE FOLLOWING GUIDELINES MAY BE ACCEPTED OR MODIFIED IN THE SEDIMENT AND EROSION CONTROL PLAN, SUBJECT TO APPROVAL BY THE ENGINEER. AS WORK PROGRESSES, THE CONTRACTOR SHALL MODIFY THE PLAN TO ADAPT TO SEASONAL VARIATIONS, CHANGES IN CONSTRUCTION ACTIVITIES, AND

FOR EACH CONSTRUCTION PHASE, INSTALL PERIMETER CONTROLS AFTER CLEARING AND GRUBBING NECESSARY FOR INSTALLATION OF CONTROLS BUT BEFORE BEGINNING OTHER WORK FOR THE CONSTRUCTION PHASE. REMOVER PERIMETER CONTROLS ONLY AFTER ALL UPSTREAM AREAS ARE

TO MINIMIZE THE IMPACT OF SOIL DISTURBING ACTIVITIES AND IMPLEMENTATION OF CONTROLS:

- PLACE SILT FENCES AROUND DITCH BOTTOM INLETS, PLACE SYNTHETIC BALES ON REMAINING
- PROTECT PROJECT AREAS NOT DISTURBED AND OFFSITE AREAS BY PLACING SILT FENCE ALONG LOW SIDE OF GRADING AND AROUND PROJECT PERIMETER.

### STABILIZATION PRACTICES:

IN THE SEDIMENT AND EROSION CONTROL PLAN, THE CONTRACTOR SHALL DESCRIBE THE STABILIZATION PRACTICES PROPOSED TO CONTROL EROSION, INITIATE ALL STABILIZATION MEASURES AS SOON AS PRACTICAL, BUT IN CASE MORE THAN 7 DAYS AFTER CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. THE STABILIZATION PRACTICES SHALL INCLUDE AT LEAST THE FOLLOWING, UNLESS OTHERWISE APPROVED BY THE ENGINEER.

- ARTIFICIAL COVERING IN ACCORDANCE WITH STANDARD SPECIFICATION FOR ROAD AND BRIDGE
- \* TURF AND SOD IN ACCORDANCE WITH, SPECIFICATION SECTION 104.

### PERMANENT:

- ASPHALT OR CONCRETE SURFACE.
- SOD IN ACCORDANCE WITH SPECIFICATION SECTION 570.
- STRUCTURAL PRACTICES:

IN THE SEDIMENT AND EROSION CONTROL PLAN, THE CONTRACTOR SHALL DESCRIBE THE PROPOSED STRUCTURAL PRACTICES TO CONTROL OR TRAP SEDIMENT AND OTHERWISE PREVENT THE DISCHARGE OF POLLUTANTS FROM EXPOSED AREAS OF THE SITE, SEDIMENT CONTROLS SHALL BE IN PLACE BEFORE DISTURBING SOIL UPSTREAM OF THE CONTROL. THE STRUCTURAL PRACTICES SHALL INCLUDE AT LEAST THE FOLLOWING, UNLESS OTHERWISE APPROVED BY THE ENGINEER.

- SEDIMENT BARRIERS IN ACCORDANCE WITH STANDARD PLAN INDEX 570-001, SPECIFICATION SECTION 104, AND FDEP EROSION AND SEDIMENT CONTROL DESIGNER AND REVIEWER
- INLET PROTECTION IN ACCORDANCE WITH STANDARD INDEX 570-001, FDEP EROSION AND SEDIMENT CONTROL DESIGNER AND REVIEWER MANUAL AND SPECIAL DETAILS SHOWN IN THE TTC PLAN,

### PERMANENT

- \* PAVEMENT
- \* SOD.

2.B. STORMWATER MANAGEMENT

TWO DRY ROCK BED SWALES WILL BE CONSTRUCTED TO COLLECT AND CONVEY STORMWATER RUNOFF FROM THE PROJECT'S ONSITE AND OFFSITE DRAINAGE AREAS, AN EXISTING DITCH BOTTOM INLET ON THE EAST BOUNDARY OF THE SITE WILL BE MODIFIED TO PROVIDE A CONTROL STRUCTURE FOR UTILIZING THE TWO SWALE AREAS FOR WATER QUALITY TREATMENT AND PEAK DISCHARGE ATTENUATION FOR THE SITE. A PERMIT IS PENDING FOR THE FACILITY BY THE NORTHWEST FLORIDA WATER MANAGEMENT DISTRICT (NWFWMD).

2.C. OTHER CONTROLS

2 C 1 WASTE DISPOSAL:

IN THE SEDIMENT AND EROSION CONTROL PLAN, THE CONTRACTOR SHALL DESCRIBE THE PROPOSED METHODS TO PREVENT THE DISCHARGE OF SOLID MATERIALS, INCLUDING BUILDING MATERIALS, TO WATERS OF THE UNITED STATES, THE PROPOSED METHODS SHALL INCLUDE AT LEAST THE FOLLOWING, UNLESS OTHERWISE APPROVED BY THE ENGINEER:

- PROVIDING LITTER CONTROL AND COLLECTION WITHIN THE PROJECT DURING CONSTRUCTION
- DISPOSING OF ALL FERTILIZER AND/OR OTHER CHEMICAL CONTAINERS ACCORDING TO EPA'S STANDARD PRACTICES AS DETAILED BY THE MANUFACTURER.
- DISPOSING OF SOLID MATERIALS INCLUDING BUILDING AND CONSTRUCTION MATERIALS OFF THE PROJECT SITE BUT NOT IN SURFACE WATERS, OR WETLANDS.
- OFF-SITE VEHICLE TRACKING & DUST CONTROL:

IN THE SEDIMENT AND EROSION CONTROL PLAN, THE CONTRACTOR SHALL DESCRIBE THE PROPOSED METHODS FOR MINIMIZING OFF-SITE VEHICLE TRACKING OF SEDIMENTS AND GENERATING DUST. THE PROPOSED METHODS SHALL INCLUDE AT LEAST THE FOLLOWING, UNLESS OTHERWISE APPROVED BY THE

\* COVERING LOADED HAUL TRUCKS WITH TARPAULINS.

REMOVING EXCESS DIRT FROM ROADS DAILY.

STABILIZING CONSTRUCTION ENTRANCES ACCORDING TO THE FDEP EROSION AND SEDIMENT

- USING ROADWAY SWEEPERS DURING DUST GENERATING ACTIVITIES SUCH AS EXCAVATION AND
- STATE AND LOCAL REGULATIONS FOR WASTE DISPOSAL. SANITARY SEWER, OR SEPTIC TANK OPERATIONS.

IN THE SPECIFICATIONS 104, EROSION CONTROL PLAN, THE CONTRACTOR SHALL DESCRIBE THE PROPOSED PROCEDURES TO COMPLY WITH APPLICABLE STATE AND LOCAL REGULATIONS FOR WASTE DISPOSAL, SANITARY SEWER OR SEPTIC SYSTEMS,

FERTILIZERS AND PESTICIDES:

IN THE SEDIMENT AND EROSION CONTROL PLAN, THE CONTRACTOR SHALL DESCRIBE THE PROCEDURES FOR APPLYING FERTILIZERS AND PESTICIDES. THE PROPOSED PROCEDURES SHALL COMPLY WITH APPLICABLE SUBSECTIONS OF SECTION 982 OF THE SPECIFICATIONS.

TOXIC SUBSTANCES:

IN THE SEDIMENT AND EROSION CONTROL PLAN, THE CONTRACTOR SHALL PROVIDE A LIST OF TOXIC SUBSTANCES THAT ARE LIKELY TO BE USED ON THE JOB AND PROVIDE A PLAN ADDRESSING THE GENERATION, APPLICATION, MIGRATION, STORAGE, AND DISPOSAL OF THESE SUBSTANCES.

APPROVED STATE AND LOCAL PLANS AND PERMITS

- FDEP RULE CHAPTER 62-65 F.A.C.
- NWFWMD ERP RULE CHAPTER 62-346 F.A.C.

MAINTENANCE:

IN THE SEDIMENT AND EROSION CONTROL PLAN, THE CONTRACTOR SHALL PROVIDE A PLAN FOR MAINTAINING ALL EROSION AND SEDIMENT CONTROLS THROUGHOUT CONSTRUCTION. THE MAINTENANCE PLAN SHALL AT A MINIMUM, COMPLY WITH THE FOLLOWING:

- SILT FENCE: MAINTAIN PER SPECIFICATION SECTION 104, ANTICIPATE REPLACING SILT FENCE ON 1
- SEDIMENT BARRIERS: REMOVE SEDIMENT AS PER MANUFACTURER'S RECOMMENDATIONS OR WHEN WATER PONDS IN UNACCEPTABLE AMOUNTS OR AREAS,

QUALIFIED PERSONNEL SHALL INSPECT THE FOLLOWING ITEMS AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.50 INCHES OR GREATER.

TO COMPLY, THE CONTRACTOR SHALL INSTALL AND MAINTAIN RAIN GAUGES AND RECORD THE DAILY RAINFALL WHERE SITES HAVE BEEN PERMANENTLY STABILIZED, CONDUCT INSPECTIONS AT LEAST ONCE EVERY MONTH. ALSO INSPECT THAT CONTROLS INSTALLED IN THE FIELD AGREE WITH THE LATEST

- POINTS OF DISCHARGE TO WATERS OF THE UNITED STATES.
- POINTS OF DISCHARGE TO MUNICIPAL SEPARATE STORM DRAIN SYSTEMS.
- DISTURBED AREAS OF THE SITE THAT HAVE NOT BEEN FINALLY STABILIZED
- AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION.
- STRUCTURAL CONTROLS,
- STORMWATER MANAGEMENT SYSTEMS.
- LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE.

THE CONTRACTOR SHALL INITIATE REPAIRS WITHIN 24 HOURS OF INSPECTIONS THAT INDICATE ITEMS ARE NOT IN GOOD WORKING ORDER.

IF INSPECTIONS INDICATE THAT THE INSTALLED STABILIZATION AND STRUCTURAL PRACTICES ARE NOT SUFFICIENT TO MINIMIZE EROSION, RETAIN SEDIMENT, AND PREVENT DISCHARGING POLLUTANTS, THE CONTRACTOR SHALL PROVIDE ADDITIONAL MEASURES, AS APPROVED BY THE ENGINEER.

NON-STORMWATER DISCHARGES:

PER SPECIFICATION SECTION 104 EROSION CONTROL PLAN, IDENTIFY ALL ANTICIPATED NON-STORMWATER DISCHARGES (EXCEPT FLOWS FROM FIRE FIGHTING ACTIVITIES). THE CONTRACTOR SHALL DESCRIBE THE PROPOSED MEASURES TO PREVENT POLLUTION OF THESE NON-STORMWATER


> THIS DOCUMENT HAS BEEN DIGITALL William H Telford 2021.11.02 10:49:41 -04'00' ON THE DATE ADJACENT TO THE SEA PAINTED COPIES OF THIS DOCUMENT A HOT CONSIDERED SIGHED AND SEALED AND THE SIGNATURE HUST BE VERIFIED OR ANY ELECTRONIC COPIES. ATKINS HORTH AMERICA, INC. 492 S. KELLER ROAD ORLANDO, EL 32810 (407) 647-7275 CERTIFICATE OF AUTHORIZATION: 24 WILLIAM H. TELFORD, F.E. NO. 32067




No 32067 STATE OF THE STORY OF THE STORY THE YEARAS

GNED BY: DMH CHECKED BY: JB#

PPROVED BY: WHT 100070185 C9.01





### LANDSCAPE NOTES

- THE ESTABLISHMENT PERIOD FOR WATERING AND MAINTENANCE BY THE CONTRACTOR SHALL BE 730 DAYS. THE CONTRACTOR SHALL REQUEST AN ESTABLISHMENT PERIOD INSPECTION AT THE END OF THE 730 DAY ESTABLISHMENT PERIOD. A REPRESENTATIVE FROM ESCAMBIA COUNTY WHO IS RESPONSIBLE FOR MAINTENANCE SHALL BE IN ATTENDANCE AT THE ESTABLISHMENT PERIOD INSPECTION.
- LANDSCAPE MATERIALS SHALL BE ADJUSTED IN THE FIELD TO AVOID CONFLICTS WITH ANY (PROPOSED OR EXISTING TO REMAIN) UTILITY STRUCTURES, DRAINAGE STRUCTURES, DITCHES, UNDER DRAINS, DITCH BLOCKS, STORM WATER MANAGEMENT FACILITIES, PAVING, DRAINAGE DISCHARGE PATHS, SIGNAGE, OVERHEAD AND UNDERGROUND UTILITIES, LIGHTING AND THEIR APPURTENANCES. THE CONTRACTOR SHALL NOT INSTALL THE PROPOSED IMPROVEMENTS IF A CONFLICT EXISTS. ANY COSTS TO REMOVE AND/OR REPAIR WORK INSTALLED THAT HAS NOT BEEN APPROVED BY THE OWNER'S REPRESENTATIVE SHALL BE AT THE CONTRACTOR'S EXPENSE.
- ALL WORK, INCLUDING BUT NOT LIMITED TO IRRIGATION AND LANDSCAPE, SHALL BE CLOSELY COORDINATED WITH THAT OF OTHER TRADES IN ORDER TO AVOID CONFLICTS. THE INSTALLATION SHALL BE COORDINATED WITH ALL NEW AND EXISTING IMPROVEMENTS.
- REFER TO THE LANDSCAPE PLANS, GENERAL NOTES, AND THE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS. WHERE CONFLICTS EXIST, THE MORE STRINGENT STANDARDS AND SPECIFICATIONS SHALL APPLY.
- THE CONTRACTOR SHALL INSURE THAT, PRIOR TO MOVING ON SITE, ALL EQUIPMENT WHICH LAST OPERATED IN AREAS KNOWN TO BE INFESTED WITH NOXIOUS WEEDS IS FREE OF SOIL, SEEDS, VEGETATIVE MATTER, OR OTHER DEBRIS THAT COULD CONTAIN OR HOLD SEEDS,
- QUANTITIES ON LANDSCAPE PLAN ARE MINIMUM ONLY. CONTRACTOR IS RESPONSIBLE FOR THEIR OWN QUANTITY TAKE-OFF, AND SHALL PROVIDE ALL PLANT MATERIAL REQUIRED TO FILL PLANT RED AREA AT SPACING SHOWN ON PLANT SCHEDULE.
- ANY EXISTING CONCRETE AND BASE MATERIAL IN PROPOSED PLANTING AREA SHALL BI REMOVED COMPLETELY AND DISPOSED OF OFF SITE, APPROPRIATE TOP SOIL AND AMENDMENTS SHALL BE IMPORTED FOR OPTIMAL PLANT GROWTH TO REPLACE REMOVED MATERIAL.
- WHERE SOD IS BEING INSTALLED, TOPSOIL SHALL BE USED AS A BASE AT LEAST SIX INCHES
- IF THE QUANTITY OF EXISTING STOCKPILED OR EXCAVATED TOPSOIL IS INADEQUATE FOR PLANTING, SUFFICIENT ADDITIONAL TOPSOIL SHALL BE IMPORTED TO THE SITE BY THE CONTRACTOR: TOPSOIL FURNISHED SHALL BE A NATURAL, FERTILE, FRIABLE, LOAMY SOIL POSSESSING CHARACTERISTICS OF REPRESENTATIVE OF PRODUCTIVE SOILS IN THE VICINITY. TOPSOIL SHALL BE OBTAINED FROM NATURALLY WELL-DRAINED AREAS. TOPSOIL SHALL BE WITHOUT ADMIXTURE OF SUBSOIL AND FREE FROM JOHNSON GRASS (SORGHUM HALAPENSE), NUT GRASS (CYPRUS ROTUNDAS), AND OBJECTIONABLE WEEDS AND TOXIC SUBSTANCES. IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, AND NOXIOUS WEEDS, AND SHOULD GIVE EVIDENCE OF BEING ABLE TO SUPPORT HEALTHY PLANT GROWTH.
- AFTER THE SITE HAS BEEN BROUGHT TO PROPER GRADE FOR PLACEMENT OF TOPSOIL AND IMMEDIATELY PRIOR TO DUMPING AND SPREADING THE TOPSOIL. THE SUBGRADE SHALL BE LOOSENED BY DISKING OR SCARIFYING TO A DEPTH OF 2 INCHES TO ENSURE BONDING OF THE TOPSOIL AND SODDING
- TOPSOIL SHALL NOT BE PLACED WHILE IN A MUDDY CONDITION, WHEN THE SUBGRADE IS EXCESSIVELY WET, OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER
- ANY IRREGULARITIES IN THE SURFACE, RESULTING FROM TOP-SOILING OR OTHER OPERATIONS, SHALL BE CORRECTED IN ORDER TO PREVENT THE FORMATION OF DEPRESSIONS OR WATER
- 13. LANDSCAPE BEDS AND PLANTING LOCATIONS MAY HAVE BEEN ADJUSTED IN THE FIELD DURING INSTALLATION AND WILL BE NOTED ON THE AS-BUILT CERTIFICATION AND NOTED AS "REVISED LOCATION IS ACCEPTABLE AND APPROVED BY THE LANDSCAPE ARCHITECT OF RECORD".
- ALL PLANTS MUST BE FLORIDA GRADE NUMBER 1 QUALITY OR BETTER ACCORDING TO THE MOST RECENT EDITION OF THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES' GRADES AND STANDARDS FOR NURSERY PLANTS, PART I AND II

### PLANTING BED PREPARATION

- LOOSEN SOIL TO A MINIMUM DEPTH OF FOUR INCHES AND REMOVE ALL DEBRIS, REGRADE THE BED TO ITS PREPLANTING SUBGRADE. DIG PLANTING PITS AT 1.5 TIMES THE DIAMETER OF THE POT. FILL PLANT PIT WITH APPROVED PLANTING MIX AND COMPACT SO THAT THE TOP OF ROOT BALL WILL SETTLE TO THE PROPER LEVEL RELATIVE TO FINISH GRADE. SET PLANT AND FILL REMAINDER OF HOLE WITH PLANTING MIX. FERTILIZE EACH PLANT WITH THE APPROVED TYPE AND RATE OF FERTILIZER. WATER IN THOROUGHLY. RESET ANY PLANTS THAT SETTLE TOO DEEP. REMOVE SPOIL SOIL AND RAKE THE BED TO ITS FINISH GRADE. COVER ALL BED AREAS WITH THE SPECIFIED MULCH DEPTH. REMOVE ALL DEBRIS FROM THE MULCH. WATER BED THOROUGHLY, ALL PINE STRAW SHALL BE HIGH GRADE FROM THE 'IMPROVED SLASH' PINE TREE WITH A MINIMUM NEEDLE LENGTH OF EIGHT INCHES.
- ALL PROPOSED PLANTING AND ROCK AREAS SHALL THEN BE TREATED WITH A PRE-EMERGENT HERBICIDE TO ASSURE THAT WEEDS WILL BE CONTROLLED PRIOR TO PLANTING. HERBICIDE INSTRUCTIONS SHALL BE FOLLOWED AS TO TREATMENT DILUTION, MIX, APPLICATION, AND TIME PERIODS BETWEEN APPLICATIONS AS APPLICABLE TO ASSURE WEEDS ARE ELIMINATED FROM THE PLANTING BEDS PRIOR TO COMMENCING PLANTING
- ALL SOIL AMENDMENTS SHALL BE ADDED TO THE PROPOSED PLANTING AREAS AND THOROUGHLY INCORPORATED INTO THE SOIL PRIOR TO COMMENCING FINAL GRADING AND INSTALLATION.

### UTILITY NOTES

- THE LOCATION(S) OF THE UTILITIES SHOWN ON THE PLANS SHOULD BE CONSIDERED APPROXIMATE ONLY.
- A UTILITY REPRESENTATIVE SHALL BE PRESENT IF LANDSCAPING REQUIRES ANY EXCAVATION OF GREATER THAN 36 INCHES DEPTH WITHIN 15' OF UNDERGROUND UTILLTIES.

### **IRRIGATION NOTES**

- PERMANENT IRRIGATION SHALL BE INSTALLED FOR ALL LANDSCAPE INCLUDING EXISTING SOD SHOWN ON THE PLANS. THE IRRIGATION COVERAGE IS TO BE COMPRISED OF DRIP, SPRAY HEADS, AND BUBBLERS. A LOCKABLE CABINET CONTROLLER(S) SHALL BE PROVIDED BY THE CONTRACTOR AND ITS LOCATION DETERMINED IN CONJUNCTION WITH THE OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION. WATER SUPPLY SHALL BE BY WELL(S) INSTALLED BY THE CONTRACTOR, LOCATION AND NUMBER OF WELLS SHALL BE DETERMINED BY THE CONTRACTOR WITH COORDINATION WITH THE COUNTY, IT IS SUGGESTED TO OBTAIN POWER AT THE LIGHTING SERVICE LOCATIONS. ALL PERMITTING IS THE RESPONSIBILITY OF THE CONTRACTOR
- THE IRRIGATION SYSTEM SHALL BE DESIGNED AND INSTALLED AS A DESIGN-BUILD PORTION OF THE WORK PERFORMED BY THE CONTRACTOR. THE SYSTEM MUST BE DESIGNED /ZONED SO THAT ALL IRRIGATION CAN OCCUR BETWEEN THE HOURS OF 1:00 A.M. AND 7:00 A.M.
- THE CONTRACTOR SHALL FURNISH THE OWNER'S REPRESENTATIVE WITH SHOP DRAWINGS AND SCHEMATIC DESIGN PLANS INDICATING FULL COVERAGE OF IRRIGATED AREAS. THE SHOP DRAWINGS MUST INCLUDE PROPOSED SLEEVING LOCATIONS/SIZES, ALL TREES SHALL HAVE 2 BUBBLERS THAT ARE PLACED ON BUBBLER-ONLY ZONES THAT ARE SEPARATE FROM THE OTHER IRRIGATION ZONES, INSTALLATION SHALL NOT COMMENCE UNTIL THE SHOP DRAWINGS ARE APPROVED BY THE OWNER'S REPRESENTATIVE.
- PERMANENT SLEEVES SHALL BE INSTALLED BY THE CONTRACTOR AS NECESSARY. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ALL BORINGS AND CASINGS, AS NEEDED. THE CONTRACTOR IS RESPONSIBLE, AT THEIR EXPENSE, TO REPAIR ANY AND ALL DAMAGE CAUSED TO ANY ROADWAY OR ANY/ALL OTHER AREAS, OR UTILITIES AS A RESULT OF THE BORINGS OR ANY OTHER IRRIGATION WORK.
- THE INSTALLER SHALL BE EXPECTED TO MAKE IRRIGATION SYSTEM FIELD ADJUSTMENTS ON THE SITE AS NEEDED, IN ORDER TO MAINTAIN COMPLETE AND ACCURATE IRRIGATION COVERAGE, AND TO MAINTAIN THE INTENT OF THE DESIGN, THE FINAL LOCATIONS FOR ALL MAJOR EQUIPMENT (AS APPLICABLE), INCLUDING CONTROLLERS, VALVES, WELLS, SUPPLY CONNECTIONS, MAINLINES, METERS, ETC. SHALL BE DETERMINED IN THE FIELD, STAKED OUT BY THE CONTRACTOR USING THEIR DRAWINGS AS A GUIDE, AND THEN APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.
- OVER FLOW ONTO STRUCTURES AND PAVED SURFACES IS NOT ALLOWED TO OCCUR.
- ALL WORK SHALL BE DONE IN ACCORDANCE WITH PREVAILING CODES AND REGULATIONS. IT SHALL BE THE RESPONSIBILITY OF THE INSTALLER TO VERIFY AND CONFORM TO THE PARTICULAR CODES FOR THIS LOCATION. THE INSTALLER SHALL OBTAIN ALL NECESSARY PERMITS (INCLUDING THOSE FOR BORES, AND ANY WATER LINE TAPS, IF NECESSARY), UTILITY LOCATES, AND INSPECTIONS.
- ALL MATERIAL AND LABOR NECESSARY TO PROVIDE A COMPLETE, FULLY OPERATIONAL, AND GUARANTEED SYSTEM SHALL BE CONSIDERED PART OF THE WORK, WHETHER OR NOT THEY ARE SPECIFICALLY INDICATED IN THE SUBMITTED DOCUMENTS. THIS SHALL INCLUDE CONFORMANCE WITH THE REQUIREMENTS AND RECOMMENDATIONS OF THE VARIOUS MANUFACTURERS OF THE EQUIPMENT, AND WITH APPLICABLE TRAINING AND CERTIFICATION OF INSTALLATION PERSONNEL
- METALLIC LOCATOR/WARNING TAPE SHALL BE BURIED ABOVE ALL WIRING AND PIPING.
- VALVE BOXES SHALL BE TAMPER-RESISTANT TYPE.
- ALL IRRIGATION SHALL BE OF THE PROPER SIZE AND TYPE FOR THE LOCATION AND PLANT MATERIAL, ALL FOURMENT SHALL BE INSTALLED WITH ADEQUATE AND UNFORM CLEARANCES. FROM ALL PAVING, CURBS, SIDEWALKS, WALLS, AND OTHER OBSTACLES, SO THAT DAMAGE TO EQUIPMENT DOES NOT OCCUR DURING NORMAL LANDSCAPE MAINTENANCE OPERATIONS. ALL IRRIGATION SHALL BE ADJUSTED TO OBTAIN OPTIMAL COVERAGE OF PLANT MATERIAL.
- 12. CONTROLLER(S) SHALL BE HOOKED UP BY A LICENSED ELECTRICIAN.
- THE CONTROLLER(S) SHALL BE EQUIPPED WITH A PROPERLY LOCATED AND INSTALLED RAIN/FREEZE SHUTOFF SENSOR DEVICE THAT COMPLIES WITH FLORIDA LAW. THE SENSOR(S) SHALL BE LOCATED IN SUCH A MANNER SO THAT THEY ARE UNOBSTRUCTED, AND DIRECTLY EXPOSED TO NATURAL RAINFALL AND SUNLIGHT FROM ALL DIRECTIONS, BUT NOT TO RUNOFF WATER FROM SWALES OR OTHER SURFACES.
- THE MINIMUM SUPPLY REQUIREMENTS FOR THE SYSTEM SHALL BE DETERMINED BY THE CONTRACTOR AND STATED ON THE DESIGN-BUILD PLANS AND SHOP DRAWINGS
- THE INSTALLER SHALL BE EXPECTED TO BE FAMILIAR WITH ALL REQUIREMENTS FOR THE WORK, AND TO CONDUCT THE WORK IN A CLEAN, SAFE, AND WORKMANLIKE MANNER. THE OWNER RESERVES THE RIGHT TO ACT TO PROTECT THEIR PROPERTY AND THE OTHER PERSONNEL AT WORK THERE, AND TO MAKE EMERGENCY REPAIRS OR TAKE CORRECTIVE ACTION IF THE INSTALLER DOES NOT FULFILL THEIR OBLIGATIONS IN A TIMELY MANNER. THE OWNER FURTHER RESERVES THE RIGHT TO BACK-CHARGE THE INSTALLER TO COVER SUCH EXPENSES, TO THE EXTENT ALLOWED UNDER APPLICABLE LAW.
- THE INSTALLER SHALL COORDINATE WITH THE OWNER'S REPRESENTATIVE FOR PROVISION OF ELECTRIC SERVICE REQUIREMENTS.
- THE IRRIGATION DESIGN AND INSTALLATION SHALL ASSURE THAT IRRIGATION PIPING DOES NOT CONFLICT WITH EXISTING UTILITIES.
- THE LANDSCAPE CONTRACTOR SHALL SUPPLY THE OWNER'S REPRESENTATIVE WITH DETAILED AND PROPERLY SCALED IRRIGATION AS-BUILT DRAWINGS IN ACAD FORMAT (2016 VERSION OR LATER) WITHIN 30 DAYS OF PROJECT ACCEPTANCE. THE AS-BUILTS MUST INCLUDE ALL SYSTEM COMPONENTS AND THEIR SIZES.
- IRRIGATION SYSTEM IS TO BE DESIGN BUILD. CONTRACTOR TO SUBMIT SCHEMATICS TO THE COUNTY FOR REVIEW AND APPROVAL. ALL LANDSCAPE ITEMS ARE TO RECEIVE IRRIGATION INCLUDING ISLANDS. THE NUMBER OF ECUA CONNECTION POINTS IS BASED ON THE

CONTRACTOR'S DESIGN. ANY POWER REQUIREMENTS FOR THE TIMERS ARE INTENDED TO COINCIDE WITH THE LIGHTING SYSTEM POWER SERVICE POINTS

20. ALL FLECTRICAL WORK WILL BE PROVIDED BY THE CONTRACTOR.

### PLANTING NOTES

- THE LANDSCAPE INSTALLATION MUST BE PROPERLY SEQUENCED WITH OTHER CONSTRUCTION SO THAT THE LANDSCAPE AND IRRIGATION IS NOT DAMAGED BY OTHER WORK/TRADES (AND
- THE CONTRACTOR SHALL VERIEY THE EXISTENCE OF AND STAKE ALL UTILITIES PRIOR TO CONSTRUCTION. EXCAVATION OF PLANT PITS LOCATED WITHIN 5' OF UTILITIES SHALL BE PERFORMED BY HAND, ANY UTILITY/PLANT MATERIAL CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION OR ANY FIELD
- THE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE THE PLANTINGS SHOWN ON ALL DRAWINGS, ALL PLANTS SHALL MEET SIZE. CONTAINER, AND SPACING SPECIFICATIONS AS SHOWN IN THE PLANT SCHEDULE. THE CONTRACTOR SHALL GUARANTEE PLANT HEALTH AND SURVIVABILITY FOR ONE YEAR FROM DATE OF PROJECT ACCEPTANCE BY THE OWNER'S REPRESENTATIVE. ANY MATERIAL NOT MEETING SPECIFICATIONS OR DISPLAYING POOR HEALTH SHALL BE REPLACED AT CONTRACTOR'S EXPENSE WITHIN 2 WEEKS OF NOTICE.
- TREAT ALL SOD AREAS WITHIN THE PROJECT LIMITS BY APPLYING 2 APPLICATIONS WITHIN A 14 DAY PERIOD WITH A NON-SELECTIVE HERBICIDE TAKING CARE TO PROJECT AREAS OUTSIDE THE PLANTING BEDS FROM OVERSPRAY, FOLLOWED BY TILLING AND SOIL AMENDMENT IF
- NOTIFY THE OWNER'S REPRESENTATIVE A MINIMUM OF ONE WEEK PRIOR TO PLANT DELIVERY TO SCHEDULE ON-SITE INSPECTION UPON DELIVERY. INSTALLED PLANT MATERIAL NOT MEETING SPECIFICATIONS SHALL BE REMOVED AND REPLACED AT CONTRACTOR'S EXPENSE. ALL PLANTS MUST BE BROUGHT TO THE SITE FREE OF WEEDS. ADDITIONALLY. THE CONTRACTOR SHALL PROVIDE THE OWNER'S REPRESENTATIVE WITH REPRESENTATIVE PLANT PHOTOS TO APPROVE FOR ALL PLANT MATERIALS PRIOR TO ANY PLANT DELIVERY, MEASURING STICKS SHALL BE SHOWN IN PHOTOS, AS APPROPRIATE.
- ALL PLANT MATERIALS INDICATED WITH A GALLON SIZE SHALL BE CONTAINER GROWN AND WITHIN A CONTAINER APPROPRIATE FOR THE PLANT SIZE. ROOT BOUND PLANTS SHALL NOT BE ACCEPTED. NO SUBSTITUTIONS SHALL BE PERMITTED WITHOUT PRIOR APPROVAL OF THE OWNER'S REPRESENTATIVE.
- THE LANDSCAPE CONTRACTOR SHALL CONDUCT REPRESENTATIVE SOIL ANALYSIS PRIOR TO THE INSTALLATION OF ANY PLANT MATERIAL. THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE OWNER'S REPRESENTATIVE OF ANY IMPROPER SOIL CONDITION (NUTRITIONAL DEFICIENCIES, WETNESS, MUCK, DEBRIS, ETC.) AND SHALL RECOMMEND FOR APPROVAL, PRIOR TO INSTALLATION, ALL SOIL AMENDMENTS THAT MAY BE NECESSARY TO PROMOTE HEALTHY, VIGOROUS PLANT GROWTH.
- ALL PLANT MATERIAL MUST BE PLANTED IMMEDIATELY UPON DELIVERY TO THE SITE AND WATERED IN (BY HAND IF THE IRRIGATION SYSTEM IS NOT FUNCTIONING PROPERLY). ANY PLANT MATERIAL NOT INSTALLED WITHIN 6 HOURS OF DELIVERY TO THE SITE MUST BE STORED IN AN APPROVED, PROTECTED HOLDING AREA AND SHALL BE WATERED AS NECESSARY TO MAINTAIN PLANT HEALTH AND QUALITY.
- SUPPLY THE OWNER'S REPRESENTATIVE WITH AS-BUILT DRAWINGS IN ACAD FORMAT (2016 VERSION OR LATER) WITHIN 30 DAYS OF PROJECT ACCEPTANCE.
- DUE TO THE LARGE QUANTITIES OF LANDSCAPE MATERIAL ON THIS PROJECT, MULTIPLE NURSERIES CAN BE UTILIZED TO SUPPLY THE MATERIALS AS LONG AS THEY MATCH IN TYPE, FORM AND PROPOSED DELIVERY CONDITIONS.

GATEW LANDSCAPE & I NOTH

Alyssa Alyssa R

Garcia 2021,12,10 13:13:28

Garcia


-05'00'

DSCAPE ARCHIT OF RECORD FL LA #666747!

RAWNBY: HIL ESIGNED BY: AG HECKED BY: SP

PPROVED BY: MR

100070185 T.2.01



- TOP OF SOD SOIL LAYER TO BE FLUSH W/ FINISH GRADE OF PAVEMENT -- PREPARED SUBGRADE

SIDEWALK OR OTHER PAVING

CAN BE REMOVED AT THE TIME OF PLANTING.
3- SETTLE SOIL AROUND ROOT BALL OF EACH PLANT PRIOR TO MULCHING.

PLAN GUYLINE STRAPPING

PLANT TREE 2" TO 4" -ABOVE GRADE

3" MULCH LAYER COVERING 2' RADIUS FROM TRUNK (1" OVER ROOT BALL)

6" SOIL SAUCER TO HOLD WATER

NATIVE SOIL BACKFILL OR AMENDED SOIL AS REQUIRED BY SOIL ANALYSIS RECEIVING HOLE SHALL BE

APPROXIMATELY 1.5 TIMES LARGER THAN ROOT BALL

FINISH GRADE

TRUNK SHALL BE MAINTAINED IN A VERTICAL POSITION

TENSION BAR

SAFETY FLAGS (TYP.) -- REMOVE BURLAP (DOES NOT APPLY TO CONTAINER GROWN MATERIAL)

EXISTING SUBGRADE ARROWHEAD ANCHOR COMPACTED SOIL TO PREVENT SETTLING


SOD PLACEMENT DETAIL 2

\*EQUAL TO FULL O.C. SPACING OF PLANT TYPE MULCH LAYER AT SPECIFIED DEPTH-TOP OF MULCH TO BE-FLUSH WITH ADJACENT GRADE EXISTING TURF, SIDEWALK,— PAVING, CURB, OR VERTICAL STRUCTURE FINISH GRADE-

NOTE:

"I.E. IF PLANT SPACING IS 36" O.C., THEN THE CENTERLINE OF THE 1ST ROW OF PLANTS ADJACENT TO TURF, SIDEWALK, PAVING, CURB, OR A VERTICAL STRUCTURE SHALL BE SET 36" FROM THE EDGE OF THOSE ELEMENTS.

CANOPY TREE PLANTING & STAKING DETAIL  $\left(4\right)\frac{CA}{NTS}$ 



TREE PLANTING DETAIL - (SINGLE TRUNK)

3/4" = 1"-0"

LANDSCAPE ARCHITECT

ď

LANDSCAPE SCHEDULE DETAUS

ENSLEY GATEWAY

DRAWN BY: AG DESIGNED BY: AG

CHECKED BY: SP APPROVED BY: MR

PROJECT NUMBER DRAWING NUMBER 100070185 L2.02

(3)

PLANT SPACING AT PERIMETER OF BED DETAIL

**GROUNDCOVER**