SITE CONSTRUCTION PLANS FOR

HIGHLAND RIDGE

A 40 LOT TOWNHOME DEVELOPMENT 1940 DETROIT BOULEVARD ESCAMBIA COUNTY, FLORIDA

RBA PROJECT NO.: 2021.006

| 5 | SITE INFORMATION |
|-------------------------------|--|
| OWNER: | PB&J-1940 DETROIT DEVELOPMENT LLC SUITE 300 2301 NORTH 9TH AVENUE PENSACOLA, FL 32503 |
| DEVELOPER: | PB&J-1940 DETROIT DEVELOPMENT LLC SUITE 300 2301 NORTH 9TH AVENUE PENSACOLA, FL 32503 |
| PROPERTY REFERENCE NO: | 12-1S-31-1100-021-008 |
| PROPERTY ADDRESS: | 1940 DETROIT BLVD |
| PROPERTY AREA: | 3.98 ACRES |
| PROJECT AREA: | 3.98 ACRES |
| PROPERTY ZONING: | MDR (PREVIOUSLY R-3) - SAVINGS CLAUSE |
| FUTURE LAND USE: | MU-U |
| PROPOSED ACTIVITY: | SUBDIVISION |
| REQUIRED BUILDING SETBACKS | FRONT AND REAR: 20' SIDES: 10' |

| FEMA FLOOD INSURANCE RATE MAP INFORMATION | | | | | |
|---|---------------|---------|-----------|--------|-------------------|
| THE PARCEL SHOWN FOR DEVELOPMENT IS LOCATED WITHIN THE FOLLOWING FLOOD ZONE(S) AS DETAILED BY FEMA FIRM (FLOOD INSURANCE RATE MAP) INFORMATION DESCRIBED BELOW: | | | | | |
| FLOOD ZONE(S) | COMMUNITY No. | MAP No. | PANEL No. | SUFFIX | MAP REVISION DATE |
| X | 120080 | 12033C | 295 | G | SEPT 29, 2006 |

| CONTACTS | | |
|--|---|--|
| GULF POWER 5120 DOGWOOD DRIVE MILTON, FLORIDA 32570 | CONTACT: CHAD SWAILS PHONE: 850.429.2446 FAX: 850.429.2432 | |
| COX CABLE 3405 McLEMORE DR. PENSACOLA, FLORIDA 32514 | CONTACT: TROY YOUNG PHONE: 850.857.4510 FAX: 850.475.0621 | |
| ECUA 9255 STURDEVANT ST. PENSACOLA, FLORIDA 32514 | CONTACT: JACOB KEARLEY, P.E. PHONE: 850.969.5823 | |
| ENERGY SERVICES GAS 1625 ATWOOD DRIVE PENSACOLA, FLORIDA 32504 | CONTACT: DIANE MOORE PHONE: 850.474.5319 FAX: 850.474.5331 | |
| AT&T, INC. 605 W. GARDEN STREET PENSACOLA, FLORIDA 32501 | CONTACT: JONATHAN BLANKINCHIP PHONE: 850.436.1489 | |
| ESCAMBIA COUNTY PUBLIC WORKS 3363 WEST PARK PLACE PENSACOLA, FLORIDA 32501 | CONTACT: MRS. JOHNNY PETTIGREW PHONE: 850.595.3404 | |
| MCI | PHONE: 800.624.9675 | |
| SUNSHINE UTILITIES | PHONE: 800.432.4770 | |

DRAINAGE FEE

This document has been reviewed in accordance with

Regulations and Ordinances and does not in any way relieve the submitting Architect, Engineer, Surveyor, or other signatory from responsibility of details as drawn.

requirements of applicable Escambia County


Imperv. Surf. 30620.0 Sq ft

Stormwater Ret. 0.31 % (F)

Total Drainage Fee \$ 474.61

Pond Maint. Fee: MSBU

June 29, 2022



VICINITY MAP SCALE: 1" = 1000'



REBOL-BATTLE & ASSOCIATES

Civil Engineers and Surveyors

2301 N. Ninth Avenue, Suite 300 Pensacola, Florida 32503 Telephone 850.438.0400 Fax 850.438.0448 EB 00009657 LB7916

INDEX OF DRAWINGS

DOCUMENT NAME

LOW PRESSURE DETAIL MULTIPLE WATER METER

*PROJECT MANUALS USED ONLY WITH ECUA CIP PROJECTS

ECUA ENGINEERING MANUAL REFERENCE NOTE

| C1.0 | EXISTING SITE, DEMOLITION AND EROSION CONTROL PLAN |
|-------------------|--|
| C1.1 | EROSION CONTROL DETAILS |
| C1.2 | NPDES-STORMWATER POLLUTION PREVENTION PLAN |
| C1.3~C1.4 | SOIL BORING REPORT |
| C2.0 | SITE LAYOUT AND DIMENSION PLAN |
| C2.1 | SITE DETAILS |
| C3.0 | GRADING AND DRAINAGE PLAN |
| C3.1~C3.3 | GRADING AND DRAINAGE DETAILS |
| C3.4~C3.5 | NEIGHBORHOOD GRADING AND DRAINAGE PLAN |
| C4.0 | UTILITY PLAN |
| C4.1 | UTILITY DETAILS |
| C5.0~C5.7 | PLAN & PROFILE |
| C6.0~C6.2 | CROSS SECTIONS |
| DECODIDITION: /AC | DDEDARED BY REBOI -RATTLE AND ASSOCIATES): |

DESCRIPTION: (AS PREPARED BY REBOL-BATTLE AND ASSOCIATES):

COMMENCE AT THE SOUTHEAST CORNER OF SECTION 12, TOWNSHIP 1 SOUTH, RANGE 31 WEST ESCAMBIA COUNTY, FLORIDA; THENCE PROCEED NORTH 86°58'42" WEST ALONG THE SOUTH LINE OF SAID SECTION 12 FOR A DISTANCE OF 653.55 FEET; THENCE DEPARTING SAID SOUTH LINE, PROCEED NORTH 03'01'18" EAST FOR A DISTANCE OF 33.55 FEET TO THE NORTH RIGHT-OF-WAY (R/W) LINE OF THE SOUTHEAST 1/4 OF SAID SECTION; THENCE DEPARTING SAID SOUTH LINE, PROCEED SOUTH 03'13'30" WEST ALONG SAID EAST LINE OF SAID 653 FEET FOR A DISTANCE OF 650.61 FEET TO THE POINT OF BEGINNING.

ALL LYING AND BEING A PORTION OF SECTION 12, TOWNSHIP 1 SOUTH, RANGE 31 WEST ESCAMBIA COUNTY, FLORIDA, AND CONTAINING 3.98 ACRES MORE OR LESS.

PROFESSIONAL SURVEYOR AND MAPPER MARK A. NORRIS P.S.M. REBOL-BATTLE & ASSOCIATES, LLC 2301 NORTH NINTH AVE., SUITE 300 PENSACOLA, FL 32503 TELEPHONE 850.438.0400

CIVIL ENGINEER
PAUL A. BATTLE, P.E.
REBOL-BATTLE & ASSOCIATES, LLC
2301 NORTH NINTH AVE., SUITE 300 PENSACOLA, FL 32503 TELEPHONE 850.438.0400



THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING "RELEASED FOR CONSTRUCTION" DRAWINGS FROM REBOL-BATTLE & ASSOCIATES BEFORE BEGINNING CONSTRUCTION. REBOL-BATTLE & ASSOCIATES WILL NOT BE RESPONSIBLE FOR ANY CONSTRUCTION BASED ON PLANS THAT HAVE NOT BEEN RELEASED FOR CONSTRUCTION.

PROPERTY OWNER.

PLAN XISTING SITEROSION

OQLZ **P O o o** Vel ETRO A CC 40

NOT FOR CONSTRUCTION LICENSE No. 53126 I c. Batter CHATE OF FLORIDA. Paul Ar Battle P.E.

Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022

DRAWING No.

SHEET 1 OF 25

1. ALL EROSION AND SEDIMENT CONTROL PRACTICES TO BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCE, OR IN THEIR PROPER SEQUENCE, AND MAINTAINED UNTIL PERMANENT PROTECTION IS

2. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 30 DAYS, AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, WILL IMMEDIATELY RECEIVE A TEMPORARY SEEDING. IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER, THE DISTURBED AREAS WILL BE MULCHED WITH STRAW, OR EQUIVALENT MATERIAL, AT A RATE OF TWO (2) TONS PER ACRE, ACCORDING TO STATE STANDARDS.

3. PERMANENT VEGETATION TO BE SEEDED OR SODDED ON ALL EXPOSED AREAS WITHIN TEN (10) DAYS AFTER GRADING. MULCH TO BE USED AS NECESSARY FOR PROTECTION UNTIL SEEDING IS ESTABLISHED.

4. ALL WORK AND MATERIALS TO BE IN ACCORDANCE WITH THE FDOT "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", LATEST EDITION, SECTIONS 104, 570, 575 AND 980 TO 986.

*5. A BITUMINOUS CONCRETE BASE COURSE WILL BE APPLIED IMMEDIATELY FOLLOWING ROUGH GRADING AND INSTALLATION OF IMPROVEMENTS IN ORDER TO STABILIZE STREETS, ROADS, DRIVEWAYS AND PARKING AREAS. IN AREAS WHERE NO UTILITIES ARE PRESENT, THE BITUMINOUS CONCRETE BASE SHALL BE INSTALLED WITHIN 15 DAYS OF THE PRELIMINARY GRADING.

*6. IMMEDIATELY FOLLOWING INITIAL DISTURBANCE OR ROUGH GRADING, ALL CRITICAL AREAS SUBJECT TO EROSION (I.E. STEEP SLOPES AND ROADWAY EMBANKMENTS) WILL RECEIVE A TEMPORARY SEEDING IN COMBINATION WITH STRAW MULCH OR A SUITABLE EQUIVALENT, AT A THICKNESS OF TWO (2) TO FOUR (4) INCHES MIXED WITH THE TOP TWO (2) INCHES OF SOIL, ACCORDING TO STATE STANDARDS.

*7. ANY STEEP SLOPES RECEIVING PIPELINE INSTALLATION WILL BE BACKFILLED AND STABILIZED DAILY, AS THE INSTALLATION PROCEEDS (I.E. SLOPES GREATER THAN 3:1).

*8. A CRUSHED LIMEROCK, VEHICLE WHEEL-CLEANING BLANKET SHALL BE INSTALLED AT THE CONTRACTOR'S STAGING YARD AND/OR STOCKPILE AREAS TO PREVENT OFF-SITE TRACKING OF SEDIMENT BY CONSTRUCTION VEHICLES ONTO PUBLIC ROADS. BLANKET SHALL BE 15FT. X 50FT. X 6IN. (MINIMUM), CRUSHED LIMEROCK 2 1/2 INCHES IN DIAMETER. SAID BLANKET SHALL BE UNDERLAIN WITH A FDOT CLASS 3 SYNTHETIC FILTER FABRIC AND MAINTAINED IN GOOD ORDER.

9. AT THE TIME WHEN THE SITE PREPARATION FOR PERMANENT VEGETATIVE STABILIZATION IS GOING TO BE ACCOMPLISHED, ANY SOIL THAT WILL NOT PROVIDE A SUITABLE ENVIRONMENT TO SUPPORT ADEQUATE VEGETATIVE GROUND COVER, SHALL BE REMOVED OR TREATED IN SUCH A WAY THAT WILL PERMANENTLY ADJUST THE SOIL CONDITIONS AND RENDER IT SUITABLE FOR VEGETATIVE GROUND COVER, IF THE REMOVAL OR TREATMENT OF THE SOIL WILL NOT PROVIDE

*10. CONDUIT OUTLET PROTECTION MUST BE INSTALLED AT ALL REQUIRED OUTFALLS PRIOR TO THE DRAINAGE

SUITABLE CONDITIONS, NON-VEGETATIVE MEANS OF PERMANENT GROUND STABILIZATION WILL HAVE TO BE

SYSTEM BECOMING OPERATIONAL. 11. UNFILTERED DEWATERING IS NOT PERMITTED. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS

DURING ALL DEWATERING OPERATIONS TO MINIMIZE SEDIMENT TRANSFER.

12. SHOULD THE CONTROL OF DUST AT THE SITE BE NECESSARY, THE SITE WILL BE SPRINKLED UNTIL THE SURFACE IS WET, TEMPORARY VEGETATION COVER SHALL BE ESTABLISHED OR MULCH SHALL BE APPLIED IN ACCORDANCE WITH STATE STANDARDS FOR EROSION CONTROL.

13. ALL SOIL WASHED, DROPPED, SPILLED OR TRACKED OUTSIDE THE LIMIT OF DISTURBANCE OR ONTO PUBLIC RIGHTS-OF-WAY WILL BE REMOVED IMMEDIATELY.

14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY EROSION OR SEDIMENTATION THAT MAY OCCUR BELOW STORMWATER OUTFALLS OR OFFSITE AS A RESULT OF CONSTRUCTION OF THE PROJECT.

15. ALL SOIL STOCKPILES ARE TO BE TEMPORARILY STABILIZED IN ACCORDANCE WITH SOIL EROSION AND SEDIMENT CONTROL NOTE NUMBER 2 (ABOVE).

16. THE SITE SHALL AT ALL TIMES BE GRADED AND MAINTAINED SUCH THAT ALL STORM WATER RUNOFF IS DIVERTED TO SOIL EROSION AND SEDIMENT CONTROL FACILITIES.

17. ALL SEDIMENTATION STRUCTURES SHALL BE INSPECTED AND MAINTAINED REGULARLY.

18. ALL CATCH BASIN INLETS SHALL BE PROTECTED WITH HAY BALES AS SHOWN ON DETAIL

19. THE CONTRACTOR SHALL PREPARE A PLAN FOR THE PROPER DEWATERING AND DOWNSTREAM SILTATION PROTECTION OF EACH STREAM CROSSING PRIOR TO EXCAVATING THE STREAM BED. PLAN SHALL BE FORWARDED TO THE ENGINEER FOR APPROVAL. THE ENGINEER SHALL BE NOTIFIED FOR INSPECTION PRIOR TO EACH STREAM CROSSING CONSTRUCTION.

20. ANY AREAS USED FOR THE CONTRACTOR'S STAGING, INCLUDING BUT NOT LIMITED TO, TEMPORARY STORAGE OF STOCKPILED MATERIALS (E.G. CRUSHED STONE, QUARRY PROCESS STONE, SELECT FILL, EXCAVATED MATERIALS, ETC.), SHALL BE ENTIRELY PROTECTED BY A SILT FENCE ALONG THE LOW ELEVATION SIDE TO CONTROL SEDIMENT RUNOFF.

21. SAG FILTERS IN CURB THROATS ARE NOT AN ALLOWABLE SEDIMENT CONTROL METHOD.

* WHERE APPLICABLE

TEMPORARY SEEDING DETAILS:

SEED BED PREPARATION:

SOIL TO BE THOROUGHLY PULVERIZED BY DISK-HARROWING AND BE LOOSE AND REASONABLY SMOOTH. APPLY FERTILIZER AT A RATE OF 260 LBS/ACRE OF 16-16-16 OR EQUIVALENT, APPLY DOLOMITIC LIMESTONE AT A RATE OF 800 TO 1000 LBS./ACRE TO PROVIDE A SOIL pH OF 5.5 TO 6.5, LIME & FERTILIZER TO BE WORKED INTO THE TOPSOIL TO A DEPTH OF 4". ADD SANDY LOAM TOPSOIL TO A MINIMUM OF TWO (2) INCHES WHERE

CONSISTING OF ANNUAL RYE (LOLIUM MULTIFLORUM) AT A RATE OF 174 LBS/ACRE.

PERMANENT SEEDING DETAILS:

SEED BED PREPARATION:

SOIL TO BE THOROUGHLY PULVERIZED BY DISK-HARROWING AND BE LOOSE AND REASONABLY SMOOTH. APPLY FERTILIZER AT A RATE OF 260 LBS/ACRE OF 16-16-16 OR EQUIVALENT, APPLY DOLOMITIC LIMESTONE AT A RATE OF 800 TO 1000 LBS./ACRE TO PROVIDE A SOIL pH OF 5.5 TO 6.5, LIME & FERTILIZER TO BE WORKED INTO THE TOPSOIL TO A DEPTH OF 4". ADD SANDY LOAM TOPSOIL TO A MINIMUM OF TWO (2) INCHES WHERE REQUIRED.

SEED MIXTURE CONSISTING OF <u>GERMINATION</u> 95% ARGENTINE BAHIA 260 LBS/AC. 80% PENSACOLA BAHIA 260 LBS/AC. 95% 40%(MIN.)-80%(TOTAL)

SOD SHALL BE WELL ROOT MATTED CENTIPEDE OR BAHIA GRASS COMMERCIALLY CUT TO A MINIMUM DIMENSION OF 12" x 24" A MAXIMUM OF 72 HOURS PRIOR TO PLACEMENT. SOD SHALL BE LIVE, FRESH AND UNINJURED, REASONABLY FREE OF WEEDS AND OTHER GRASSES, WITH A HEAVY SOIL MAT ADHERING TO THE ROOT SYSTEM. SOD SHALL BE GROWN, CUT, AND SUPPLIED BY A STATE CERTIFIED GROWER.

TRAFFIC CONTROL STANDARDS:

1. CONSTRUCTION TRAFFIC SHALL BE RESTRICTED TO ONSITE ACCESS BY MEANS SO DESIGNATED BY THE ENGINEER, POLICE/SHERIFF DEPARTMENT, ESCAMBIA COUNTY HIGHWAY DEPARTMENT, AND/OR THE FLORIDA

2. TRAFFIC DURING WET WEATHER SHALL BE MINIMIZED AND APPROPRIATE ROADWAY AND SITE CLEAN-UP SHALL BE PROVIDED BY THE CONTRACTOR AS SOON AS WEATHER CONDITIONS PERMIT.

TREE PROTECTION:

1. DAMAGED TRUNKS OR EXPOSED ROOTS WILL BE PAINTED IMMEDIATELY WITH A GOOD GRADE OF "TREE

2. TREE LIMB REMOVAL, WHERE NECESSARY, WILL BE DONE FLUSH TO TRUNK OR MAIN BRANCH AND THAT AREA PAINTED IMMEDIATELY WITH A GOOD GRADE OF TREE PAINT.

1. ALL AREAS OF CLEARING AND EMBANKMENT AS WELL AS CONSTRUCTION HAUL ROADS SHALL BE TREATED AND M INTAINED IN SUCH A MANNER AS TO MINIMIZE ANY DUST GENERATION.

2. DIST JRBED AREAS SHALL BE MAINTAINED IN A ROUGH GRADED CONDITION AND TEMPORARILY SEEDED AND/O MULCHED UNTIL PROPER WEATHER CONDITIONS EXIST FOR THE ESTABLISHMENT OF PERMANENT VEGETA ION COVER.

3. IN EVENT OF EMERGENCY CONDITIONS, TILLAGE WILL BE SATISFACTORY FREE BEFORE SOIL BLOWING STARTS.

4. CAL IUM CHLORIDE MAY BE APPLIED TO UNPAVED ROADWAY AREAS, ONLY, SUBJECT TO THE ENGINEER'S APPRO'AL AND CONFORMANCE WITH FDOT STANDARD SPECIFICATIONS, SECTION 102-5, LATEST EDITION.

PROPOSED SEQUENCE OF CONSTRUCTION:

1. THE INSTALLATION OF ALL SEDIMENT AND EROSION CONTROL DEVICES THAT CAN BE PLACED PRIOR TO ANY MAJOR SOIL DISTURBANCES.

2. CLE R AND REMOVE ALL EXISTING VEGETATION IN THOSE AREAS WHERE NECESSARY. ALL REMAINING VEGETA ION IS TO BE PROPERLY PROTECTED AND IS TO REMAIN IN ITS NATURAL STATE, TOPSOIL IN AREAS TO BE DIS URBED IS TO BE STRIPPED TO A MINIMUM DEPTH OF SIX (6) INCHES AND STOCKPILED SEPARATELY FROM | ROM OTHER EXCAVATED SOIL(S)

3. THE IMMEDIATE INSTALLATION OF ALL REMAINING SEDIMENT AND EROSION CONTROL DEVICES.

4. PER ORM ALL DEMOLITION WORK.


5. CON STRUCT ALL UNDERGROUND UTILITIES AND STORM DRAIN SYSTEMS.

6. CON TRUCT ROADS (SUBGRADE, CURB & GUTTER, BASE, PAVEMENT, SIDEWALKS AND LANDSCAPING).

7. CON PLETE STORMWATER PONDS.


8. UPC \ THE COMPLETION OF THE CONSTRUCTION ACTIVITIES, PROVIDE RESTORATION, FINE GRADE REMAINDER OF SITI, RESPREAD STOCKPILED TOPSOIL AND STABILIZE WITH PERMANENT VEGETATIVE COVER AND LANDSC APING.

9. THE REMOVAL OF APPROPRIATE TEMPORARY SEDIMENT AND EROSION CONTROL DEVICES.



STABILIZED CONSTRUCTION **ENTRANCE DETAIL**

N.T.S.



ALL PROTECTED TREES AS SHOWN ON THE PLANS TO REMAIN ARE TO BE PROTECTED DURING CONSTRUCTION. THE CONTRACTOR SHALL INSTALL ORANGE CONSTRUCTION FENCING AT THE DRIP LINE OF EACH PROTECTED TREE BEFORE WORKING IN THE VICINITY OF THE TREE.


TREE BARRICADE DETAIL N.T.S.

DESCRI TION:
FILTER 3AGS WILL BE USED AS AN EFFECTIVE FILTER MEDIUM TO CONTAIN SAND, SILT AND FI IES WHEN TRENCH DEWATERING. THE WETLAND FILTER BAG CONTAINS THESE MATERI/ LS WHILE ALLOWING THE WATER TO FLOW THROUGH THE FABRIC.

WETLAN) FILTER BAGS MAY REPLACE HAY BALE CORRALS DURING TRENCH DEWATERING, AT THE DISCRETION OF THE ENGINEER INSPECTOR. TO INSURE PROPER INSTALLATION, FILTER 3AGS WILL BE PLACED ON RELATIVELY FLAT TERRAIN FREE OF BRUSH AND STUMP: TO AVOID RUPTURES AND PUNCTURES. PROPER INSTALLATION REQUIRES CUTTINI A SMALL HOLE IN THE CORNER OF THE BAG, INSERTING THE PUMP DISCHARGE HOSE, AND THEN SECURING THE DISCHARGE HOSE TO THE BAG WITH A HOSE CLAMP. FILTER 3AGS WILL BE PLACED AS FAR AWAY FROM FLOWING STREAMS AND WETLANDS

MAINTE ANCE:
PRIOR O REMOVING A BAG FROM THE HOSE, THE BAG WILL BE TIED OFF BELOW THE END OF THE HOSE ALLOWING THE BAG TO DRAIN. DRAINAGE WILL NOT BE ALLOWED THROUGH THE INLET HOLE. TO AVOID RUPTURE, THE BAGS WILL BE ATTENDED AND PUMPIN 3 RATES MONITORED. ONCE THE BAG IS INFLATED TO A HEIGHT OF 4 FEET, PUMPIN 3 WILL STOP TO AVOID RUPTURE. FILTER BAGS USED DURING CONSTRUCTION WILL B BUNDLED AND REMOVED FOR PROPER DISPOSAL.

FILTER BAGS ARE CONSTRUCTED OF NON-WOVEN GEOTEXTILE FABRIC. A MAXIMUM OF ONE SI (INCH DISCHARGE HOSE WILL BE ALLOWED PER FILTER BAG. BAG CAPACITY WILL B EXCEEDED BEYOND 2,000 GALLONS PER MINUTE, TYPICAL BAG DIMENSIONS ARE 1: FEET BY 13.25 FEET. TO HELP PREVENT PUNCTURES, GEOTEXTILE FABRIC WILL BE PLACED BENEATH THE FILTER BAG WHEN USED IN WOODED LOCATIONS. UNATTENDED FILTER 3AGS WILL BE ENCIRCLED WITH A HAY BALE OR SILT FENCE CORRAL. HOSE CLAMPS WILL BE USED TO SECURE THE DISCHARGE HOSE, WIRE OR STRING WILL NOT



ANCHOR BALES WITH

STAKES PER BALE.

(2)-2"X2"X4'-

ELEVATION

TO BE USED AT SELECTED SITES WHERE THE NATURAL GROUND SLOPES TOWARD THE TOE OF SLOPE

ELEVATION

GROUND SLOPES AWAY FROM THE TOE OF SLOPE

TO BE USED AT SELECTED SITES WHERE THE NATURAL

BARRIERS FOR FILL SLOPES

N.T.S.

PLAN VIEW

CROSS SECTION

FILTER BAG DETAIL FOR

TRENCH DEWATERING OPERATIONS

FILTER BAG-

GROUND

SURFACE

FILTER

ANCHOR BALES WITH

LOOSE SOIL PLACED BY

COMPACTED ALONG THE

UPSTREAM EDGE OF BALES.

FILTER BAG

-HOSE CLAMP

-HOSE CLAMP

-WOODEN STAKES

PUMP DISCHARGE

-WOODEN STAKES

HOSE


PUMP DISCHARGE


-SET ON FILTER BAG


SHOVEL AND LIGHTLY

STAKES PER BALE.

-(2)-2"X2"X4'







2"x4" OR 3"Ø TREATED


-TIMBER POST @ 6' O.C.

(TYPICAL)


SILT FENCE DETAIL N.T.S.

AROUND DITCH BOTTOM INLETS. SILT FENCE APPLICATIONS

DO NOT DEPLOY IN A MANNER THAT SILT FENCES WILL ACT AS A DAM ACROSS PERMANENT FLOWING WATERCOURSES. SILT FENCES ARE TO BE USED AT UPLAND LOCATIONS AND TURBIDITY BARRIERS USED AT PERMANENT BODIES OF WATER.



STRAW BALES BACKED BY FENCE N.T.S.





STRAW BALE DETAIL

LOOSE SOIL PLACED BY SHOVEL

-AND LIGHTLY COMPACTED ALONG

THE UPSTREAM EDGE OF BALES.





ELEVATION

APPLICATION AND SPACING: THE USE OF TYPES I & II BALE BARRIERS SHOULD BE LIMITED TO THE CONDITIONS OUTLINED IN CHART I, SHEET 1 OF 3, INDEX NO. 102

WOVEN FILTER FABRIC IN ABSENCE OF

ESTABLISHED GRASS (APPROX. 12' X 12').

SECURE EDGES BY ENTRENCHING AND EXTEND UNDER BAGS AND BALES. FABRIC

SHALL MEET THE REQUIREMENTS OF

SECTION 985 OF THE STANDARD

SPECIFICATIONS. COST OF FABRIC TO BE


FOR BALED HAY OR STRAW, TN.

LOOSE SOIL PLACED BY SHOVEL


-AND LIGHTLY COMPACTED ALONG

NCLUDED IN THE CONTRACT UNIT PRICE


TYPE II TYPE I BARRIER FOR UNPAVED DITCH





BALE BARRIERS FOR PAVED DITCHES SHOULD BE SPACED IN ACCORDANCE WITH CHART I, SHEET 1 OF 3, INDEX NO. 102 BARRIER FOR PAVED DITCH N.T.S.



MATERIAL STOCKPILE DETAIL







PROTECTION AROUND INLETS OR SIMILAR STRUCTURES

ANCHOR BALES WITH (2)-2"x2"x4' STAKES PER BALE.

S EROSION





Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022

SHEET 2 OF 25

STORM WATER POLLUTION PREVENTION PLAN

1.0 BACKGROUND & REQUIREMENTS:

1.1 INTRODUCTION:

THE REFERENCED SUPPORT DOCUMENTATION FOR THIS STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS THE UNITED STATES ENVIRONMENTAL PROTECTION AGENCY'S (EPA) STORM WATER MANAGEMENT FOR CONSTRUCTION ACTIVITIES, DEVELOPING POLLUTION PREVENTION PLANS AND BEST MANAGEMENT PRACTICES SUMMARY GUIDANCE (EPA 833-R-92-001) AND STORM WATER MANAGEMENT FOR CONSTRUCTION ACTIVITIES, DEVELOPING POLLUTION PREVENTION PLANS AND BEST MANAGEMENT PRACTICES (EPA 832-R-92-005). THIS SWPPP IS DESIGNED TO PROTECT ONSITE AND ADJACENT NATURAL RESOURCES, INCLUDING BUT NOT LIMITED TO, WETLANDS, MARSHES, BAYOUS AND BAYS, WHILE PRESERVING WILDLIFE AND ARCHEOLOGICAL RESOURCES.

AN ENVIRONMENTAL RESOURCE PERMIT APPLICATION WILL BE SUBMITTED NWFWMD DECEMBER 2021

1.2 NOTICE OF INTENT (NOI):

RULE 62-621.300(4), FAC REQUIRES THE CONSTRUCTION OPERATOR OF A SITE THAT DISTURBS ONE OR MORE ACRES TO OBTAIN COVERAGE FROM THE GENERIC PERMIT FOR STORMWATER DISCHARGE FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES. THE CONTRACTOR IS REQUIRED TO SUBMIT A NOTICE OF INTENT TO USE GENERIC PERMIT FOR STORMWATER DISCHARGE FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES (FDEP FORM 62-621.300(4)(B)) ALONG WITH THE APPROPRIATE APPLICATION FEE TO THE FOLLOWING ADDRESS 48 HOURS PRIOR TO COMMENCING CONSTRUCTION:

> NPDES STORMWATER NOTICES CENTER, MS # 2510 FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION 2600 BLAIR STONE ROAD TALLAHASSEE, FLORIDA 32399-2400

THIS FORM CAN BE OBTAINED FROM FDEP'S WEBSITE (WWW.DEP.STATE.FL.US) OR BY CONTACTING FDEP. PLEASE NOTE THAT THE CURRENT APPLICATION FEE IS \$300; HOWEVER, THIS FEE IS SUBJECT TO CHANGE WITHOUT NOTICE. ALWAYS REFER TO THE MOST CURRENT VERSION OF RULE 62-4.050(4)(D), FAC TO CONFIRM THE AMOUNT BEFORE SUBMITTING PAYMENT. IF CONSTRUCTION ACTIVITY EXCEEDS FIVE YEARS, THE CONTRACTOR MUST RE-APPLY FOR COVERAGE.

1.3 STORMWATER POLLUTION PREVENTION PLAN (SWPPP):

THE CONTRACTOR IS REQUIRED TO CERTIFY THIS STORMWATER POLLUTION PREVENTION PLAN (SWPPP) BELOW PRIOR TO SUBMITTING THE NOI. THIS SWPPP IS NOT REQUIRED TO BE SUBMITTED WITH THE NOI, BUT IS REQUIRED TO BE KEPT ON SITE DURING ALL PHASES OF CONSTRUCTION. BECAUSE EROSION AND SEDIMENT CONTROLS AND CONSTRUCTION METHODS VARY SIGNIFICANTLY FROM CONTRACTOR TO CONTRACTOR, THE CONTRACTOR CAN PROPOSE ALTERNATIVE METHODS TO THIS SWPPP THAT ARE EQUAL OR BETTER AT CONTROLLING EROSION AND SEDIMENTATION. AT A MINIMUM, THE CONTRACTOR MUST FOLLOW THE EROSION CONTROL PLAN SPECIFIED IN THE CONSTRUCTION PLANS AND DOCUMENTS. ANY MODIFICATIONS TO THIS SWPPP MUST BE DOCUMENTED AND KEPT WITH THE PLAN AS PART OF THE RECORDS KEEPING PROCESS TO BE IN FULL COMPLIANCE WITH THE CGP.

1.4 CONTRACTOR'S / SUBCONTRACTOR CERTIFICATION:

I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND, AND SHALL COMPLY WITH, THE TERMS AND CONDITIONS OF THE STATE OF FLORIDA GENERIC PERMIT FOR STORMWATER DISCHARGE FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES AND THIS STROMWATER POLLUTION PREVENTION

| PRINT & SIGN NAME | _ | COMPANY & ADDRES |
|----------------------|------|------------------|
| NAME & TITLE (PRINT) | | |
| SIGNATURE | DATE | |

1.5 RESPONSIBLE AUTHORITY CERTIFICATION:

SIGNATURE

I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL GATHERED AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS.

| COMPANY & ADDRESS |
|-------------------|
| |
| |

DATE

1.6 NOTICE OF TERMINATION (NOT):

THE CONTRACTOR IS REQUIRED TO SUBMIT A NOTICE OF TERMINATION OF GET ERIC PERMIT COVERAGE (FDEP FORM 62-621.300(6)) UPON CONSTRUCTION COMPLETION TO DISCONTINUE PERMIT COVERAGE. THE NOT IS 'O BE SUBMITTED TO THE FOLLOWING ADDRESS:

NPDES STORMWATER NOTICES CENTER, MS # 2510 FLC RIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION 26(O BLAIR STONE ROAD TAL AHASSEE, FLORIDA 32399-2400

THIS FORM CAN BE OBTAINED FROM FDEP'S WEBSITE (WWW.DEP.STATE.FL.US) OR BY CONTACTING FDEP. THE NOT CAN NOT BE SUBMITTED UNTIL ALL DIS URBED SOILS AT THE CONSTRUCTION SITE HAVE BEEN FINALLY STABILIZED AND TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES HA'E BEEN REMOVED OR WILL BE REMOVED AT AN APPROPRIATE TIME. FIN L STABILIZATION MEANS THAT ALL SOIL DISTURBING ACTIVITIES AT THE SIT : HAVE BEEN COMPLETED AND THAT A UNIFORM PERENNIAL VEGETATIVE CO'ER WITH A DENSITY OF 70 PERCENT OF THE COVER FOR UNPAVED ARIAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES HAS BEEN ESTABLISHED, OR EQUIVALENT STABILIZATION MEASURES HAVE BEEN EMI'LOYED. IF CONSTRUCTION ACTIVITY EXCEEDS FIVE YEARS, THE COLITRACTOR MUST RE-APPLY FOR COVERAGE.

1.7 APPLICATION INFORMATION:

| PROJECT ADDRESS: | 1940 W DETROIT BLVD PENSACOLA, FL |
|------------------|--------------------------------------|
| | |

N 30.520750° LAT TUDE: LONGITUDE: W 87.299309° NORTHWEST FLORIDA (NWFWMD) WA ER MANAGEMENT DISTRICT: ESCAMBIA COUNTY

2.0 SITE DESCRIPTION:

MS + OPERATOR NAME:

RECEIVING WATER NAME:

2.1 NATURE OF CONSTRUCTION ACTIVITIES:

THIS PROJECT INVOLVES THE CONSTRUCTION OF A 3 PHASE, 240 LOT RESIDENTIAL SUBDIVISION. CONSTRUCTION INCLUDES ROADWAYS, UTILITIES AND 3 SEPARATE STORMWATER COLLECTION/MANAGEMENT SYSTEMS.

PERDIDO BAY

2.2 SEQUENCE OF MAJOR SOIL DISTURBING ACTIVITIES:

THE FOLLOWING SEQUENCE OF MAJOR ACTIVITIES SHALL BE FOLLOWED UNLESS THE CONTRACTOR CAN PROPOSE AN ALTERNATIVE THAT IS EQUAL TO OR BETTER AT CONTROLLING EROSION AND SEDIMENTATION. THE DETAILED SEQUENCE FOR THE ENTIRE PROJECT CAN VARY SIGN IFICANTLY FROM CONTRACTOR TO CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR DOC JMENTING ANY CHANGES.

- 1. CLEAR, GRUB AND PERFORM ALL DEMOLITION WORK.
- 2. COMPLETE ROUGH GRADING OF THE POND AND DIRECT ALL STORMWATER RUNOFF TO THE PON)(S).
- 3. CONSTRUCT ALL UNDERGROUND UTILITIES AND STORM DRAIN SYSTEM.
- 4. CONSTRUCT ROADS (SUBGRADE, CURB & GUTTER, BASE, PAVEMENT, SIDEWALKS, AND LAN SCAPING).
- COMPLETE STORMWATER PONDS.

2.3 AREA ESTIMATES:

| ONSITE AREA: | 3.96 ACRES |
|------------------------|------------|
| OFI SITE AREA: | 0.61 ACRES |
| TO AL AREA: | 4.57 ACRES |
| ARI A TO BE DISTURBED: | 3.96 ACRES |
| | |

2.4 RUNOFF DATA:

RULIOFF COEFFICIENTS (C):

| BEFORE: | COMPOSITE C = | 0.30 |
|---------|------------------|-------------|
| DURING: | VARIES BETWEEN = | 0.30 & 0.62 |
| AFTER: | COMPOSITE C = | 0.62 |

SOI_S DATA: BEI EATH UP TO 24" OF TOPSOIL, THE TEST BORINGS GENERALLY ENCOUNTERED MIXED STRATA OF FINE-GRAINED SANDS, SLIGHTLY SILTY SAI DS. AND SILTY SANDS.

DR/ INAGE AREAS FOR EACH OUTFALL

| OU FALL LOCATION | TOTAL AREA FLOWING TO POND | 'C' COEFFICIENT |
|------------------|----------------------------|-----------------|
| PON) A | 4.57 AC | 0.65 |

2.5 SITE MAP:

THE CONSTRUCTION PLANS ARE TO BE USED AS THE SITE MAPS. THE LOCATION OF THE REQUIRED INFORMATION IS DESCRIBED BELOW. THE SHEET NUMBERS FOR ALL THE ITEMS DISCUSSED BELOW ARE IDENTIFIED ON THE KEY SHEET OF THE CONSTRUCTION PLANS.

- DRAINAGE PATTERNS: ALL DRAINAGE PATTERNS ARE SHOWN ON THE GRADING & DRAINAGE PLANS.
- APPROXIMATE SLOPES: APPROXIMATE SLOPES ARE SHOWN ON THE GRADING & DRAINAGE POND SIDE SLOPES ARE SHOWN ON THE POND CROSS-SECTIONS.
- AREAS OF SOIL DISTURBANCE: ALL DEMOLITION IS SHOWN ON THE EXISTING SITE CONDITIONS AND DEMOLITION AND EROSION CONTROL PLAN SHEET. ALL PROPOSED CONSTRUCTION IS SHOWN ON THE REMAINING PLANS. ANY AREAS WHERE DEMOLITION WORK OR PERMANENT FEATURES ARE SHOWN ABOVE OR BELOW GROUND WILL BE
- AREAS NOT TO BE DISTURBED: ANY AREAS NOT SHOWING DEMOLITION WORK OR PERMANENT FEATURES ARE ASSUMED NOT TO BE DISTURBED. IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO INDICATE ON THE PLANS ANY OF THESE AREAS THAT DO GET DISTURBED AS WELL AS ANY AREAS USED FOR STAGING AND MATERIALS STORAGE.
- LOCATIONS OF CONTROLS: ALL PROPOSED TEMPORARY CONTROLS AND EXISTING PERMANENT CONTROLS ARE SHOWN ON THE EXISTING SITE, DEMOLITION AND EROSION CONTROL PLAN. ALL PROPOSED PERMANENT CONTROLS ARE SHOWN ON THE REMAINING PLANS. IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO INDICATE THE LOCATION OF ANY OTHER CONTROLS ON THE PLANS THAT ARE USED DURING CONSTRUCTION.
- PERMANENT STABILIZATION IS SHOWN ON THE PLANS. IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO INDICATE THE LOCATION ON THE PLANS OF ALL TEMPORARY STABILIZATION PRACTICES USED DURING CONSTRUCTION.
- SURFACE WATERS: N/A

DISCHARGE POINTS: DETROIT BLVD R/W

2.6 RECEIVING WATERS:

PERDIDO BAY

3.0 CONTROLS

3.1 EROSION AND SEDIMENT CONTROLS:

ALL EROSION AND SEDIMENT CONTROLS SPECIFIED ON THE DEMOLITION AND EROSION CONTROL PLAN SHEETS, AND THE EROSION CONTROL DETAILS SHALL BE INSTALLED PRIOR TO ANY CONSTRUCTION OR DEMOLITION. SILT FENCING AND STAKED HAY BALES SHALL BE INSTALLED ALONG DOWN-GRADIENT LIMITS.

TEMPORARY SEEDING AND MULCHING SHALL BE APPLIED AFTER 14-DAY INTERVALS OF CEASED DISTURBANCE ACTIVITIES THAT WILL EXCEED 20-DAY PERIODS. GRADED AREAS SHALL BE STABILIZED WITH PERMANENT SEEDING, MULCHING, AND FERTILIZING, OR SODDING WITHIN FIVE DAYS OF FINAL GRADING. LANDSCAPING, INCLUDING SODDING, SHALL BE INSTALLED BY AN EXPERIENCED LANDSCAPE CONTRACTOR. PROPOSED DISTURBED AREAS WILL NOT EXCEED 8 ACRES IN ANY DRAINAGE AREA.

3.2 STORMWATER MANAGEMENT:

PROPOSED STORMWATER MANAGEMENT FACILITIES FOR THIS SITE INCLUDE: DRY RETENTION FACILITY.

THE PROPOSED STORMWATER MANAGEMENT FACILITIES MEET ALL STORMWATER TREATMENT REQUIREMENTS AND ALL RATE CONTROL REQUIREMENTS SET FORTH BY THE LOCAL AND STATE REGULATORY AGENCIES.

3.3 OTHER CONTROLS:

WASTE DISPOSAL: THE CONTRACTOR IS RESPONSIBLE FOR ALL WASTE DISPOSAL FROM THE SITE. THE CONTRACTOR SHALL EMPLOY WASTE DISPOSAL PRACTICES THAT MEET ALL LOCAL, STATE, AND FEDERAL GUIDELINES AND PREVENT DISCHARGE OF SOLID MATERIALS TO WATERS OF THE UNITED STATES. THE CONTRACTOR IS RESPONSIBLE FOR DOCUMENTING THIS PORTION OF THE SWPPP.

OFFSITE VEHICLE TRACKING: IF OFF SITE TRACKING OF SEDIMENTS BY CONSTRUCTION VEHICLES OCCURS, THE CONTRACTOR IS REQUIRED TO INSTALL A SOIL TRACKING PREVENTION DEVICE (STPD) AS PER FDOT STANDARD INDEX 106 AT ALL EXITS TO THE SITE WHERE SEDIMENT TRACKING IS OCCURRING. THE CONTRACTOR IS ALSO RESPONSIBLE FOR DOCUMENTING THIS PORTION OF THE SWPPP.

HAZARDOUS MATERIALS: ALL POLLUTANTS AND HAZARDOUS MATERIALS INCLUDING BUT NOT LIMITED TO FERTILIZERS, HERBICIDES, PESTICIDES, SOLVENTS, OILS AND OIL FILTERS, PETROLEUM PRODUCTS, PAINT, AND EQUIPMENT MAINTENANCE FLUIDS, SHALL BE STORED INDOORS OR UNDER COVER IN AREAS WITH SECONDARY CONTAINMENT. SECONDARY CONTAINMENT PREVENTS A SPILL FROM SPREADING ACROSS THE SITE AND INCLUDES DIKES, BERMS, CURBING, OR OTHER CONTAINMENT METHODS. HAZARDOUS MATERIAL STORAGE AREAS SHALL BE INSPECTED WEEKLY AND AFTER STORM EVENTS. STORAGE AREAS SHALL BE KEPT CLEAN, WELL ORGANIZED, AND EQUIPPED WITH AMPLE CLEANUP SUPPLIES/SPILL KITS AS APPROPRIATE FOR THE MATERIALS BEING STORED. MATERIAL SAFETY DATA SHEETS, MATERIAL INVENTORY, AND EMERGENCY CONTACT INFORMATION SHALL BE MAINTAINED ON-SITE. ALL PERSONNEL SHALL RECEIVE INSTRUCTION REGARDING PROPER PROCEDURES FOR HAZARDOUS MATERIAL HANDLING AND DISPOSAL. HAZARDOUS MATERIALS SHALL NOT BE DISPOSED OF INTO ON-SITE DUMPSTERS; HAZARDOUS MATERIALS SHALL BE DISPOSED OF IN ACCORDANCE WITH FEDERAL, STATE, AND MUNICIPAL REGULATIONS. VEHICLES AND EQUIPMENT WILL BE MAINTAINED OFF-SITE. ALL VEHICLES AND EQUIPMENT INCLUDING SUBCONTRACTOR VEHICLES WILL BE CHECKED FOR LEAKING OIL AND FLUIDS. VEHICLES LEAKING FLUIDS WILL NOT BE ALLOWED ON-SITE. DRIP PANS SHALL BE PLACED UNDER ALL VEHICLES AND FOUIPMENT THAT ARE PARKED OVERNIGHT.

APPLICATION OF FERTILIZERS, HERBICIDES, AND PESTICIDES: FERTILIZERS, HERBICIDES, AND PESTICIDES SHALL BE DELIVERED TO THE SITE IN ORIGINAL UNOPENED CONTAINERS BEARING MANUFACTURER'S CHEMICAL ANALYSIS, NAME, TRADE NAME, TRADEMARK, AND INDICATION OF CONFORMANCE TO STATE AND FEDERAL LAWS. FERTILIZERS, HERBICIDES, AND PESTICIDES SHALL BE IN APPLIED IN ACCORDANCE WITH THE MANUFACTURER'S SUGGESTED

5.0 INSPECTIONS:

QUALIFIED PERSONNEL SHALL INSPECT THE FOLLOWING ITEMS, BUT NOT LIMITED TO, AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.25 INCHES OR GREATER. WHERE SITES HAVE BEEN FINALLY STABILIZED, INSPECTIONS SHALL BE CONDUCTED AT LEAST ONCE EVERY MONTH.

- POINTS OF DISCHARGE TO WATERS OF THE UNITED STATES.
- POINTS OF DISCHARGE TO MUNICIPAL SEPARATE STORM SEWER DISTURBED AREAS OF THE SITE THAT HAVE NOT BEEN FINALLY

STABILIZED. AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION.

- STRUCTURAL CONTROLS.
- STORMWATER MANAGEMENT SYSTEMS. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE.

6.0 NON-STORMWATER DISCHARGES:

THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPORTING ANY HAZARDOUS SUBSTANCE SPILLS THAT MAY EQUAL OR EXCEED A REPORTABLE QUANTITY (RQ). REFER TO EPA'S LIST OF HAZARDOUS SUBSTANCES AND REPORTABLE QUANTITIES (EPA 40 CFR 302.4 & 117). V THIS LIST CAN BE OBTAINED FROM EPA'S WEBSITE (WWW.EPA.GO) OR BY CONTACTING EPA. IF AN RQ RELEASE DOES OCCUR THE CONTRACTOR SHALL PERFORM THE FOLLOWING

 NOTIFY THE NATIONAL RESPONSE CENTER IMMEDIATELY AT 800-424-8802. PROVIDE WRITTEN DESCRIPTION OF THE RELEASE WITHIN 14 DAYS PROVIDING DATES, CAUSE AND PREVENTION METHODS TO THE REGIONAL MODIFY THE SWPPP AS NECESSARY TO ADDRESS ADDED PREVENTION

7.0 IMPLEMENTATION CHECKLIST:

7.1 RECORDS:

METHODS.

THE CONTRACTOR SHALL MAINTAIN RECORDS OF CONSTRUCTION ACTIVITIES INCLUDING, BUT NOT LIMITED TO:

- DATES WHEN MAJOR GRADING ACTIVITIES OCCUR.
- DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY CEASE ON A PORTION OF THE SITE. DATES WHEN CONSTRUCTION ACTIVITIES PERMANENTLY CEASE ON A
- PORTION OF THE SITE. DATES WHEN STABILIZATION MEASURES ARE INITIATED ON THE SITE.

7.2 INSPECTION REPORTS:

THE CONTRACTOR SHALL PREPARE INSPECTION REPORTS SUMMARIZING THE FOLLOWING, BUT NOT LIMITED TO:

- NAME OF INSPECTOR.
- QUALIFICATIONS OF INSPECTOR.
- MEASURES/AREAS INSPECTED. OBSERVED CONDITIONS.
- CHANGES NECESSARY TO THE SWPPP.

7.3 RELEASES OF REPORTABLE QUANTITIES OF OIL OR HAZARDOUS MATERIALS:

THE CONTRACTOR SHALL REPORT ANY RELEASES OF REPORTABLE QUANTITIES OF OIL OR HAZARDOUS MATERIALS IF THEY OCCUR AS PER THE MEASURES OUTLINED IN SECTION 6.0 OF THE SWPPP.

7.4 SWPPP MODIFICATION:

THE CONTRACTOR SHALL MODIFY THE SWPPP AS NECESSARY TO:

 COMPLY WITH MINIMUM PERMIT REQUIREMENTS WHEN NOTIFIED BY FDEP THAT THE PLAN DOES NOT COMPLY. ADDRESS ANY CHANGES IN DESIGN, CONSTRUCTION OPERATIONS OR MAINTENANCE, WHICH HAS AN EFFECT ON THE POTENTIAL FOR DISCHARGE OF POLLUTANTS. PREVENT REOCCURRENCE OF REPORTABLE QUANTITY RELEASES OF HAZARDOUS MATERIAL OR OIL.

8.0 TERMINATION CHECKLIST

THE FOLLOWING ITEMS SHALL BE COMPLETE BEFORE SUBMITTING THE NOT:

 ALL SOIL DISTURBING ACTIVITIES ARE COMPLETE. TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES HAVE BEEN REMOVED OR WILL BE REMOVED AT AN APPROPRIATE TIME. ALL AREAS OF THE CONSTRUCTION SITE NOT OTHERWISE COVERED BY PERMANENT PAVEMENT OR STRUCTURE HAVE BEEN STABILIZED WITH UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 70% OR EQUIVALENT MEASURES HAVE BEEN EMPLOYED.

B

ATE 0 (

wnhome ment Boulevard P L B Lot To evelop DETROIT BIA COUNTY

∓∢


1940 ESC/


NPD


NOT FOR CONSTRUCTIO No. 53126


Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022


SHEET 3 OF 25


















BORING SOIL





Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022 DRAWING No.


SHEET 4 OF 25

SUMMARY OF CLASSIFICATION & INDEX TESTING

Detroit Townhomes Escambia County, Florida


NOVA Project No. 10116-2021075

| | SUMMARY OF CLASSIFICATION AND INDEX TESTING | | | | | |
|--------|---|--------------|-----------------------------|-----------------------------|------------------------|----|
| Boring | | | Percent | Ну | USCS | |
| No. | Depth (ft. BEG) | (0() (#000) | K _{vs} (ft/day) | Unit Weight of Sample (pcf) | Soil Classification | |
| A-1 | 1-4 | 8 | 18 | _ | | SM |
| R-1 | 3-6 | 18 | 21 | - | <u> </u> | SC |
| R-2 | 1.5-3.5 | 10 | 19 | <0.1 | 121 | SM |
| R-3 | 5-10 | 26 | 73 | - | <u>-</u> | CL |
| R-3 | 12-15 | 18 | 35 | <0.1 | 125 | SC |



NOVA

Lab Summary - Page 1 of 1





BORING SOIL


HIGHLAND RIDGE
A 40 Lot Townhome
Development
1940 W DETROIT BOULEVARD
ESCAMBIA COUNTY, FLORIDA

No. 53126

Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022

DRAWING No.

SHEET 5 OF 25



SITE LAYOUT

Lot Town

velopme


ETROIT BOU 940 W


NOT FOR CONSTRUCTION No. 53126 STATE OF FLORIDA. Paul A. Battle, P.E.


Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022

DRAWING No.


SHEET 6 OF 25








[] • F.D.O.T. TYPE III-A REFLECTIVE SHEETING TO BE USED ON ALL STREET NAME SIGN BLADES. STREET NAME SIGN BLADES TO HAVE WHITE LEGENDS. 1/2" WHITE BORDERS AND GREEN BACKGROUND •PRIMARY LETTERING TO SERIES B, 6" UPPER CASE AND 4 1/2" LOWER CASE. •PREFIX AND SUFFIX LETTERING TO BE SERIES C, 2 1/2" UPPER CASE AND 1 3/4" LOWER CASE.



ESCAMBIA COUNTY STANDARD DETAILS FOR STREET NAME SIGNS

DEPARTMENT OF ENGINEERING - TRAFFIC ENGINEERING DIVISION Suite 1, 1190 West Leonard Street, Pensacola, Florida 32501-1116

BY: Alan Thedford, Engineering Technician III Revised 6-2002 * NOT TO SCALE *




1. ALL CURB TO HAVE DUMMY JOINT AT 10' ON CENTER. MIN. DEPTH OF JOINT TO BE 2".

2. EXPANSION JOINTS ARE TO BE 30' ON CENTER. TYPICAL FOR ALL CURB.

3. ALL CONCRETE SHALL BE 3000 psi AT 28 DAYS.

LAYBACK CURB & GUTTER N.T.S.



1. ALL CURB TO HAVE DUMMY JOINT AT 10' ON CENTER. MIN. DEPTH OF JOINT TO BE 2".

2. EXPANSION JOINTS ARE TO BE 30' ON CENTER. TYPICAL FOR ALL CURB.

12" RIBBON CURB

N.T.S.

NOT FOR CONSTRUCTION 6-29-2021: STATE OF FLORIDA . Dr. By: CBD


SEAL

SITE LAYOUT &

Developme 1940 W DETROIT BOU ESCAMBIA COUNTY, I

Ck By: PAB Job No.: 2021.006 Date: 6/29/2022 DRAWING No.


SHEET 7 OF 25



BOB 00

NOT FOR CONSTRUCTION LICENSE STATE OF PauDA Battle, P.E.

Job No.: 2021.006 Date: 6/29/2022



ETAIL

DRAINAGE ంర GRADING


A 40 Lot Tow Developm 1940 W DETROIT BC ESCAMBIA COUNTY


SEALI NOT FOR CONSTRUCTION LICENSE No. 53126 e Bathe 26TATE OF FLORIDA. N6!58126 Dr. By: CBD Ck By: PAB Job No.: 2021.006


Date: 6/29/2022 DRAWING No.

C3.1 SHEET 9 OF 25

- 1.)IRT ROAD PATCH WORK SUB BASE MATERIAL SHALL BE PLACED IN NOT MORE THAN 3" LIFTS. EACH LAYER TO BE TAMPED TO A MINIMUM OF 40 LBR.
- 2. FRADED AGGREGATE BASE SHALL BE COMPACTED TO A MIN LBR 100.
- 3. ROAD CUTS SHALL BE MECHANICALLY SAW CUT TO FORM A SURFACE PAVEMENT JOINT AND TACK COATED ALONG THE FACE OF CUT JOINTS PRIOR TO ASPHALT PLACEMENT.
- 4. ONGITUDINAL ROAD CUTS THAT AFFECT ONE TRAVEL LANE SHALL REQUIRE MILLING AND REPAVING OF THE AFFECTED TRAVEL LANE 10.0' BEYOND THE CUT AND PATCHED WITH THE SAME BASE MATERIAL. LONGITUDINAL ROAD CUTS THAT AFFECT BOTH TRAVEL ANES SHALL REQUIRE MILLING AND REPAVING OF THE ENTIRE ROADWAY 10.0' BEYOND THE CUT AND PATCHED WITH THE SAME BASE MATERIAL.








NOTE:
THE ENTIRE BANK SLOPE SHALL BE SODDED IN A MANNER TO
GUARANTEE HEALTHY GRASS GROWTH (FREE FROM NOXIOUS WEEDS)
SUCH AS ST. AUGUSTINE, CENTIPEDE OR OTHER SUITABLE GRASS.

POND CROSS SECTION D1-D1


N.T.S.




THE ENTIRE BANK SLOPE SHALL BE SODDED IN A MANNER TO GUARANTEE HEALTHY GRASS GROWTH (FREE FROM NOXIOUS WEEDS) SUCH AS ST. AUGUSTINE, CENTIPEDE OR OTHER SUITABLE GRASS.

POND CROSS SECTION D2-D2

N.T.S.





TYPE 'D' OUTFALL STRUCTURE DI-70 DETAIL N.T.S.

POND No.1 DETAIL (PARCEL D)

REBOL-BATTLE & ASSOCIATE Civil Engineers and Surveyors

Civil Engineers and Surveyors

2301 N. Ninth Avenue, Suite 300
Pensacola, Florida 32503
Telephone 850.438.0400 Ex 850.438.0448

POND & DRAINAGE DETAILS

GHLAND RIDGE
40 Lot Townhome
Development

No. DATE REVISION
eproduced without written permission.

NOT FOR CONSTRUCTION
LICENS
No. 53126


No. 53126

Paul A Battle R.E.
No. 53126

Dr. By: CBD
Ck By: PAB
Job No.: 2021.006
Date: 6/29/2022

DRAWING No.

SHEET 10 OF 25




0 OND

A 40 Lot Tow Developm 1940 W DETROIT BO ESCAMBIA COUNTY

NOTFOR CONSTRUCTION STATE OF FLORIDA Paul A Battle P.E.

Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022

> DRAWING No. C3.3



| | LEGEND |
|--------------------------------|---------------------------------------|
| | EXISTING ASPHALT |
| | EXISTING CONCRETE |
| | EXISTING GRAVEL |
| | PROPOSED ASPHALT |
| | PROPOSED CONCRETE |
| | RIP RAP |
| | PUBLIC DRAINAGE/ACCESS EASEMENT |
| | PRIVATE DRAINAGE/ACCESS EASEMENT |
| 100 | EXISTING CONTOUR |
| 100 — | PROPOSED CONTOUR |
| | BOUNDARY LINE |
| | EASEMENT LINE |
| | RIGHT-OF-WAY LINE |
| FFE FINISHED FLOOR ELEVATION + | BENCHMARK |
| GFE GARAGE FLOOR ELEVATION | FLOW ARROW |
| ← 100.00 | PROPOSED SPOT ELEVATION |
| •─ 100.00 M.E. | PROPOSED SPOT ELEVATION MEET EXISTING |

100.00 (BACK OF CURB)

99.50 (EDGE OF PAVEMENT)

| STRUCTURES BY HOMEBUILDER | | | |
|-----------------------------|---------------|--------------------------------------|--|
| NAME | TOP ELEVATION | INVERTS | |
| CO-3 CLEANOUT | 90.20 | INV=88.04 (PD-7) | |
| CO-4 CLEANOUT | 87.85 | INV=85.34 (PD-8) | |
| YI-1 12" NYLOPLAST INLET | 92.50 | INV=90.50 (PD-1) | |
| YI-2 12" NYLOPLAST INLET | 92.50 | INV=90.26 (PD-1) INV=90.26 (PD-2) | |
| YI-3 12" NYLOPLAST INLET | 92.50 | INV=89.96 (PD-2) INV=89.86 (PD-3) | |
| Y1-4 12" NYLOPLAST INLET | 91.50 | INV=89.49 (PD-4) | |
| YI-5 12" NYLOPLAST INLET | 91.50 | INV=89.00 (PD-4) INV=89.00 (PD-5) | |
| YI-6 12" NYLOPLAST INLET | 91.50 | INV=88.40 (PD-5) INV=88.40 (PD-6) | |

| STRUCTUR | E2 BY HOME | BUILDER |
|-----------------------------|---------------|--------------------------------------|
| NAME | TOP ELEVATION | INVERTS |
| CO-3 CLEANOUT | 90.20 | INV=88.04 (PD-7) |
| CO-4 CLEANOUT | 87.85 | INV=85.34 (PD-8) |
| YI-1 12" NYLOPLAST INLET | 92.50 | INV=90.50 (PD-1) |
| YI-2 12" NYLOPLAST INLET | 92.50 | INV=90.26 (PD-1) INV=90.26 (PD-2) |
| YI-3 12" NYLOPLAST INLET | 92.50 | INV=89.96 (PD-2) INV=89.86 (PD-3) |
| YI-4 12" NYLOPLAST INLET | 91.50 | INV=89.49 (PD-4) |
| YI-5 12" NYLOPLAST INLET | 91.50 | INV=89.00 (PD-4) INV=89.00 (PD-5) |
| YI-6 12" NYLOPLAST INLET | 91.50 | INV=88.40 (PD-5) INV=88.40 (PD-6) |

| MAXIMUM LOT SURF, CE C | OVERAGE |
|--------------------------------------|-----------------------------------|
| ALL RESIDENTIAL LOTS AMENITY SITE | 1,500 SF (HOUSE & DRIVEWAY N/A |

| TOTAL IMPERVIOUS URFACE | |
|----------------------------|-------------------------------------|
| TOTAL NEW INFRAST RUCTURE | 30,620 SF (ROADWAY, SIDEWALK, CURB) |
| TOTAL IMPERVIOUS / REA FOR | |

POST DEVELOPMENT CONDITIONS 79,620 SF (NEW INFRASTRUCTURE, LOTS)

| Pipe Name | Length | Size | Slope | |
|-----------|--------|--------|-------|--|
| PD-1 | 48' | 8" PVC | 0.50% | |
| PD-2 | 60' | 8" PVC | 0.50% | |
| PD-3 | 60' | 8" PVC | 0.50% | |
| PD-4 | 49' | 8" PVC | 1.00% | |
| PD-5 | 60' | 8" PVC | 1.00% | |
| PD-6 | 60' | 8" PVC | 1.00% | |
| PD-7 | 170' | 8" PVC | 1.79% | |
| PD-8 | 178' | 8" PVC | 2.15% | |

5. DEVELOPER/CONTRACTOR/HOME OWNER'S ASSOCIATION SHALL RESHAPE PER PLAN SPECIFICATIONS, CLEAN OUT ACCUMULATED SILT, AND STABILIZE RETENTION/DETENTION POND(S) AT THE END OF CONSTRUCTION WHEN ALL DISTURBED AREAS HAVE BEEN STABILIZED AND AT THE END OF THE 2-YEAR WARRANTY PERIOD.

6. ON SITES > 1 ACRE, IF > CONTIGUOUS ACRE IS CLEARED, A GROUND COVER SUFFICIENT TO PREVENT EROSION SHOULD BE PLANTED OR OTHERWISE STABILIZED WITHIN 10 WORKING DAYS ON THAT PORTION OF THE SITE UPON WHICH FURTHER ACTIVE CONSTRUCTION WILL NOT BE UNDERTAKEN WITHIN 90 DAYS.

7. TO COMPLY WITH NPDES REQUIREMENTS, ALL EROSION CONTROL MEASURES SHALL BE INSPECTED AFTER EACH " RAINFALL OR AT LEAST WEEKLY. THE CONTRACTOR SHALL 12" RAINFALL OR AT LEAST WEEKLY. THE CONTRACTOR SHALL DOCUMENT SUCH INSPECTIONS AND EROSION CONTROL MAINTENANCE EFFORTS; INSPECTION RECORDS SHALL BE PROVIDED TO THE NPDES PERMIT APPLICANT FOR PROPER REPORTING TO FDEP/NWFWMD.

8. A HEALTHY GROWTH OF GRASS WITHIN DISTURBED RIGHT-OF-WAY AREAS IS REQUIRED PRIOR TO COUNTY APPROVAL/ACCEPTANCE (RIGHT-OF-WAY TO REMAIN PRIVATE). IF TIME CONSTRAINTS EXIST DURING THE FINAL PLAT APPROVAL AND ACCEPTANCE PROCESS, A MINIMUM OF TWO STRIPS OF SOD (MINIMUM 2' WIDE) BEHIND THE BACK OF CURB WITH ALL OTHER DISTURBED AREAS SEEDED/MULCHED/FERTILIZED WILL BE ACCEPTABLE.

9. ALL NEW BUILDING ROOF DRAINS, DOWN SPOUTS, OR GUTTERS SHALL BE ROUTED TO CARRY ALL STORMWATER TO RETENTION/DETENTION AREAS.

10. NO DEVIATIONS OR REVISIONS FROM THESE PLANS BY THE CONTRACTOR SHALL BE ALLOWED WITHOUT PRIOR APPROVAL FROM BOTH THE DESIGN ENGINEER AND THE ESCAMBIA COUNTY. ANY DEVIATIONS MAY RESULT IN DELAYS IN COUNTY ACCEPTANCE OF IMPROVEMENTS.

11. THE CONTRACTOR SHALL MAINTAIN RECORD DRAWINGS DURING CONSTRUCTION WHICH SHOW "AS-BUILT" CONDITIONS OF ALL WORK INCLUDING PIPING, DRAINAGE STRUCTURES, OUTLET STRUCTURES, DIMENSIONS, ELEVATIONS, GRADING, ETC. RECORD DRAWINGS SHALL BE PROVIDED TO THE ENGINEER OF RECORD PRIOR TO REQUESTING A FINAL INSPECTION.

12. ALL ASPECTS OF THE STORMWATER/DRAINAGE COMPONENTS AND/OR TRANSPORTATION COMPONENTS SHALL BE COMPLETED PRIOR TO REQUESTING A FINAL INSPECTION.

13. THE OWNER OR HIS AGENT SHALL ARRANGE/SCHEDULE WITH THE COUNTY A FINAL INSPECTION OF THE DEVELOPMENT UPON COMPLETION AND ANY INTERMEDIATE INSPECTIONS (595-3434). AS-BUILT CERTIFICATION IS REQUIRED PRIOR TO REQUEST FOR FINAL INSPECTION/APPROVAL.

FOR SUBMITTING THE 'AS BUILT CERTIFICATION AND REQUEST FOR CONVERSION TO OPERATIONAL PHASE FOR 62-330.310(1) WITHIN 30 DAYS AFTER WORK IS DEEMED COMPLETE.

17. THE OPERATION AND MAINTENANCE OF THE FACILITY WILL BE THE RESPONSIBILITY OF THE OWNER, AS IN ACCORDANCE WITH THE APPROVED PERMIT.

18. ELECTRIC/PHONE/CABLE/GAS STRUCTURES INSTALLED WITHIN DRAINAGE ACCESS EASEMENTS SHALL BE LOCATED ALONG THE BOUNDARY OF THE EASEMENT TO MAXIMIZE CLEAR ACCESS FOR MAINTENANCE EQUIPMENT.

19. MINIMUM ONE (1) FOOT GROUND COVER IS REQUIRED FOR ALL UNDERGROUND PIPES.

20. RIGHT-OF-WAY SHOULDER STABILIZATION SHALL BE IN ACCORDANCE WITH FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION.

21. RETAINING WALLS SHOWN ARE TO BE DESIGNED BY OTHERS. THE CONTRACTOR SHALL OBTAIN BUILDING INSPECTION DEPARTMENT'S PERMIT(S) FOR ANY RETAINING WALL HIGHER THAN 2 FEET.

22. WORK PROPOSED NEXT TO THE R/W WITH EXISTING SWALE SYSTEMS MAY REQUIRE ADDITIONAL PROVISIONS TO REPAIR/RESTORE EXISTING DRAINAGE SWALES AS NEEDED TO ENSURE ADEQUATE DRAINAGE. R/W SHOULDER STABILIZATION SHOULD BE IN ACCORDANCE WITH FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

23. THE CONTRACTOR SHALL NOTIFY THE COUNTY DESIGNEE AND/OR COUNTY INSPECTOR 48 HOURS PRIOR TO INITIATION OF CONSTRUCTION.

24. RETENTION/DETENTION AREAS SHALL BE SUBSTANTIALLY COMPLETE PRIOR TO ANY CONSTRUCTION ACTIVITIES THAT MAY INCREASE STORMWATER RUNOFF RATES. THE CONTRACTOR SHALL CONTROL STORMWATER DURING ALL PHASES OF CONSTRUCTION AND TAKE ADEQUATE MEASURES TO PREVENT THE EXCAVATED POND FROM BLINDING DUE TO SEDIMENTS.

25. SAG FILTERS IN CURB INLETS ARE NOT AN ALLOWABLE SEDIMENT CONTROL METHOD.

26. CONVEYANCE SWALES SHALL BE BUILT BY THE CONTRACTOR AND TREATMENT/SIDE YARD SWALES SHALL BE BUILT BY THE HOMEBUILDER.

27. HOME EQUIPMENT (I.E. AC UNITS) SHALL NOT HINDER THE PROPER INSTALLATION AND/OR FUNCTION OF THE PRIVATE YARD SWALES.

LOT NEIGHBORHOOD L GRADING PLAN

TION NO evel DETRO BIA CC 0033 4


| REVISION | | | |
|----------|--|--|--|
| DATE | | | |
| No. | | | |

NOT FOR CONSTRUCTION LICENSE No. 53126 I a. Battin CSTATE OF FLORIDA. Paul Al Battle, R.E. No 581126

Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022

DRAWING No.

SHEET 12 OF 25




- 1) ALL MATERIALS AND LABOR FOR INSTALLATION WILL BE THE RESPONSIBILITY OF THE PROPERTY OWNER/CONTRACTOR.
- 2) DRIVEWAYS ABUTTING PAVED ROADS SHALL BE 1 1/2" ASPHALT WITH 6" STABILIZED SUB GRADE OR 4" TO 6" CONCRETE WITH 4" STABILIZED SUB GRADE - 95% COMPACTION (MODIFIED PROCTOR) WITH LBR 40 BETWEEN EDGE OF ROADWAY AND R/W LINE. COMPACTION AND TESTING IF NECESSARY, THIS WILL BE THE RESPONSIBILITY OF THE OWNER/CONTRACTOR.
- 3) DRIVEWAYS ABUTTING A DIRT ROAD SHALL BE MILLED ASPHALT, GRADED AGGREGATE BASE, OR WASHED CONCRETE (4" IN DEPTH) ON THE COUNTY MAINTAINED PORTION OF DRIVEWAY.
- 4) IF NECESSARY, REFER TO FDOT INDEX DETAILS AS REFERENCED BELOW.
- RADIUS OR FLARE IS REQUIRED FOR TYPE II OR TYPE III CONNECTIONS. SEE DETAIL.

SILT FENCE DETAIL


N.T.S.

- PARKING SPACES WITHIN COUNTY RIGHT-OF-WAY SHALL PROVIDE A MINIMUM OF 2 PARKING SPACES.
- 7) TYPICAL DRIVEWAY SECTIONS ARE TO BE 12' WIDE MINIMUM.




TYPICAL DRIVEWAY CONNECTION STANDARDS FOR EXISTING ROADWAY CONDITIONS

NOT TO SCALE






GRADING OA NEIGHBORHOOD I PLAN DET



NOT FOR CONSTRUCTIO STATE OF FLORIDA. Paul A Battle, P.E. NO 581126 Dr. By: CBD


Ck By: PAB Job No.: 2021.006 Date: 6/29/2022 DRAWING No.

> C3.5 SHEET 13 OF 25




NOTES:


- 1. DIRT ROAD PATCH WORK SUB BASE MATERIAL SHALL BE PLACED IN NOT MORE THAN 8" L TS. EACH LAYER TO BE TAMPED TO A MINIMUM OF 40 LBR.
- 2. GRAE ED AGGREGATE BASE SHALL BE COMPACTED TO A MIN LBR 100.
- 3. ROAL CUTS SHALL BE MECHANICALLY SAW CUT TO FORM A SURFACE PAVEMENT JOINT AND TACK COATED ALONG THE FACE OF CUT JOINTS PRIOR TO ASPHALT PLACEMENT.
- 4. LONG TUDINAL ROAD CUTS THAT AFFECT ONE TRAVEL LANE SHALL REQUIRE MILLING AND REPAVING OF THE AFFECTED TRAVEL LANE 10.0' BEYOND THE CUT AND PATCHED WITH THE SAME BASE MATERIAL. LONGITUDINAL ROAD CUTS THAT AFFECT BOTH TRAVEL LANE; SHALL REQUIRE MILLING AND REPAVING OF THE ENTIRE ROADWAY 10.0' BEYOND THE CUT AND PATCHED WITH THE SAME BASE MATERIAL.



PAVED ROAD (SMALL PATCH) DETAIL FOR PATCHES LESS THAN 24" WIDE

NOT TO SCALE








A 40 Lot Town
Developme
1940 W DETROIT BOU
ESCAMBIA COUNTY, I




NOT FOR CONSTRUCTION A. BATTI Pan 20053 126 111 STATE OF Paul A Battle P.E. No.53126

Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022

SHEET 14 OF 25






REBOL-BAT

PROFILE **∞**ŏ PLAN

Ck By: PAB Job No.: 2021.006 Date: 6/29/2022 DRAWING No.

C5. SHEET 16 OF 25



2


PROFIL ంర

NOT FOR CONSTRUCTION


Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022

DRAWING No.


C5.2




∞ŏ




Ck By: PAB Job No.: 2021.006 Date: 6/29/2022





STATELOF Paul A, Battle, P.E. No.53126

Date: 6/29/2022



REBOL-BATTLE & ASSOCIA

Civil Engineers and Surveyors
2301 N. Ninth Avenue, Suite 300
Pensacola, Florida 32503
Telephone 850.438.0408
EB 00009657

PLAN & PROFILE

A 40 Lot Townhome
Development

Boulevard


DATE REVISION

No. 53126

No. 53126

State of Paul A. Battle & Associates, and may not be reproduced by the state of the sta

Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022



REBOL-BATTLE & ASSOCIATE
Civil Engineers and Surveyors
2301 N. Ninth Avenue, Suite 300
Pensacola, Florida 32503
Telephone 850.438.0400 Fax 850.438.0448

SECTIONS

CROSS

A 40 Lot Townhome
Development

No. DATE REVISION

NOT FOR ISONSTRUCTION
ICENSE

No. 53126

STATE OF
STATE OF
NIN 5 SRIDA

Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022

C6.0

HORIZONTAL SCALE: 1"=20"
HIGHLAND RIDGE DRIVE - Sta 105+47 80 -70 -60 -50 -40 -30 -20 -10 0 10 20 30 40 50 60 HIGHLAND RIDGE DRIVE - Sta 105+00 0—6"PVC HIGHLAND RIDGE DRIVE - Sta 105+86 HORIZONTAL SCALE: 1"=20"
HIGHLAND RIDGE DRIVE - Sta 104+50


Dr. By: CBD Ck By: PAB Job No.: 2021.006 Date: 6/29/2022

DRAWING No. C6.1

REBOL-BATTLE & ASSOCIAT
Civil Engineers and Surveyors
2301 N. Ninth Avenue, Suite 300
Pensacola, Florida 32503
Telephone 850.438.0408
EB 00009657

CROSS SECTIONS

A 40 Lot Townhome
Development



Dr. By: CBD
Ck By: PAB
Job No.: 2021.006
Date: 6/29/2022

C6.2

SHEET 25 OF 25