

1. THE CONTRACTOR MUST PROVIDE THE ENGINEER WITH REDLINED DRAWINGS FOR THE ENGINEER'S USE IN PREPARING AS-BUILT CERTIFICATIONS AND AS-BUILT RECORD DRAWINGS FOR THE OWNER. AS-BUILT INFORMATION WILL INCLUDE AND NOT BE LIMITED TO: ROUTING OF ALL EXISTING AND PROPOSED UNDERGROUND UTILITIES WITH DISTANCES TO/LOCATIONS OF LINES, BENDS, FITTINGS, STRUCTURES, AND OTHER APPURTENANCES MEASURED FROM AT LEAST TWO FIXED POINTS; TOP, BOTTOM, AND PIPE INVERT ELEVATIONS OF ALL STORM WATER AND SANITARY SEWER STRUCTURES, INCLUDING CLEANOUTS, RELATIVE TO FINISHED FLOOR; REVISIONS TO SITE LAYOUT DEPICTED IN THE PLANS.
2. THE CONTRACTOR IS RESPONSIBLE FOR SODDING ALL AREAS INDICATED ON THE PLANS AND ALL OTHER EXISTING SODDED AREAS WHICH ARE DISTURBED AS A RESULT OF CONSTRUCTION ACTIVITIES, WHETHER SUCH AREAS AND OR ACTIVITIES ARE INDICATED ON THE PLANS OR NOT.
3. TREES NOT BEING REMOVED MUST BE PROTECTED PER DETAILS PRESENTED IN THE PLANS.
4. ALL TREE PROTECTION BARRICADES MUST BE PLACED PRIOR TO COMMENCEMENT OF ANY SITE WORK INCLUDING LAND CLEARING, AND MUST BE MAINTAINED FOR THE DURATION OF THE PROJECT.
5. ALL SITE DRAINAGE MUST BE ROUTED TO CARRY ALL STORM WATER TO THE PROPOSED DRAINAGE SYSTEM.
6. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION PRIOR TO CONSTRUCTION AND MAINTENANCE/REPAIRS DURING CONSTRUCTION OF SEDIMENT CONTROL MEASURES AS REQUIRED TO RETAIN ALL SEDIMENTS AND EROSION ON THE SITE OF DEVELOPMENT. THE PROVISIONS AS SHOWN HEREON REPRESENT THE MINIMUM EROSION CONTROL MEASURES TO BE TAKEN. THE CONTRACTOR IS RESPONSIBLE FOR INCLUDING ANY ADDITIONAL REQUIRED MEASURES IN HIS BASE BID OR PROVIDING ADDITIONAL MEASURES AS NECESSARY AT NO ADDITIONAL COST TO THE OWNER DURING CONSTRUCTION. IMPROPER SEDIMENT CONTROL MEASURES MAY RESULT IN CODE ENFORCEMENT VIOLATION.
7. ALL ASPECTS OF THE STORM DRAINAGE COMPONENTS AND/OR TRANSPORTATION COMPONENTS MUST BE COMPLETED PRIOR TO REQUEST FOR FINAL INSPECTION.
8. ANY DAMAGE TO EXISTING ROADS, CURBS, SIDEWALKS, PARKING LOTS OR OTHER IMPROVEMENTS DURING CONSTRUCTION MUST BE REPAIRED BY THE CONTRACTOR PRIOR TO FINAL "AS-BUILT" SIGN-OFF FROM THE COUNTY AT NO ADDITIONAL COST TO THE OWNER.
9. THE CONTRACTOR MUST ARRANGE/SCHEDULE WITH THE COUNTY A FINAL INSPECTION OF THE DEVELOPMENT UPON COMPLETION AND ANY INTERMEDIATE INSPECTIONS AT (850) 595-3472. AS-BUILT CERTIFICATION IS REQUIRED PRIOR TO REQUEST FOR FINAL APPROVAL.
10. THE CONTRACTOR MUST COMPLY WITH ALL FEDERAL AND STATE REGULATIONS CONCERNING NOTIFICATION TO THE REGULATORY AUTHORITIES OF ANY AND ALL BUILDING RENOVATIONS AND/OR DEMOLITION.
11. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROTECT ALL BENCHMARKS DURING CONSTRUCTION, INCLUDING ALL PUBLIC AND PRIVATE LAND CORNER MONUMENTATION. IF A PUBLIC OR PRIVATE CORNER IS IN DANGER OF BEING DISTURBED AND HAS NOT BEEN PROPERLY REFERENCED, THE CONTRACTOR WILL NOTIFY THE ENGINEER OF RECORD IMMEDIATELY. IF ANY MONUMENT IS DISTURBED OR DESTROYED THE CONTRACTOR WILL BE RESPONSIBLE FOR REPLACEMENT OF THE MONUMENT AT A LOCATION DETERMINED BY A FLORIDA LICENSED PROFESSIONAL SURVEYOR AND MAPPER USING GUIDELINES AS ESTABLISHED BY NATIONAL GEODETIC SURVEY FOR BLUE BOOKING AND APPROVAL.
12. NO DEVIATIONS OR REVISIONS FROM THESE PLANS BY THE CONTRACTOR WILL BE ALLOWED WITHOUT PRIOR APPROVAL FROM BOTH THE DESIGN ENGINEER AND ESCAMBIA COUNTY. ANY DEVIATIONS MAY RESULT IN DELAYS IN OBTAINING A CERTIFICATE OF OCCUPANCY.
13. THE PROJECT ENGINEER (ENGINEER OF RECORD) MUST PROVIDE ESCAMBIA COUNTY WITH THE SIGNED/SEALED "AS-BUILT" RECORD DRAWINGS FOR VERIFICATION AND APPROVAL BY ESCAMBIA COUNTY ONE WEEK PRIOR TO REQUESTING A FINAL INSPECTION AND CERTIFICATE OF OCCUPANCY, OR PROVIDE "AS-BUILT" CERTIFICATION THAT THE PROJECT CONSTRUCTION ADHERES TO THE PERMITTED PLANS AND SPECIFICATIONS. THE "AS-BUILT" CERTIFICATION OR THE "AS-BUILT" RECORD DRAWINGS MUST BE SIGNED, SEALED AND DATED BY A REGISTERED FLORIDA PROFESSIONAL ENGINEER.
14. CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF A NEW IRRIGATION SYSTEM SUCH THAT COVERAGE IS PROVIDED TO ALL SODDED AREAS.
15. THE CONTRACTOR SHALL CONTROL STORM WATER DURING ALL PHASES OF CONSTRUCTION AND TAKE ADEQUATE MEASURES TO PREVENT THE EXISTING POND FROM BLINDING DUE TO SEDIMENTS.
16. DEVELOPER/CONTRACTOR SHALL RESHAPE PER PLAN SPECIFICATIONS, CLEAN OUT ACCUMULATED SILT, AND STABILIZE RETENTION/DETENTION POND(S) AT THE END OF CONSTRUCTION WHEN ALL DISTURBED AREAS HAVE BEEN STABILIZED AND PRIOR TO REQUEST FOR INSPECTION.
17. THE SUBJECT PARCEL FALLS WITHIN SEVERAL TRAVEL TIME CONTOURS OF PROTECTED (POTABLE) WELLHEADS. CONTRACTORS SHALL BE RESPONSIBLE FOR REPORTING SPILLS OF POTENTIALLY HAZARDOUS SUBSTANCES (I.E. GASOLINE, DIESEL FUEL, HYDRAULIC FLUID, CLEANING PRODUCTS, CHEMICALS, ETC.) TO THE APPROPRIATE STATE (FDEP STATE WARNING POINT 1-800-320-0519) AND LOCAL (ECUA- EMERALD COAST UTILITIES AUTHORITY (850) 476-5110 AND ESCAMBIA COUNTY HEALTH DEPARTMENT/ENVIRONMENTAL HEALTH 595-6712) AGENCIES.
18. ALL ADEQUATE TREE PROTECTION MEASURES AND BARRICADES SHALL BE INSTALLED PRIOR TO SITE DISTURBANCE AND MAINTAINED IN GOOD WORKING ORDER UNTIL PROJECT IS COMPLETE AND SITE BECOMES STABILIZED.
19. CONTRACTOR SHALL MAINTAIN RECORD DRAWINGS DURING CONSTRUCTION WHICH SHOW "AS-BUILT" CONDITIONS OF ALL WORK INCLUDING PIPING, DRAINAGE STRUCTURES, TOPO OF POND, OUTLET STRUCTURES, DIMENSIONS, ELEVATIONS, GRADING, ETC. RECORD DRAWINGS SHALL BE PROVIDED TO THE ENGINEER OF RECORD PRIOR TO REQUESTING FINAL INSPECTION.

AT&T DISTRIBUTION (TELEPHONE)  
TOM MANNING  
TM2709@ATT.COM  
(850) 623-3521

EMERALD COAST UTILITIES AUTHORITY (WATER, SEWER)  
BRANDON KNIGHT  
BRANDON.KNIGHT@ECUA.FL.GOV  
(850) 969-6511

VERIZON BUSINESS (FIBER, COMMUNICATION)  
(FORMERLY MCI)  
THOMAS BROYLES  
THOMAS.BROYLES@VERIZON.COM  
(850) 475-7465

QUANTA TELECOM. SERVICES LLC (FIBER)  
RUSSELL RIBBLETT  
RRIBBLETT@QUANTASERVICES.COM  
(850) 836-5610

## SITE DATA SUMMARY:

CURRENT USE: CHURCH

PROPOSED IMPROVEMENT:            PARKING ADDITION

<u>STORM WATER</u>	
CONTRIBUTING AREA	312,103 SF (100%)
EXISTING	
PERVIOUS	182,713 SF (59.0%)
IMPERVIOUS	129,390 SF (41.0%)
PROPOSED	
PERVIOUS	156,047 SF (50.0%)
IMPERVIOUS	156,056 SF (50.0%)



SECTION 30, TOWNSHIP 1-S, RANGE 30-W

Sheet List Table	
Sheet Number	Sheet Title
CIVIL	
C0.0	SITE NOTES & INFORMATION
C1.0	EXISTING CONDITIONS
C2.0	SITE DEMOLITION PLAN
C3.0	SITE IMPROVEMENTS, DIMENSIONING & LANDSCAPE PLAN
C4.0	SITE TREE INVENTORY & SUMMARY
C5.0	SITE GRADING PLAN
C6.0	SITE MISCELLANEOUS DETAILS
C6.1	SITE EROSION CONTROL DETAILS

USE OR ACTIVITY	1 PER 4 SEATS OR 1 PER
PLACE OF WORSHIP	35 SQ. FT. IN PRINCIPAL
	ASSEMBLY AREA IF NO
	FIXED SEATS

EXISTING (APPROVED)	135 STANDARD SPACES 5 ADA SPACES
---------------------	-------------------------------------

TOTAL SPACES PROVIDED    165 STANDARD SPACES  
5 ADA SPACES

<p align="center"><b>Approved</b>  <b>ESCAMBIA COUNTY DRC PLAN REVIEW</b></p>	
<p>DRC Chairman Signature: <u><i>[Signature]</i></u></p>	<p align="right"><u>7-6-22</u>  Date</p>
<p>Printed Name: <u><i>[Signature]</i></u>  Development Services Director or Designee</p>	

This document has been reviewed in accordance with the requirements of applicable Escambia County Regulations and Ordinances, and does not in any way release the submitting Architect, Engineer, Surveyor or other signatory from responsibility of details as drawn. A Development Order (DO) must be obtained through the Development Review Process prior to the commencement of construction. This DO approval does not constitute approval by any other agency. All additional state/federal permits shall be provided to the county prior to approval of a final plat or the issuance of state/federal permits shall be provided to the county prior to approval of a final plat or the issuance of a building permit.

[illegible]CIVIL  
S & INFORMATION

PROJ. START DATE	MARCH, 2022
MCE PROJ. #	07813-0001
DRAWN	SV
DESIGNED	SV
CHECKED	DPJj
PROJ. MGR.	DPJj

SCALE  
HORIZONTAL:  
AS NOTED  
VERTICAL:  
N/A

**C0.0**

DRAWING NUMBER

## DISCUSSION

REVISION

NEW SET

STATUS: **PERMIT REVIEW SET**  
**NOT RELEASED FOR CONSTRUCTION**







S PORTION TAKEN FOR RIGHT OF WAY  
(O.R.BOOK 3260, PAGE 436-437).

CREIGHTON ROAD (A)  
(AKA CREIGHTON BOULEVARD)  
(RIGHT OF WAY VARIES)






1. ALL OFF-SITE IMPROVEMENTS ARE TO BE PROTECTED UNLESS OTHERWISE NOTED. ANY DAMAGE TO OFF-SITE FEATURES RESULTING FROM CONTRACTOR'S ACTIONS MUST BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER. CONTRACTOR MUST SUBMIT, TO THE ENGINEER, A PRE-WORK REPORT DETAILING ANY EXISTING DAMAGED OR DETERIORATED FEATURES. FAILURE TO SUBMIT THIS REPORT WILL EQUAL AN ASSUMPTION OF NO DAMAGED OR DETERIORATED FEATURES, AND ANY SUCH DAMAGE DISCOVERED DURING FINAL INSPECTION WILL REQUIRE CORRECTION.
2. THE TREES NOTED ON THESE PLANS ARE THOSE DEEMED TO BE OF PARTICULAR IMPORTANCE DUE TO EITHER SIZE, PROTECTED/UNPROTECTED STATUS, AND LOCATION. NOT ALL TREES AND VEGETATION ARE NECESSARILY DEPicted. UPON ACQUIRING ALL NECESSARY DEVELOPMENT REVIEW COMMITTEE APPROVALS AND PERMITS (COMMERCIAL PRE-SITE IF SOUGHT AFTER ISSUANCE OF THE DO, &/OR AN BUILDING PERMITS FOR SITE WORK, STRUCTURES, ETC.), THE CONTRACTOR MUST REMOVE ALL EXISTING VEGETATION WITHIN THE PROJECT LIMITS AS NECESSARY TO FACILITATE THE PROPOSED CONSTRUCTION, AND MUST VERIFY THE EXACT REQUIREMENTS OF THAT REMOVAL IN THE FIELD PRIOR TO BID. TREES SPECIFICALLY NOTED TO BE REMOVED OR PROTECTED ON THESE PLANS MUST BE ADDRESSED AS NOTED.
3. TREES SHALL REMAIN ONSITE AND ANY LAND CLEARING/LAND DISTURBING ACTIVITIES INCLUDING PLACEMENT OF FILL/FILL MATERIALS, GRADING, EXCAVATION, ETC. SHALL NOT OCCUR UNTIL SUCH TIME AS APPROPRIATE PERMIT(S) ARE ISSUED FOR THE PROPOSED SITE WORK.
4. ALL ADEQUATE TREE PROTECTION MEASURES AND BARRICADES SHALL BE INSTALLED PRIOR TO SITE DISTURBANCE AND MAINTAINED IN GOOD WORKING ORDER UNTIL PROJECT IS COMPLETE AND SITE BECOMES STABILIZED.
4. CONTRACTOR SHALL MAINTAIN RECORD DRAWINGS DURING CONSTRUCTION WHICH SHOW "AS-BUILT" CONDITIONS OF ALL WORK INCLUDING PIPING, DRAINAGE STRUCTURES, TOPO OS POND, OUTLET STRUCTURES, DIMENSIONS, ELEVATIONS, GRADING, ETC. RECORD DRAWINGS SHALL BE PROVIDED TO THE ENGINEER OF RECORD PRIOR TO REQUESTING FINAL INSPECTION.
5. PLEASE REFER TO THE ENVIRONMENTAL & WELLHEAD PROTECTION NOTES ON SHEET C1.0.

## TREE REMOVAL SUMMARY

ID NO.	DBH	SPECIES	CANOPY	PROTECTED PER LDC	TO BE REMOVED
T5*	16"	WATER OAK	15'	XX	SEE NOTE BELOW
T16	13"	LAUREL OAK	20'	XX	XX
T17*	10"	CEDAR	8'		SEE NOTE BELOW
T18*	25"	LIVE OAK	30'	XX	SEE NOTE BELOW
T19*	28"	LIVE OAK	20'	XX	SEE NOTE BELOW
T20*	30"	LAUREL OAK	25'	XX	SEE NOTE BELOW
T24*	12"	LAUREL OAK	25'	XX	SEE NOTE BELOW
T25	17"	LAUREL OAK	15'	XX	XX

NOTE: TREES NOTED WITH \* REMOVED AFTER SUFFERING DAMAGE DURING HURRICANE SALLY

[illegible]

**McKIM & CREED**

1206 N. Palafox Street  
Pensacola, Florida 32501  
Phone: (850) 994-9503

CA Lic. No. 29598  
[www.mckimcreed.com](http://www.mckimcreed.com)



CIVIL

## SITE DEMOLITION PLAN

PROJ. START DATE		MARCH, 2022
MCE PROJ. #	07813-0001	
DRAWN	SV	
DESIGNED	SV	
CHECKED	DPJ	
PROJ. MGR.	DPJ	

STATUS:

**PERMIT REVIEW SET**

SCALE
HORIZONTAL: AS NOTED
VERTICAL: N/A

C2.0


DRAWING NUMBER	
----------------	--







NOTE: TREES NOTED WITH \* REMOVED AFTER SUFFERING DAMAGE DURING HURRICANE SALLY

[illegible]




PROJ. START DATE <b>MARCH, 2022</b>	SCALE	<div style="font-size: 2em; font-weight: bold;">C4.0</div>
MCE PROJ. # <b>07813-0001</b>	HORIZONTAL:  <b>AS NOTED</b>  VERTICAL:  <b>N/A</b>	DRAWING NUMBER
DRAWN <b>SV</b>		<div style="border: 1px solid black; height: 40px; width: 100%;"></div> REVISION
DESIGNED <b>SV</b>		
CHECKED <b>DPJj</b>		
PROJ. MGR. <b>DPJj</b>		



1. THE FOLLOWING ABBREVIATIONS APPLY:

EOP	=	EDGE OF PAVEMENT
FG	=	FINISHED GRADE
MEG	=	MATCH EXISTING GRADE
	=	SURFACE FLOW ARROW

2. UPON ACQUIRING ALL NECESSARY ESCAMBIA COUNTY DEVELOPMENT REVIEW COMMITTEE APPROVALS AND PERMITS (COMMERCIAL PRE-SITE IF SOUGHT AFTER ISSUANCE OF THE DO, &/OR ANY BUILDING PERMITS FOR SITE WORK, STRUCTURES, ETC.), CONTRACTOR IS RESPONSIBLE FOR GRADING SITE TO ACHIEVE PROPOSED SURFACE FLOW PATTERNS INDICATED BY PROPOSED SPOT ELEVATIONS. IN ALL CASES RUNOFF MUST BE DIRECTED AWAY FROM BUILDINGS, WALKS AND PADS AND TOWARD COLLECTION INLETS.
3. CERTAIN TREES ARE SCHEDULED TO REMAIN ON SITE AND ANY LAND CLEARING/LAND DISTURBING ACTIVITIES INCLUDING PLACEMENT OF FILL/FILL MATERIALS, GRADING, EXCAVATION, ETC. SHALL NOT OCCUR UNTIL SUCH TIME AS APPROPRIATE PERMIT(S) ARE ISSUED FOR THE PROPOSED SITE WORK.
4. CONTRACTOR SHALL MAINTAIN RECORD DRAWINGS DURING CONSTRUCTION WHICH SHOW "AS-BUILT" CONDITIONS OF ALL WORK INCLUDING PIPING, DRAINAGE STRUCTURES, TOPO OS POND, OUTLET STRUCTURES, DIMENSIONS, ELEVATIONS, GRADING, ETC. RECORD DRAWINGS SHALL BE PROVIDED TO THE ENGINEER OF RECORD PRIOR TO REQUESTING FINAL INSPECTION.
5. PLEASE REFER TO THE ENVIRONMENTAL & WELLHEAD PROTECTION NOTES ON SHEET C1.0.

[illegible]

**McKIM & CREED**

1206 N. Palafox Street  
Pensacola, Florida 32501  
Phone: (850) 994-9503


CA Lic. No. 29588  
[www.mckimcreed.com](http://www.mckimcreed.com)



CIVIL  
**SITE GRADING PLAN**

PROJ. START DATE <b>MARCH, 2022</b>	SCALE <b>1" = 40'</b>	<div style="border: 1px solid black; padding: 10px; text-align: center;"> <b>C5.0</b> </div>
MCE PROJ. # <b>07813-001</b>	HORIZONTAL: <b>AS NOTED</b>	DRAWING NUMBER
DRAWN <b>SV</b>	VERTICAL: <b>N/A</b>	REVISION
DESIGNED <b>SV</b>		
CHECKED <b>DP/JJ</b>		
PROJ. MGR. <b>DP/JJ</b>		






1  
C6.0




2  
C6.0



STOP SIGN

NOT TO SCALE


3  
C6.0



NOTES:

1. CENTER OF STOP BAR TO BE 6' FROM EDGE OF TRAVEL OF PRIMARY ROADWAY.
2. STOP BAR MUST BE WHITE THERMOPLASTIC.


VEHICLE STOP BAR 4  
NOT TO SCALE C6.0



TYPE 'F' CURB DETAIL


NOT TO SCALE

5  
C6.0




	MATERIALS
ASPHALT	1.5" SP-12.5
BASE	6" G.A.B.

ASPHALT PAVING SECTIONS 6  
NOT TO SCALE C6.0



**TYPICAL CONCRETE FLUME SECTION** 7  
NOT TO SCALE C6.0

[illegible]

# GATEWAY CHURCH OF CHRIST

---

## CIVIL

### SITE MISCELLANEOUS DETAILS

PROJ. START DATE		MARCH, 2021
MCE PROJ. #	07813-000	
DRAWN	SV	
DESIGNED	SV	
CHECKED	DPJ	
PROJ. MGR.	DPJ	

STATUS: **PERMIT REVIEW SET**  
**NOT RELEASED FOR CONSTRUCTION**

<p>SCALE</p> <p>HORIZONTAL: <b>AS NOTED</b></p> <p>VERTICAL: <b>N/A</b></p>	<p><b>C6.0</b></p> <p>DRAWING NUMBER</p>
---	--





1. LOCATIONS OF DOUBLE ROW WIRED BACK SILT FENCE ARE NOTED ON THE DEMOLITION SITE PLAN SHEET C002.

1

NOT TO SCALE



1. FOR TEMPORARY USE DURING CONSTRUCTION. BARRICADE MUST BE PLACED PRIOR TO ANY LAND DISTURBANCE.
2. FENCE MATERIAL WILL BE PLACED AT THE DRIP LINE OF THE TREE OR GROUP OF TREES TO BE PROTECTED.
3. NONE OF THE FOLLOWING ACTIVITIES MUST OCCUR WITHIN THE TREE PROTECTION BARRICADE: DRIVING, PARKING, STORING MATERIALS, DUMPING WASTE, CONCRETE WASHOUT, ADDING FILL SOIL, TRENCHING, REMOVING SOIL OR GRUBBING.

3

NOT TO SCALE



1. CONSTRUCTION ENTRANCES PROVIDE AN AREA WHERE MUD CAN BE REMOVED FROM VEHICLE TIRES BEFORE THEY LEAVE THE CONSTRUCTION SITE. THE MOTION OF THE VEHICLE AS IT MOVES OVER THE GRAVEL CONSTRUCTION MATERIAL DISLODGES CAKED MUD.
2. IF THE ACTION OF THE VEHICLE ON THE GRAVEL PAD IS NOT SUFFICIENT TO DISLODGE MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLE LEAVES THE SITE.
3. UTILIZE GRAVEL, 2"-3" (MIN.) IN DIAMETER. GRAVEL LAYER SHOULD BE AT LEAST 6" THICK. THE PAD SHOULD BE AT LEAST 50' LONG. WIDTH SHOULD BE APPROPRIATE TO VEHICLE SIZE.

$$\overbrace{2}$$

NOT TO SCALE



1. SEE WRITTEN SPECIFICATIONS FOR FULL DETAILS.
2. PLACE SOD BEGINNING AT THE TOE OF THE SLOPE AND LONG EDGE PERPENDICULAR TO DIRECTION OF FLOW.
3. SOD SHALL BE PINNED ON ALL SLOPES 4:1 OR STEEPER, IN AREAS OF CONCENTRATED DRAINAGE FLOWS, AND ANYWHERE THAT THERE IS DANGER OF SOD SLIPPING.
4. INSTALL SOD EDGES FLUSH WITH FINISHED GRADE OR ADJOINING SOD.

4

NOT TO SCALE





SYNTHETIC BALES OR SEDIMENT LOG MUST BE PLACED AT COMMENCEMENT OF CONSTRUCTION OR IMMEDIATELY AFTER INLET INSTALLATION AND MAINTAINED THROUGHOUT PROJECT COMPLETION AND STABILIZATION.

5

NOT TO SCALE

## REVISIONS



CA Lic. No. 29588  
www.mckimcreed.com



## CIVIL

## HORIZONTAL

AS NOTED

VERTICAL

N/A

## C6.1

DRAWING NUMBER
----------------

\_\_\_\_\_

REVISION

PROJ. START DATE		MARCH, 2022
MCE PROJ. #	07813-0001	
DRAWN	SV	
DESIGNED	SV	
CHECKED	DPJ	
PROJ. MGR.	DPJ	

STATUS:

STATUS: **PERMIT REVIEW SET**  
**NOT RELEASED FOR CONSTRUCTION**