
#### FOUR STAR FARM ROAD PAVING AND DRAINAGE

ESCAMBIA COUNTY

FLORIDA





SHEET NO

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY:

ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THIS SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

THE ABOVE NAMED PROFESSIONAL ENGINEER SHALL BE RESPONSIBLE FOR THE FOLLOWING SHEETS IN ACCORDANCE WITH RULE 61G15-23.004, F.A.C

#### 60% DESIGN SUBMITTAL

SHEET DESCRIPTION

SHEET NO.	SHEET DESCRIPTION
00	COVER SHEET
01	PROJECT NOTES
02	PROJECT NOTES & LEGEND
03	EROSION & SEDIMENT CONTROL GENERAL NOTES & DETAILS
04	BID ITEMS AND CONFLICT MATRIX
05	STORMWATER POLLUTION PREVENTION PLAN (SWPPP)
06	OVERALL PROJECT LAYOUT AND KEY SHEET
07 - 09	DEMOLITION & EROSION CONTROL PLANS
10 - 16	PLAN & PROFILE SHEETS
17 - 22	CROSS SECTIONS
23 - 25	PROJECT SIGNAGE AND PAVEMENT MARKING PLAN
26 - 28	UTILITY RELOCATION PLAN
29 - 34	PROJECT DETAILS



# BOARD OF COUNTY COMMISSIONERS ESCAMBIA COUNTY, FLORIDA

PUBLIC WORKS DEPARTMENT
ENGINEERING / INFRASTRUCTURE DIVISION

PLANS PROPOSED FOR

### FOUR STAR FARM ROAD

(PD 02-03.79.68.2 PO #211408)
DIRT ROAD PAVING & DRAINAGE PROJECT

#### INDEX OF PLANS

IFFT NO	SHEET DESCRIPTION
ELI 110.	BILLI DESCRITION
00	COVER SHEET
01	PROJECT NOTES
02	PROJECT NOTES & LEGEND
03	EROSION & SEDIMENT CONTROL GENERAL NOTES & DETAI
04	BID ITEMS AND CONFLICT MATRIX
05	STORMWATER POLLUTION PREVENTION PLAN (SWPPP)
06	OVERALL PROJECT LAYOUT AND KEY SHEET
07 - 09	DEMOLITION & EROSION CONTROL PLANS
10 - 16	PLAN & PROFILE SHEETS
17 - 22	CROSS SECTIONS
23 - 25	PROJECT SIGNAGE AND PAVEMENT MARKING PLAN
26 - 28	UTILITY RELOCATION PLAN

PROJECT DETAILS

## 60% DRAWING SUBMITTAL FEBRUARY 2023

#### **COMMISSIONERS**

DISTRICT ONE JEFF BERGOSH

DISTRICT TWO MIKE KOHLER


DISTRICT THREE LUMON MAY, CHAIRMAN

DISTRICT FOUR ROBERT BENDER

DISTRICT FIVE STEVEN BARRY, VICE CHAIRMAN

THESE PLANS HAVE BEEN PREPARED IN ACCORDANCE WITH THE LATEST ESCAMBIA COUNTY TECHNICAL SPECIFICATIONS.

ANY REFERENCE TO FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION, DIVISION 1, GENERAL REQUIREMENTS AND COVENANTS, SHALL BE EXCLUDED AND NOT APPLICAPABLE TO ANY SPECIFICATION REFERED HEREIN OR OTHERWISE LISTED IN THESE PLANS OR RELATED DOCUMENTS OR THE ESCAMBIA COUNTY TECHNICAL SPECIFICATIONS.



PROJECT MANAGER:		
JOHN ROSENAU		
SECTION / TOWNSHIP / RANGE:	DISTRICT:	
06-2N-31W	5	
PROJECT ENGINEER:	REG FLA EN	IG NO:
DALE E. LONG, PE	55393	
SIGNATURE:		DATE:
		FEBRUARY 2023

#### **ESCAMBIA COUNTY NOTES:**

- 1. ALL CONDITIONS AND STIPULATIONS OF THE CONSTRUCTION PERMITS AND THE APPROVALS ISSUED BY THE ESCAMBIA COUNTY ENGINEER SHALL BE COMPLIED WITH IN EVERY DETAIL.
- 2. THE CONTRACTOR SHALL TAKE STEPS NECESSARY TO PREVENT EROSION AND ANY OFF SITE SEDIMENT TRANSPORT RESULTING FROM INCREASED RUNOFF DURING CONSTRUCTION BY PROVIDING SILT FENCE AND/OR STAKED HAY BALES AS REQUIRED BY FDOT, THE FLORIDA STORMWATER, EROSION, AND SEDIMENT CONTROL INSPECTOR'S MANUAL, 2000 EDITION, OR AS INDICATED ON THE PLANS. ALL EROSION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL ASSOCIATED DISTURBED AREAS ARE STABILIZED AS TO REDUCE SEDIMENT RUNOFF, UNLESS OTHERWISE DIRECTED BY THE ENGINEER OR DESIGNEE.
- 3. COMPLIANCE OF NECESSARY PERMITS WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 4. THE CONTRACTOR IS CAUTIONED TO VISIT THE SITE AND FAMILIARIZE THEMSELVES WITH THE PROJECT PRIOR TO BIDDING AND/OR CONSTRUCTION.
- 5. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PRESERVE OR RELOCATE ALL BENCHMARKS (VERTICAL CONTROL) AS NEEDED DURING CONSTRUCTION. ALL PUBLIC OR PRIVATE CORNER MONUMENTATION SHALL BE PROTECTED. IF A PUBLIC OR PRIVATE CORNER MONUMENTATION IS IN DANGER OF BEING DESTROYED AND HAS NOT BEEN PROPERLY REFERENCED, THE CONTRACTOR SHALL NOTIFY THE ENGINEER OR DESIGNEE IMMEDIATELY. ANY ESCAMBIA COUNTY HARN/GPS NETWORK MONUMENTS OR BUREAU OF SURVEY AND MAPPING GPS NETWORK MONUMENTS WITHIN THE LIMITS OF CONSTRUCTION SHALL BE PROTECTED. IF A HARN/GPS NETWORK MONUMENTS OR BUREAU OF SURVEY AND MAPPING GPS NETWORK MONUMENTS ARE DISTURBED OR DESTROYED THE CONTRACTOR SHALL BE RESPONSIBLE FOR RELACEMENT OF THE MONUMENTS AND HAVE THE MONUMENTS POSITION DETERMINED BY A FLORIDA LICENSED PROFESSIONAL SURVEYOR AND MAPPER USING GUIDELINES AS ESTABLISHED BY NATIONAL GEODETIC SURVEY FOR BLUE BOOKING AND APPROVAL.
- 6. EXISTING DRAINAGE FEATURES WITHIN CONSTRUCTION LIMITS SHALL REMAIN UNLESS OTHERWISE NOTED.
- THE CONTRACTOR SHALL MATCH EXISTING CONDITIONS AT THE BEGINNING AND END OF CONSTRUCTION AS DIRECTED BY THE COUNTY ENGINEER OR DESIGNEE.
- 8. EXISTING STREETS AND DRIVES SHALL BE MAINTAINED TO LOCAL TRAFFIC AND PROPERTY OWNERS.
- 9. ALL ROADWAY CONSTRUCTION SHALL COMPLY WITH THE ESCAMBIA COUNTY TECHNICAL SPECIFICATIONS, LATEST EDITION.
- 10. ALL MATERIALS, TESTING AND CONSTRUCTION METHODS SHALL CONFORM TO THE ESCAMBIA COUNTY TECHNICAL SPECIFICATIONS, LATEST EDITION.
- 11. ANY REFERENCE TO FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION, DIVISION 1, GENERAL REQUIREMENTS AND COVENANTS, SHALL BE EXCLUDED AND NOT APPLICABLE TO ANY SPECIFICATION REFERRED HEREIN OR OTHERWISE LISTED IN THESE PLANS OR RELATED DOCUMENTS OR THE ESCAMBIA COUNTY TECHNICAL SPECIFICATIONS.
- 12. EXISTING STREET AND ROAD NAME SIGNS ON THE PROJECT SHALL BE KEPT VISIBLE AT ALL TIMES FOR THE FACILITATION OF ACCESS BY EMERGENCY VEHICLES. ALL OTHER EXISTING SIGNS THAT CONFLICT WITH CONSTRUCTION OPERATIONS SHALL BE TAKEN DOWN AND STOCKPILED WITHIN THE R/W LIMITS BY THE CONTRACTOR AS DIRECTED BY THE COUNTY ENGINEER OR DESIGNEE. ANY EXISTING SIGNS THAT ARE TO BE RELOCATED AND ARE DAMAGED BEYOND USE BY THE CONTRACTOR SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE
- 13. THE CONTRACTOR SHALL MAINTAIN AT LEAST ONE 10' OPEN LANE AT ALL TIMES. NO OPEN EXCAVATION SHALL REMAIN OVER NIGHT. CONTRACTOR SHALL RESTORE ROAD TO TWO LANES OF TRAFFIC AT THE END OF EACH WORK DAY.
- 14. CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REQUIREMENTS.
- 15. ONLY ACCESS TO THE ROAD R/W AS SHOWN IS GUARANTEED BY THE COUNTY. PRIVATE R/W REQUIRED BY THE CONTRACTOR TO FACILITATE CONSTRUCTION SHALL BE ACQUIRED BY THE CONTRACTOR WITH NO ADDITIONAL COMPENSATION OR ASSISTANCE FROM THE COUNTY.
- 16. VEGETATION ON R/W AND EASEMENTS SHALL BE RESTORED TO ORIGINAL CONDITION UNLESS OTHERWISE NOTED ON THE PLAN SHEETS. COST OF SAID RESTORATION SHALL BE CONSIDERED INCIDENTAL TO OTHER PAY ITEMS.
- 17. GRADED AGGREGATE BASE SHALL BE REQUIRED FOR ROADWAYS UNLESS OTHERWISE NOTED.
- 18. ALL TREES WITHIN LIMITS OF CONSTRUCTION SHALL REMAIN UNLESS OTHERWISE NOTED IN PLANS. REMOVAL OF ANY TREES OR SHRUBS SHALL BE COORDINATED WITH HOME OWNER PRIOR TO REMOVAL. ALL PROPOSED SOD SHALL MATCH EXISTING TYPE.
- 19. ALL COMPACTED FILL SHALL BE PLACED IN LAYERS OR LIFTS NOT MORE THAN 12" IN LOOSE DEPTH FOR MATERIAL COMPACTED BY HEAVY COMPACTION EQUIPMENT, AND NOT MORE THAN 8" IN LOOSE DEPTH FOR MATERIAL COMPACTED BY HAND-OPERATED TAMPERS.
- 20. MAINTENANCE OF TRAFFIC AS PER FDOT.
- 21. ALL EXISTING MAILBOXES SHALL BE RELOCATED BEYOND THE EDGE OF PAVEMENT BY THE CONTRACTOR IN ACCORDANCE WITH US POSTAL REQUIREMENTS AND IN ACCORDANCE WITH ESCAMBIA COUNTY TECHNICAL SPECIFICATION AND FDOT DESIGN STANDARDS. ALL EXISTING BRICK MAILBOXES WITHIN LIMITS OF CONSTRUCTION OR COUNTY RIGHT OF WAY SHALL BE REMOVED AND PLACED ON THE PROPERTY LINE OF THE OWNER. CONTRACTOR SHALL REPLACE EXISTING BRICK MAILBOX WITH APPROVED PLASTIC BREAK AWAY MAILBOX.
- 22. THE CONTRACTOR SHALL, AT A MINIMUM, MATCH EXISTING SIGNING AND PAVEMENT MARKINGS. ALL SIGNING AND PAVEMENT MARKINGS SHALL BE PLACED IN ACCORDANCE WITH THE LATEST FDOT DESIGN STANDARDS. THE CONTRACTOR SHALL CONTACT THE COUNTY TRAFFIC DEPARTMENT PRIOR TO INSTALLATION OF ANY SIGNING AND PAVEMENT MARKINGS.
- 23. WHERE UNSUITABLE MATERIAL, AS DEFINED BY THE COUNTY SPECIFICATIONS SECTION 02300, 1.3(I), IS ENCOUNTERED IN THE AREAS PROPOSED FOR PAVING, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE COUNTY ENGINEER OR DESIGNEE PRIOR TO ANY EXCAVATION.
- 24. PIPE LENGTHS SHOWN IN THE PLANS DO NOT INCLUDE THE LENGTH OF PIPE THAT MUST BE INSTALLED WITH THE MITERED END SECTION. THEREFORE, ALL PIPE LENGTHS ASSOCIATED WITH MITERED END SECTIONS SHALL BE PAID FOR IN THE UNIT COST OF THE MITERED END SECTION.

- 25. IF ARCHAEOLOGICAL MATERIAL/PREHISTORIC ARTIFACTS SUCH AS POTTERY OR CERAMICS, STONE TOOLS OR METAL IMPLEMENTS, OR ANY OTHER PHYSICAL REMAINS THAT COULD BE ASSOCIATED WITH NATIVE AMERICAN CULTURES, OR EARLY COLONIAL OR AMERICAN SETTLEMENT ARE ENCOUNTERED AT ANY TIME, THE PROJECT SHOULD CEASE ALL ACTIVITIES INVOLVING SUBSURFACE DISTURBANCE IN THE IMMEDIATE VICINITY OF SUCH DISCOVERIES. THE APPLICANT/RECIPIENT, OR OTHER DESIGNEE, SHOULD CONTACT THE FLORIDA DEPARTMENT OF STATE, DIVISION OF HISTORICAL RESOURCES, THE STATE HISTORIC PRESERVATION OFFICER (SHPO) AND THE DSH/FEMA REGION IV ENVIRONMENTAL OFFICER AND FDEM STATE ENVIRONMENTAL LIAISON OFFICER FOR FURTHER GUIDANCE. PROJECT ACTIVITIES SHOULD NOT RESUME WITHOUT VERBAL AND/OR WRITTEN AUTHORIZATION FROM THE DIVISION OF HISTORICAL RESOURCES.
- 26. IN THE EVENT THAT UNMARKED HUMAN REMAINS ARE ENCOUNTERED DURING PERMITTED ACTIVITIES, ALL WORK MUST STOP IMMEDIATELY AND THE PROPER AUTHORITIES NOTIFIED IN ACCORDANCE WITH F.S. 872.05.
- 27. CONTRACTOR SHALL OBTAIN COUNTY APPROVED CHANGE ORDER PRIOR TO PERFORMING ANY ADDITIONAL WORK.
- 28. ANY DAMAGE TO EXISTING ROADS DURING CONSTRUCTION WILL BE REPAIRED BY THE CONTRACTOR PRIOR TO FINAL "AS-BUILT" SIGN OFF FROM THE COUNTY.
- 29. ALL SIDEWALKS, SHARED PATH WALKWAYS, AND CURB RAMPS ARE TO BE BUILT TO ADA STANDARDS USING THE LATEST EDITION OF THE DESIGN STANDARDS PARK ADA REQUIREMENTS AND PUBLIC RIGHTS OF WAY ACCESSIBILTY GUIDELINES (PROWAG).
- 30. NO DEVIATIONS OR REVISIONS FROM THESE PLANS BY THE CONTRACTOR SHALL BE ALLOWED WITHOUT PRIOR APPROVAL FROM THE ENGINEER OF RECORD AND ESCAMBIA COUNTY.

#### **GENERAL NOTES:**

- 1. THE OWNER INTENDS THAT THE CONTRACT DOCUMENTS WILL PROVIDE A COMPLETE AND FULLY FUNCTIONAL PROJECT. WHERE LABOR AND MATERIAL MAY BE REQUIRED TO PROVIDE A COMPLETE AND FULLY FUNCTIONAL PROJECT BUT IS NOT FULLY SPECIFIED, DETAILED, OR SHOWN AS A CONSTRUCTION ITEM, THE CONTRACTOR SHALL PROVIDE THE REQUIRED MATERIAL OR LABOR TO MEET THE INTENT OF THE CONTRACT DOCUMENTS. THIS REQUIREMENT MAY ONLY BE CONSTRUED AS A REQUIREMENT TO COMPLETE OR MAKE FUNCTIONAL CONSTRUCTION ITEMS SHOWN IN OR ON THE CONTRACT DOCUMENTS.
- 2. PRIOR TO COMMENCING CONSTRUCTION WITHIN THE PROJECT AREA(S), THE CONTRACTOR SHALL VIDEO THE EXISTING CONDITIONS AND AREAS ADJACENT TO THE PROJECT THAT MAY BE IMPACTED BY THE CONSTRUCTION. THE CONTRACTOR SHALL KEEP ONE COPY AND PROVIDE ONE COPY EACH TO THE OWNER AND OWNER'S CONSTRUCTION INSPECTION/ADMINISTRATION REPRESENTATIVE.
- 3. ALL FINAL CONSTRUCTION AND CONSTRUCTION WORK SHALL BE IN COMPLIANCE WITH ALL LOCAL, STATE AND FEDERAL BUILDING AND/OR CONSTRUCTION CODES, RULES OR REQUIREMENTS AS APPLICABLE.
- 4. ABOVE GROUND FEATURES SHOWN WHICH MAY AFFECT CONSTRUCTION WERE TAKEN FROM THE BEST AVAILABLE INFORMATION AND FIELD SURVEYS. THE OWNER DOES NOT GUARANTEE THAT ALL PHYSICAL FEATURES OR ABOVE GROUND OBSTRUCTIONS AFFECTING CONSTRUCTION ARE SHOWN. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF/HERSELF WITH THE EXISTING CONDITIONS PRIOR TO SUBMITTING HIS/HER BID. THERE SHALL BE NO ADJUSTMENT OF THE CONTRACT PRICE FOR VISIBLE FEATURES AFFECTING CONSTRUCTION.
- 5. THE CONTRACT DOCUMENTS, SPECIFICATIONS, AND GEOTECHNICAL INVESTIGATION REPORT FOR THIS PROJECT ARE AN INTEGRAL PART OF THE CONSTRUCTION. THE CONTRACTOR SHALL FULLY REVIEW AND FOLLOW ALL REQUIREMENTS OF THESE DOCUMENTS IN THE COMPLETION OF THE WORK. ALL CONSTRUCTION SHALL BE IN STRICT COMPLIANCE WITH THE CONTRACT DOCUMENTS UNLESS OTHERWISE APPROVED IN WRITING BY THE OWNER OR OWNER'S AUTHORIZED REPRESENTATIVE.
- 6. ALL EXISTING FENCES, STORM DRAINS, PROPERTY CORNERS, SURVEY MONUMENTS, PAVEMENT, ROADS, SIDEWALKS, SIGNS OR ANY OTHER EXISTING OBJECTS OR STRUCTURES WHICH ARE NOT DESIGNATED FOR REMOVAL, BUT ARE DAMAGED OR DESTROYED BY THE CONTRACTOR OR BY ANYONE FOR WHOM THE CONTRACTOR IS RESPONSIBLE ARE TO BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE. THE CONTRACTOR IS RESPONSIBLE FOR REPLACING IN KIND OR REPAIRING TO ORIGINAL CONDITION; MAILBOXES, DRIVEWAY CULVERTS, RETAINING WALLS, LANDSCAPING, ETC. THAT ARE DISTURBED, DAMAGED OR DESTROYED BY CONSTRUCTION ACTIVITIES.
- 7. THE LEGEND IS TYPICAL FOR ALL SHEETS. SOME ITEMS MAY NOT APPLY TO EACH SHEET.
- 8. CONTRACTOR SHALL LIMIT CONSTRUCTION ACTIVITIES TO THE LIMITS OF CONSTRUCTION, RIGHT-OF-WAYS AND/OR EASEMENTS SHOWN. CONTRACTOR SHALL BE LIABLE FOR ALL DAMAGE TO AND RESTORATION OF ALL AREAS OUTSIDE OF RIGHT-OF-WAYS AND EASEMENTS, AT HIS EXPENSE.
- 9. IN THE EVENT THAT ANY STANDARDS OR SPECIFICATIONS AS DESCRIBED HEREIN OR SHOWN ON THE PLANS, ARE IN CONFLICT WITH EACH OTHER, THE MORE STRINGENT CRITERIA WILL APPLY. CONTRACTOR SHALL NOTIFY THE ENGINEER OF RECORD IMMEDIATELY AND IN WRITING. SHOULD THE MORE STRINGENT CRITERIA BE UNCLEAR, THE ENGINEER WILL PROVIDE AN INTERPRETATION AND DETERMINE WHICH CRITERIA IS TO BE USED.
- 10. THESE PLANS WERE BASED ON THE GEOTECHNICAL REPORT BY UNIVERSAL ENGINEERING SERVICES, PHONE: (850) 944-5555. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACQUIRE A COPY OF THE REPORT(S) FROM THE GEOTECHNICAL ENGINEER, FAMILIARIZE THEMSELVES WITH THE CONDITIONS AS DESCRIBED IN THE REPORT(S), AND COMPLY WITH ALL RECOMMENDATIONS MADE IN THE REPORT(S) SPECIFICALLY FOR SOIL PREPARATION ON THE SITE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN A COPY OF ALL SUPPLEMENTAL REPORTS FOR THIS PROJECT FROM THE OWNER AND TO FOLLOW THE SUPPLEMENTAL REPORTS' RECOMMENDATIONS.
- 11. THE OWNER, OWNER'S REPRESENTATIVES, AND INSPECTORS OF APPLICABLE GOVERNMENT AGENCIES HAVING JURISDICTION, SHALL AT ALL TIMES HAVE ACCESS TO THE WORK SITE. THE CONTRACTOR SHALL PROVIDE PROPER FACILITIES FOR SUCH ACCESS AND INSPECTIONS.
- 12. IT IS THE CONTRACTOR'S RESPONSIBILITY TO TAKE ALL REASONABLE AND PRUDENT PRECAUTIONS TO ENSURE THAT ALL COMPLETED WORK, MATERIALS AND EQUIPMENT STORED ON SITE ARE SAFE AND SECURE FROM UNAUTHORIZED ACCESS OR USE. SUCH PRECAUTIONS MAY INCLUDE INSTALLATION OF SIGNS, FENCES, OR POSTING OF SECURITY GUARDS.

- 13. ALL DISCHARGE FROM ANY REQUIRED DEWATERING OPERATIONS SHALL BE RESTRICTED AND MAINTAINED ON SITE. PERCOLATION THROUGH TEMPORARY PONDS OR EVAPORATION ARE THE ONLY ALLOWABLE NON-PERMITTED MEANS OF DISPOSAL OF GROUNDWATER. THE CONTRACTOR AT HIS EXPENSE, MAY PROVIDE TESTING OF GROUNDWATER PER F.D.E.P. GUIDELINES INCLUDING FAC CHAPTER 62-621.300(2). THE CONTRACTOR WILL BE REQUIRED TO OBTAIN A "GENERIC PERMIT FOR THE DISCHARGE OF PRODUCED GROUNDWATER FROM ANY NON-CONTAMINATED SITE ACTIVITY" FROM F.D.E.P. IF REQUIRED AT HIS EXPENSE.
- 14. ABOVE GROUND FEATURES SHOWN WHICH MAY AFFECT CONSTRUCTION WERE TAKEN FROM THE BEST AVAILABLE INFORMATION AND FIELD SURVEYS. THE OWNER DOES NOT GUARANTEE THAT ALL PHYSICAL FEATURES OR ABOVE GROUND OBSTRUCTIONS AFFECTING CONSTRUCTION ARE SHOWN. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF/HERSELF WITH THE EXISTING CONDITIONS PRIOR TO SUBMITTING HIS/HER BID. THERE SHALL BE NO ADJUSTMENT OF THE CONTRACT PRICE FOR VISIBLE FEATURES AFFECTING CONSTRUCTION.
- 15. ALL EXISTING FENCES, STORM DRAINS, PROPERTY CORNERS, SURVEY MONUMENTS, PAVEMENT, ROADS, SIDEWALKS, SIGNS OR ANY OTHER EXISTING OBJECTS OR STRUCTURES WHICH ARE NOT DESIGNATED FOR REMOVAL, BUT ARE DAMAGED OR DESTROYED BY THE CONTRACTOR OR BY ANYONE FOR WHOM THE CONTRACTOR IS RESPONSIBLE ARE TO BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE. THE CONTRACTOR IS RESPONSIBLE FOR REPLACING IN KIND OR REPAIRING TO ORIGINAL CONDITION; MAILBOXES, DRIVEWAY CULVERTS, RETAINING WALLS, SURVEY MARKERS, LANDSCAPING, ETC. THAT ARE DISTURBED, DAMAGED OR DESTROYED BY CONSTRUCTION ACTIVITIES.
- 16. THE LEGEND IS TYPICAL FOR ALL SHEETS. SOME ITEMS MAY NOT APPLY TO EACH SHEET.
- 17. CONTRACTOR SHALL LIMIT CONSTRUCTION ACTIVITIES TO RIGHT-OF-WAYS AND EASEMENTS SHOWN. CONTRACTOR SHALL BE LIABLE FOR ALL DAMAGE TO AND RESTORATION OF ALL AREAS OUTSIDE OF RIGHT-OF-WAYS AND EASEMENTS, AT HIS EXPENSE.
- 18. CONSTRUCTION NOTES ON THE PLANS AND STATIONING IDENTIFIED ARE NONSPECIFIC AND APPROXIMATE AND ARE INTENDED TO SHOW GENERAL INTENT OF THE WORK. THE CONTRACTOR SHALL APPLY ALL MATERIALS AND LABOR TO PROVIDE A COMPLETE AND FUNCTIONAL PROJECT AS IDENTIFIED ON THE PLANS.
- 19. THE CONTRACTOR SHALL COMPLY FULLY WITH ALL PERMIT REQUIREMENTS IMPOSED BY THE REGULATORY AGENCIES.


#### **PROJECT SAFETY NOTES:**

- 1. THE CONTRACTOR SHALL BE SOLELY LIABLE FOR THE SAFETY OF THE WORK AND ANY AND ALL DAMAGES ARISING FROM THE CONSTRUCTION SHOWN ON THE PLANS. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ASSURING THAT THE CONSTRUCTION MATERIALS AND METHODS ARE COMPLIANT WITH ALL APPLICABLE LOCAL, STATE OR FEDERAL SAFETY CODES, RULES, OR REQUIREMENTS.
- 2. THE CONTRACTOR SHALL COMPLY IN EVERY RESPECT WITH THE FEDERAL OCCUPATIONAL SAFETY AND HEALTH ACT OF 1970 (OSHA) AND ALL RULES AND REGULATIONS NOW OR HEREAFTER IN EFFECT UNDER THIS ACT. THE CONTRACTOR FURTHER AGREES TO COMPLY WITH ANY AND ALL APPLICABLE STATE LAWS AND REGULATIONS PERTAINING TO JOB SAFETY AND HEALTH.
- 3. THE CONTRACTOR SHALL PROTECT AND KEEP THE OWNER (INCLUDING THEIR AGENTS, CONSULTANTS, AND EMPLOYEES) FREE AND HARMLESS FROM ANY AND ALL LIABILITY, PUBLIC OR PRIVATE, PENALTIES, CONTRACTUAL OR OTHERWISE, LOSSES, DAMAGES, COSTS, ATTORNEY'S FEES, EXPENSES, CAUSES OF ACTION, ETC. RESULTING FROM THE FEDERAL OCCUPATIONAL SAFETY AND HEALTH ACT OF 1970 AS AMENDED.

#### **HAZARDOUS MATERIALS NOTES:**

- 1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH LOCAL STATE AND FEDERAL REGULATIONS REGARDING TESTING FOR AND DISPOSAL OF HAZARDOUS MATERIALS DURING DEMOLITION.
- HAZARDOUS MATERIAL MEANS ANY SUBSTANCE: (A) THE PRESENCE OF WHICH REQUIRES INVESTIGATION OR REMEDIATION UNDER ANY PRESENT FEDERAL, STATE OR LOCAL STATUTE REGULATION, ORDINANCE, RULE, CODE, ACTION, POLICY OR COMMON LAW, OR (B) WHICH IS OR BECOMES DEFINED AS A "HAZARDOUS WASTE", "HAZARDOUS SUBSTANCE" POLLUTANT OR CONTAMINANT UNDER ANY PRESENT FEDERAL, STATE OR LOCAL STATUTE, REGULATION, RULE OR ORDINANCE OR AMENDMENTS THERETO INCLUDING, WITHOUT LIMITATION, THE COMPREHENSIVE ENVIRONMENTAL RESPONSE COMPENSATION AND LIABILITY ACT (42 USC SECTIONS 9601 ET SEQ.) AND/OR THE RESOURCE CONSERVATION AND RECOVERY ACT (42 USC SECTIONS 6901 ET SEO.), OR (C) WHICH IS TOXIC, EXPLOSIVE, CORROSIVE, FLAMMABLE INFECTIOUS, RADIOACTIVE, CARCINOGENIC, MUTAGENIC, OR OTHERWISE HAZARDOUS AND IS REGULATED BY ANY GOVERNMENTAL AUTHORITY, AGENCY, DEPARTMENT, COMMISSION, BOARD AGENCY OR INSTRUMENTALITY OF THE UNITED STATES, THE STATE IN WHICH THE PREMISES ARE LOCATED OR ANY POLITICAL SUBDIVISION THEREOF, OR (D) THE PRESENCE OF WHICH ON THE PREMISES CAUSES OR THREATENS TO CAUSE A NUISANCE UPON THE PREMISES OR TO ADJACENT PROPERTIES OR POSES OR THREATENS TO POSE A HAZARD TO THE HEALTH OR SAFETY OF PERSONS ON OR ABOUT THE PREMISES, OR (E) WHICH CONTAINS GASOLINE, DIESEL FUEL, OR OTHER PETROLEUM HYDROCARBONS, OR (F) WHICH CONTAINS POLYCHLORINATED BIPHENYL (PCB'S), ASBESTOS, LEAD OR UREA FORMALDEHYDE FOAM INSULATION.
- 3. CONTRACTOR AND ITS SUBCONTRACTORS SHALL USE, HANDLE, TEST TRANSPORT, AND DISPOSE OF ALL HAZARDOUS MATERIALS (AS DEFINED HEREIN) IN COMPLIANCE WITH ALL CURRENT FEDERAL, STATE AND LOCAL ENVIRONMENTAL, HEALTH OR SAFETY LAW, INCLUDING, BUT NOT LIMITED TO, ALL SUCH STATUTES, REGULATIONS, RULES, ORDINANCES, CODES, AND RULES OF COMMON LAW.
- CONTRACTOR FURTHER AGREES THAT CONTRACTOR AND ITS SUBCONTRACTORS SHALL NOT CAUSE THE DISCHARGE, RELEASE, OR DISPOSAL OF ANY HAZARDOUS MATERIAL CREATED BY ITS WORK ON OR ABOUT THE JOB SITE. IN THE EVENT OF ANY SPILL, RELEASE, OR ANY OTHER REPORTABLE OCCURRENCE, CONTRACTOR SHALL NOTIFY THE APPROPRIATE GOVERNMENTAL AGENCY AND SHALL TAKE SUCH ACTION AS MAY BE NECESSARY TO MINIMIZE THE DELETERIOUS EFFECT OF SUCH A SPILL ON PERSONS OR PROPERTY.

# FOUR STAR FARM ROAD DIRT ROAD PAVING & DRAINAG



			<u>)</u>	3 3	1			
ACIO SEBVICE			4TION: CA-30886	DATE:				
EXCELLENCE IN ENGINEERING SERVICE 8574 Turkey Bluff Road Navarre, Florida 32566 p: (850) 939-5732 NC CERTIFICATE OF AUTHORIZATION: CA-30886				REG. FLA. ENG. NO.	20233	55555	SIGNATURE:	DALE E. LONG, P.E.
TITONA		J	ICES I	CHECKED BY:	WVP.II	DISTRICT:	5	SECTION / TOWNSHIP / RANGE 06-2N-31W
UDICIP SINEERING SERVI			DESIGNED BY:	DEL	PROJECT MANAGER:	JOHN ROSENAU	SECTION / TOWN O6-2N-31W	
<b>&lt;</b>		<b>ာ</b>	ENG	DRAWN BY:	EMD	DATE:	FEBRUARY 2023	FIELD BOOK / PAGES: FB 506/PP 21-33
APPROVED BY								
DATE								
REVISIONS								
NUMBER	ND 4 ***	(D)C						
	RAW IUMB		(	] <b>-(</b>	)(	)1		
	ROJE IUMB		1	70	)(	)()1	_(	)09

L-6217

SHEET 01 of 34

#### **DEMOLITION AND CLEARING NOTES:**

- 1. TREES SLATED FOR PROTECTION SHALL BE MARKED AND TREE PROTECTION BARRICADES SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF ANY LAND DISTURBING ACTIVITIES. NO PROTECTED TREES SHALL BE REMOVED, DESTRUCTIVELY DAMAGED, MUTILATED, RELOCATED, DISFIGURED, DESTROYED, CUT DOWN OR EXCESSIVELY PRUNED DURING CONSTRUCTION
- 2. NO GRADING OR CLEARING BY, OR STORAGE OF HEAVY EQUIPMENT SHALL OCCUR WITHIN THE DRIP LINE OF PROTECTED TREES OR WITHIN ENVIRONMENTALLY SENSITIVE AREAS.
- TRENCHING FOR PROPOSED UTILITY IMPROVEMENTS WITHIN THE DRIP LINE OF SPECIMEN TREES TO REMAIN, WILL REQUIRE THE ADVANCED PRE-TREATMENT OF EACH IMPACTED TREE BY A QUALIFIED ARBORIST OR THE LANDSCAPE ARCHITECT TO MINIMIZE THE POTENTIALLY ADVERSE IMPACTS OF CONSTRUCTION. HAND DIGGING MAY BE REQUIRED WITHIN THE DRIP LINE OF PROTECTED TREES.
- 4. WHERE DEMOLITION REQUIREMENTS LEAVE OPEN TRENCHES, PITS OR OTHER VOIDS, PROVIDE CLEAN FILL AND COMPACTION PER THE SPECIFICATIONS, THE GEOTECHNICAL REPORT OR OTHER REQUIREMENTS.
- REMOVAL OF EXISTING PAVED SURFACES INCLUDES REMOVAL OF EXISTING BASE OR SOIL MATERIALS SUFFICIENTLY TO CONSTRUCT THE NEW SURFACE IN ACCORDANCE WITH THE CONSTRUCTION PLANS.
- 6. ALL DEMOLISHED MATERIALS SHALL BE REMOVED FROM THE SITE AT THE CONTRACTOR'S EXPENSE. DEBRIS SHALL BE DISPOSED OF IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS.
- ALL ASPHALT AND CONCRETE SHALL BE SAW CUT AT EDGES TO REMAIN. REMAINING EDGES SHALL BE PROTECTED AT THE CONTRACTOR'S EXPENSE.
- CONTRACTOR SHALL MAINTAIN EXISTING DRAINAGE PATTERNS WHILE REMOVING OR REPAIRING ANY EXISTING STORM DRAINS OR SWALES.
- EXCAVATED MATERIALS (SPOILS) SHALL BE DISPOSED OF AS REQUIRED IN UPLAND AREAS IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL LAWS. IF SPOILS ARE TO BE STORED ON SITE EITHER TEMPORARILY OR PERMANENTLY, THE STORAGE LOCATION SHALL BE AN UPLAND AREA APPROVED BY THE OWNER AND ENGINEER. THE SPOILS SHALL BE PREVENTED FROM ERODING WITH THE USE OF SILT FENCING AND GRASSING AS APPROPRIATE.

#### **PAVING GRADING AND DRAINAGE NOTES:**

- 1. ALL DRAINAGE STRUCTURES ARE TO BE TRAFFIC RATED UNLESS SPECIFICALLY NOTED OTHERWISE.
- 2. ALL REINFORCED CONCRETE PIPE (RCP) SHALL BE A MINIMUM CLASS III, UNLESS OTHERWISE APPROVED OR NOTED ON THE PLANS OR SPECIFICATIONS.
- THE CONTRACTOR IS RESPONSIBLE FOR GRADING/PAVING ALL ROADWAYS TO DRAIN POSITIVELY IN THE DIRECTION SHOWN BY THE PROPOSED GRADES AND FLOW ARROWS ON THE PLANS. INTERSECTIONS SHALL BE TRANSITIONED TO PROVIDE A SMOOTH DRIVING SURFACE WHILE MAINTAINING POSITIVE DRAINAGE. IF AN AREA OF POOR DRAINAGE IS OBSERVED DURING CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO PAVING SO THAT A SOLUTION OR RECOMMENDATION FOR CORRECTION CAN BE MADE.
- 4. ALL STORMWATER JOINTS SHALL BE WRAPPED WITH FILTER FABRIC.

#### **RECORD DRAWING NOTES:**

- 1. THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER OF RECORD REDLINE DRAWINGS DEPICTING THE AS-BUILT CONDITION AT LEAST TWO (2) WEEKS PRIOR TO REQUESTING A FINAL INSPECTION OF THE WORK TO BE CERTIFIED.
- 2. THE CONTRACTOR SHALL KEEP A DAILY SET OF AS-BUILT DRAWINGS WHILE THE WORK IS BEING DONE IS VISIBLE AND EXPOSED ACCORDING TO THE CRITERIA CONTAINED HEREIN.
- 3. THE OWNER RESERVES THE RIGHT TO REQUIRE THAT THE CONTRACTOR UNCOVER, RE-TEST, AND/OR PERFORM ANY ACTION NECESSARY TO ENSURE THAT THE IMPROVEMENTS HAVE BEEN CONSTRUCTED IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS.
- THE CONTRACTOR WILL BE RESPONSIBLE FOR PROVIDING SUFFICIENT AS-BUILT INFORMATION TO CONVEY THAT THE CONSTRUCTION HAS BEEN COMPLETED WITHIN ACCEPTABLE TOLERANCES. AS-BUILT INFORMATION SHALL INCLUDE BUT IS NOT LIMITED TO THE FOLLOWING:

#### A.STORM DRAINAGE:

- 1) TOP ELEVATION OF EACH STRUCTURE FRAME AND COVER AS WELL AS THE TOP ELEVATION OF ALL HEADWALLS, CONTROL STRUCTURES, ETC.
- INVERT OF EACH LINE ENTERING AND EXITING EACH STRUCTURE.
- 3) INVERTS OF ALL PIPE OUTFALLS.
- 4) PIPE SLOPE (GRADE) BETWEEN STRUCTURES.
- 5) LENGTH OF RUN OF MAIN BETWEEN STORMWATER STRUCTURES (MEASURED FROM CENTER TO CENTER OF STRUCTURE)
- 6) PROVIDE DIMENSIONS AND INVERTS FOR ALL UNDERDRAINS INCLUDING FITTINGS AND CLEANOUTS.
- 7) LOCATE WITH MEASUREMENTS (MINIMUM TWO-POINT TIES) FROM PERMANENT VISIBLE OBJECTS ALL FITTINGS, STUB-OUT, ACCESSORIES, ETC. NOT VISIBLE FROM THE SURFACE.

#### B.PRESSURE MAINS (WATER AND SEWER):

- 1) ACTUAL LENGTH OF PIPE BETWEEN EACH BRANCH OR VALVE IN RUN.
- 2) LOCATE ALL FITTINGS WITH MEASUREMENTS (MINIMUM TWO-POINT TIES) FROM PERMANENT VISIBLE OBJECTS ALL FITTINGS, STUB-OUT, ACCESSORIES, ETC. NOT VISIBLE FROM THE SURFACE.
- 3) LIST THE DEPTH OF LINES AT ALL VALVES, FITTINGS, AND FIRE HYDRANTS.
- 4) DIMENSIONS WHICH CLEARLY DEMONSTRATE COMPLIANCE WITH MINIMUM SEPARATION DISTANCES OR REQUIRED PIPE UPGRADES (ENCASEMENT).
- CONTRACTOR SHALL MAINTAIN RECORD DRAWINGS DURING CONSTRUCTION WHICH SHOW "AS-BUILT" CONDITIONS OF ALL WORK INCLUDING PIPING, DRAINAGE STRUCTURES, TOPO OF POND(S), OUTLET STRUCTURES, DIMENSIONS, ELEVATIONS, GRADING, ETC. RECORD DRAWINGS SHALL BE PROVIDED TO THE ENGINEER OF RECORD PRIOR TO REQUESTING FINAL INSPECTION.

#### **UTILITY NOTES:**

- 1. THE LOCATION SHOWN FOR EXISTING UNDERGROUND UTILITIES IS APPROXIMATE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK IN EACH AREA. THE CONTRACTOR AGREES TO BE COMPLETELY RESPONSIBLE FOR ALL DAMAGES WHICH MIGHT OCCUR BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ALL UTILITIES.
- UTILITY OWNERS SHALL BE NOTIFIED AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION SO THAT THE UTILITY OWNER CAN SPOT VERIFY AND/OR EXPOSE THEIR UTILITIES. KNOWN **UTILITIES OWNERS INCLUDE:**

WATER - MOLINO UTILITIES, INC

MR. RANDY WEAVER

1640 MOLINO ROAD

ONE ENERGY PLACE

MOLINO, FL 32577 PH: (850)587-5538

**ELECTRIC - FLORIDA POWER & LIGHT** MR. DEREK GILMORE

PENSACOLA, FL 32520 PH: (850)777-9476

NATURAL GAS - PENSACOLA ENERGY MS. DIANE MOORE

1625 ATWOOD DRIVE

PENSACOLA, FL 32514 PH: (850)474-5319

TELEPHONE - FRONTIER COMMUNICATIONS MR. RICKY WASDIN 125 S. ALABAMA AVE

MONROEVILLE, AL 36460 PH: (251)368-9678

TELEPHONE - AT&T MR. TOM MANNING 6689 E. MAGNOLIA STREET MILTON, FL 32570 PH: (850)623-3521

SUNSHINE STATE ONE-CALL 7200 LAKE ELLENOR DRIVE, SUITE 200 ORLANDO, FL 32809 PH: (800)432-4770

- CONTRACTOR IS TO USE CAUTION WHEN WORKING IN OR AROUND AREAS OF OVERHEAD TRANSMISSION LINES AND UNDERGROUND UTILITIES.
- UTILITIES TO REMAIN AND BE PROTECTED DURING CONSTRUCTION. NECESSARY REPAIRS SHALL BE CONSIDERED INCIDENTAL TO OTHER PAY ITEMS AND SHALL BE TO THE SATISFACTION OF UTILITY OWNERS.
- 5. MOST IF NOT ALL OF MOLINO UTILITIES WATER METERS AND VALVE BOXES ARE DEPICTED ON PLANS.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND VERIFYING SIZE, TYPE, LOCATION, AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION AND NOTIFYING THE INVOLVED UTILITY PROVIDERS TO MAKE ANY NECESSARY ARRANGEMENTS FOR RELOCATION, DISRUPTION OF SERVICE OR CLARIFICATION OF ACTIVITY REGARDING SAID UTILITY. THE CONTRACTOR SHALL USE EXTREME CAUTION WHEN CROSSING AN UNDERGROUND UTILITY, WHETHER SHOWN ON THESE PLANS OR FIELD LOCATED. THE RESPECTIVE UTILITY PROVIDERS SHALL RELOCATE UTILITIES THAT INTERFERE WITH THE PROPOSED CONSTRUCTION AND THE CONTRACTOR SHALL COOPERATE WITH THE UTILITY PROVIDERS DURING RELOCATION OPERATIONS. ANY DELAY OR INCONVENIENCE CAUSED BY THE INVOLVED UTILITIES SHALL BE INCIDENTAL TO THE CONTRACT.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAKING ALL NECESSARY ARRANGEMENTS WITH GOVERNMENTAL DEPARTMENTS, PUBLIC UTILITIES, PUBLIC CARRIERS, SERVICE COMPANIES AND CORPORATIONS OWNING OR CONTROLLING ROADWAYS, RAILWAYS, WATER, SEWER, GAS, ELECTRICAL, TELEPHONE, AND TELEGRAPH FACILITIES, SUCH AS PAVEMENTS, TRACKS, PIPING, WIRES, CABLES, CONDUITS, POLES, GUYS, OR OTHER SIMILAR FACILITIES, INCLUDING INCIDENTAL STRUCTURES CONNECTED THEREWITH THAT ARE ENCOUNTERED IN THE WORK IN ORDER THAT SUCH ITEMS MAY BE PROPERLY SUPPORTED, PROTECTED OR LOCATED.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR OR REPLACEMENT OF PRIVATELY (HOMEOWNER) OWNED UNDERGROUND UTILITIES SUCH AS SPRINKLER SYSTEMS, SEPTIC DRAIN LINES, UNDERDRAINS, ETC. THAT ARE DAMAGED OR DESTROYED DURING CONSTRUCTION.
- 9. IN LOCATIONS WHERE CONSTRUCTION IS SHOWN CROSSING EXISTING UTILITIES, THE CONTRACTOR SHALL POTHOLE THE EXISTING UTILITIES TO CONFIRM LOCATION, SIZE AND DEPTH IN ADVANCE OF CONSTRUCTION. CONTRACTOR SHALL USE THE POTHOLE INFORMATION TO PROVIDE THE REQUIRED CLEARANCE BETWEEN THE PROPOSED UTILITY LINE ABOVE OR BELOW THE EXISTING UTILITIES.
- 10. ALL EXISTING VALVE BOX & LIDS SHALL BE RAISED TO FINAL GRADE BY THE CONTRACTOR.
- 11. THE CONTRACTOR IS REQUIRED TO LOCATE AND PROTECT ALL UTILITIES DURING CONSTRUCTION UNLESS OTHERWISE NOTED ON THE PLANS.
- 12. ALL VALVE BOXES LOCATED OUTSIDE OF PAVED AREAS SHALL BE SET FLUSH IN A CONCRETE COLLAR TO FINISH GRADE. ALL CONCRETE VALVE COLLARS SHALL BE CIRCULAR PRECAST MEMBER WITH A MINIMUM ANNULAR COVERAGE OF 6-INCHES.
- 13. ALL NEW UTILITY MAINS (WATER, GAS OR SANITARY FORCEMAINS) SHALL HAVE A MINIMUM COVER OF 30-INCHES AND A MAXIMUM COVER OF 36-INCHES, UNLESS OTHERWISE NOTED.
- 14. AT TIMES WHEN PIPE INSTALLATION IS NOT IN PROGRESS, THE OPEN ENDS OF THE PIPE SHALL BE CLOSED BY AN APPROVED MEANS AND SHALL REMAIN CLOSED UNTIL CONSTRUCTION OF THAT PARTICULAR SECTION IS RESUMED. NO OPEN TRENCHES WILL BE ALLOWED WHEN PIPE INSTALLATION IS NOT IN PROGRESS. THE TERMINAL JOINT MAY BE LEFT EXPOSED IN AN OPEN TRENCH, PROVIDED ADEQUATE SAFETY BARRICADES ARE INSTALLED BY THE CONTRACTOR.
- 15. CONNECTIONS TO EXISTING WATER AND SEWER FACILITIES SHALL BE COORDINATED WITH

MOLINO UTILITIES AT (850) 587-5538 PRIOR TO MAKING CONNECTIONS. A REPRESENTATIVE OF THE UTILITY SHALL WITNESS ALL CONNECTIONS.

- 16. UTILITY LINES SHALL BE ADJUSTED VERTICALLY GRADUALLY WITHOUT THE USE OF FITTINGS AS REOUIRED TO ACCOMMODATE EXISTING UTILITIES. IF GRADUAL LOWERING IS NOT POSSIBLE APPROPRIATE FITTINGS AND JOINT RESTRAINT SHALL BE PROVIDED TO AVOID THE EXISTING CONFLICT. NO FITTINGS GREATER THAN 45° WILL BE ALLOWED. SEPARATION SHALL BE A MINIMUM OF 18" UNLESS OTHERWISE NOTED ON THE PLANS. CONTRACTOR SHALL REFERENCE PLAN NOTES AND CONFLICT DETAILS FOR ADDITIONAL GUIDANCE.
- 17. THE CONTRACTOR SHALL PREPARE AND DISTRIBUTE TO ALL HOMEOWNERS A NOTICE NOTIFYING THEM OF THE IMPENDING CONSTRUCTION AT LEAST ONE WEEK IN ADVANCE OF BEGINNING WORK. THE NOTICE SHALL INCLUDE THE RESPONSIBILITIES OF THE HOMEOWNER AND THE CONTRACTOR, AS WELL AS EMERGENCY AND AFTER HOURS CONTACT INFORMATION FOR THE CONTRACTOR. THE NOTICE SHALL BE PREPARED BY THE CONTRACTOR AND PROVIDED TO THE OWNER AND THE ENGINEER FOR APPROVAL PRIOR TO DISTRIBUTION.
- 18. CONTRACTOR SHALL COORDINATE SERVICE OUTAGES RELATED TO WATER MAIN TIE-INS WITH MOLINO UTILITIES STAFF. CONTRACTOR IS ADVISED THAT TIE-INS MAY NEED TO BE MADE OVERNIGHT DURING OFF-PEAK HOURS.

#### **LEGEND:**


<b>A</b>	SET 60D NAIL	СРР	DENOTES CORRUGATED PLASTIC PIPE
$\otimes$	SET 1/2" DIA RED CAPPED IRON ROD (No. 7916)	(D)	DENOTES DEED INFORMATION
•	FOUND 4"x4" CONCRETE MONUMENT WITH PUNCHHOLE	DIA	DENOTES DIAMETER
$\blacksquare$	FOUND 3" DIA ROUND CONCRETE MONUMENT (UNNUMBERED)	ECMP	DENOTES ELLIPTICAL CORRUGATED METAL PIPE
<b>*</b>	SET BENCHMARK	EL	DENOTES ELEVATION
15)	DENOTES SECTION NUMBER	EOP	DENOTES EDGE OF PAVEMENT
Þ	DENOTES WOOD UTILITY POLE	(D)	DENOTES FIELD INFORMATION
$\leftarrow$	DENOTES GUY WIRE ANCHOR	MPH	DENOTES MILES PER HOUR
⋫	DENOTES METAL LIGHT POLE	No.	DENOTES NUMBER
<b>÷</b>	DENOTES MAILBOX	(P)	DENOTES PLAT INFORMATION
	DENOTES SINGLE SUPPORT SIGN	RCP	DENOTES REINFORCED CONCRETE PIPE
A/C	DENOTES AIR CONDITIONER UNIT	R/W	DENOTES RIGHT-OF-WAY
(P)	DENOTES TELEPHONE PEDESTAL	N/ VV	
<b>*</b>	DENOTES FIRE HYDRANT		EXISTING DIRT ROAD
WM	DENOTES WATER METER		EXISTING ASPHALT ROAD
×	DENOTES WATER VALVE		EXISTING CONCRETE DRIVEWAY
₩P	DENOTES WELL PUMP		EXISTING GRAVEL DRIVEWAY
	DENOTES GAS TANK		EXISTING DIRT DRIVEWAY
	DENOTES 4"X4" WOOD POST	* * * * * * * * * * * * * * * * * * *	EXISTING GRASS DRIVEWAY
$\bigcirc$	DENOTES TREE (SIZE AND TYPE NOTED)	/DIRT/	EXISTING DIRT DRIVEWAY
×	DENOTES UTILITY SPOT LOCATION	4" DIA CEDAR	DENOTES TREES & SHRUBS
A-1<	DENOTES WETLAND FLAG LOCATION	CEDAR	5-110 / <b>15</b> / 11-12-13 (
+ 6.00	DENOTES SPOT ELEVATION		DENOTES EXISTING STORM DRAIN
<u> </u>	DENOTES ELEVATION CONTOUR LINE AT ONE FOOT INTERVALS		DENOTES RIGHT OF WAY
<del></del>	DENOTES CHAIN LINK FENCE		
— // ——	DENOTES WIRE FENCE		
— xx ——	DENOTES CHAIN LINK FENCE WITH BARBED WIRE		
— оно ——	DENOTES OVERHEAD UTILITIES		
-3"W(PVC)	DENOTES BURIED WATER LINE, SIZE AND PIPE MATERIAL		
$\sim\sim$	DENOTES TREE LINE		
sik	DENOTES WETLAND LINE BOUNDARY		

#### PROPOSED LEGEND:

RELOCATED SIGN

HAY BALE

-X-X-X-X SILT FENCE



RO AR AR 1 

DRAWING NUMBER C-002


PROJECT 170001-009

SHEET 02 of 34


L-6217

BALES SHALL BE PLACED IN A SINGLE ROW, LENGTHWISE, WITH ENDS OF ADJACENT BALES TIGHTLY ABUTTING ONE ANOTHER, ALL BALES SHALL BE SECURELY ANCHORED BY AT LEAST TWO STAKES OR REBARS DRIVEN THROUGH THE BALE. THE FIRST STAKE IN EACH BALE SHALL BE DRIVEN TOWARD THE PREVIOUSLY LAID BALE TO FORCE THE BALES TOGETHER. CONTRACTOR SHALL WEDGE OR CHINK LOOSE STRAW BETWEEN BALES. INSPECTION SHALL BE FREQUENT AND REPAIR OR REPLACEMENT SHALL BE MADE AS PROMPTLY AS NEEDED. SYNTHETIC BALE BARRIERS SHALL BE REMOVED AFTER THEY HAVE SERVED THEIR USEFULNESS, BUT NOT BEFORE THE UPSLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED. SYNTHETIC BALE BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED BALES, END RUNS AND UNDERCUTTING BENEATH BALES.


#### NATURAL OR SYNTHETIC HAY BALE DETAIL



KEY STONE INTO THE DITCH BANKS AND EXTEND IT BEYOND THE ABUTMENTS A MINIMUM OF 18" TO PREVENT OVER FLOW AROUND DAM. CENTER OF STONE SHALL BE LOWER THAN ENDS




#### STONE CHECK DAM DETAIL



- USED FOR SMALL, NEARLY LEVEL DRAINAGE AREAS. (LESS THAN 5%)
- 2. USE 2x4 WOOD OR EQUIVALENT METAL STAKES, (3 FT. MIN. LENGTH)
- 3. INSTALL 2x4 WOOD TOP FRAME TO INSURE STABILITY.
- 1. DROP INLET SEDIMENT BARRIERS ARE TO BE 4. THE TOP OF THE FRAME (PONDING HEIGHT) MUST BE WELL BELOW THE GROUND ELEVATION DOWNSLOPE TO PREVENT RUNOFF FROM BY-PASSING THE INLET. A TEMPORARY DIKE MAY BE NECESSARY ON THE DOWNSLOPE SIDE OF THE STRUCTURE
  - 5. FILTER FABRIC SHALL BE PLACED AND MAINTAINED UNDER THE GRATE.

#### SILT FENCE DROP INLET SEDIMENT BARRIER DETAIL NOT TO SCALE



- 1. A SOIL TRACKING PREVENTION DEVICE (STPD) SHALL BE CONSTRUCTED AT 5. THE SWALE DITCH DRAINING THE STPD SHALL HAVE A 0.2% MINIMUM AND A APPROPRIATE LOCATIONS FOR POINTS OF EGRESS FROM UNSTABILIZED AREAS OF THE PROJECT TO PUBLIC ROADS WHERE OFFSITE TRACKING OF MUD COULD OCCUR. TRAFFIC FROM UNSTABILIZED AREAS OF THE CONSTRUCTION PROJECT SHALL BE DIRECTED THRU A STPD. BARRIERS, FLAGGING, OR OTHER POSITIVE MEANS SHALL BE USED AS REQUIRED TO LIMIT AND DIRECT VEHICULAR EGRESS
- ALL MATERIALS SPILLED, DROPPED, OR TRACKED ONTO PUBLIC ROADS (INCLUDING THE STPD AGGREGATE AND CONSTRUCTION MUD) SHALL BE REMOVED DAILY, OR MORE FREQUENTLY IF SO DIRECTED BY THE ENGINEER.
- AGGREGATES SHALL BE AS DESCRIBED IN SECTION 901 OF THE F.D.O.T. STANDARD SPECIFICATIONS EXCLUDING 901-2.3. AGGREGATES SHALL BE F.D.O.T. SIZE #1. IF THIS SIZE IS NOT AVAILABLE, THE NEXT AVAILABLE SMALLER SIZE AGGREGATE MAY BE SUBSTITUTED WITH THE APPROVAL OF THE ENGINEER. SIZES CONTAINING EXCESSIVE SMALL AGGREGATE WILL TRACK OF
- ISOLATED FROM OTHER DRAINAGE AREAS, THE FOLLOWING PIT VOLUMES WILI SATISFY THIS REQUIREMENT: 15'x 50'=100 FT<sup>3</sup> 30'x 50'=200 FT<sup>3</sup> AS AN OPTION TO THE SEDIMENT PIT, THE WIDTH OF THE SWALE BOTTOM CAN BE INCREASED TO OBTAIN THE VOLUME. WHEN THE SEDIMENT PIT OR SWALE IS

THE SEDIMENT PIT SHOULD PROVIDE A RETENTION VOLUME OF 3600 CUBIC

FEET/ACRE OF SURFACE AREA DRAINING TO THE PIT. WHEN THE STPD IS

USED, HAY BALES OR SILT FENCE SHALL BE PLACED ALONG THE ENTIRE LENGTH

- SATISFIES THE CLEAR ZONE REQUIREMENTS.


1.0% MAXIMUM GRADE ALONG THE STPD AND TO THE SEDIMENT PIT.


THE STPD SHALL BE MAINTAINED IN A CONDITION THAT WILL ALLOW IT TO PERFORM ITS FUNCTION. TO PREVENT OFFSITE TRACKING, THE STPD SHALL BE RINSED (DAILY WHEN IN USE) TO MOVE ACCUMULATED MUD DOWNWARD THRU THE STONE. ADDITIONAL STABILIZATION OF THE VEHICULAR ROUTE LEADING TO THE STPD MAY BE REQUIRED TO LIMIT THE MUD TRACKED.

MITRED END SECTIONS ARE NOT REQUIRED WHEN THE SIDEDRAIN PIPI

THE NOMINAL SIZE OF A STANDARD STPD IS 15'x 50' UNLESS OTHERWISE SHOWN IN THE PLANS. IF THE VOLUME OF ENTERING AND EXITING VEHICLES WARRANT, A 30' WIDTH STPD MAY BE USED IF APPROVED BY THE ENGINEER.

#### SOIL TRACKING PREVENTION DEVICE (CONSTRUCTION EXIT)





#### DOUBLE ROW STAKED SILT FENCE DETAIL

#### **EROSION AND SEDIMENT CONTROL NOTES:**

- $1. \;\;$  FOR ALL PROJECTS WHICH DISTURB MORE THAN ONE ACRE OF AREA, THE CONTRACTOR IS WHOLLY RESPONSIBLE FOR PREPARING, SUBMITTING, AND ACQUIRING THE FDEP/NPDES PERMIT, INCLUDING THE REQUIRED STORMWATER POLLUTION PREVENTION PLAN (SWPPP). THE CONTRACTOR SHALL SUBMIT A NOTICE OF INTENT TO FDEP NO LESS THAN 48 HOURS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION ACTIVITIES. THE CONTRACTOR IS ALSO RESPONSIBLE FOR ENSURING THAT THE PROJECT COMPLIES WITH THE PERMIT CONDITIONS (INCLUDING THE REQUIRED NPDES INSPECTIONS AND DOCUMENTATION) AND APPLICABLE LOCAL, STATE, AND FEDERAL WATER QUALITY STANDARDS DURING CONSTRUCTION. THE CONSTRUCTION DOCUMENTS CONTAIN ONLY THE MINIMUM REQUIREMENTS FOR EROSION AND SEDIMENT CONTROL. ANY AND ALL COSTS ASSOCIATED WITH OBTAINING THE NPDES PERMIT OR COMPLYING WITH THE PERMIT REQUIREMENTS SHALL BE BORNE BY THE CONTRACTOR
- 2. WHEN REQUIRED, THE CONTRACTOR SHALL DEVELOP AND IMPLEMENT A SWPPP ACCORDING TO EPA/FDEP CRITERIA TO MINIMIZE EROSION AND ENSURE PROPER FUNCTIONING OF THE STORMWATER MANAGEMENT SYSTEM UPON COMPLETION OF CONSTRUCTION. IN ADDITION TO MEETING EPA/FDEP NPDES CRITERIA, THE SWPPP SHALL BE SUBMITTED TO AND COMPLY WITH ANY REQUIREMENTS OF THE LOCAL AGENCY HAVING JURISDICTION. A COPY OF THE APPROVED STORMWATER POLLUTION PREVENTION PLAN (SWPPP) SHALL BE KEPT ON SITE AT ALL TIMES FOR REVIEW AS MAY BE
- THE CONTRACTOR SHALL COMPLY WITH ALL FEDERAL, STATE, AND LOCAL LAWS AND ALL REGULATIONS CONTROLLING POLLUTION OF THE ENVIRONMENT
- 4. CONTRACTOR SHALL EXECUTE ALL MEASURES AND IMPLEMENT ALL BEST MANAGEMENT PRACTICES NECESSARY TO LIMIT THE TRANSPORTATION OF SEDIMENTS OUTSIDE THE LIMITS OF THE PROJECT. THE EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION AND MUST REMAIN IN SATISFACTORY OPERATION UNTIL THE PROJECT IS FULLY COMPLETED AND ACCEPTED AND UNTIL THE PERMANENT EROSION CONTROL MEASURES ARE ESTABLISHED AND CAPABLE OF PROVIDING EROSION AND SILTATION CONTROL. CONTRACTOR SHALL PROVIDE ROUTINE MAINTENANCE ON TEMPORARY EROSION CONTROL MEASURES AT HIS EXPENSE. CONTRACTOR SHALL CONTINUALLY MONITOR WEATHER AND SITE CONDITIONS AND SHALL PROVIDE CONTINUOUS MONITORING OF EROSION AND SEDIMENT CONTROLS AND SHALL DOCUMENT ALL CORRECTIVE MEASURES
- INLETS AND CATCH BASINS SHALL BE PROTECTED FROM SEDIMENTATION RESULTING FROM SURFACE RUNOFF UNTIL COMPLETION OF ALL CONSTRUCTION OPERATIONS THAT MAY CAUSE SEDIMENT TO RUNOFF. FILTER FABRIC SHALL BE PLACED AND MAINTAINED UNDER THE GRATE AND FILTER SOCKS SHALL BE PLACED IN FRONT OF THE THROAT OF CURB INLETS, DURING CONSTRUCTION AND SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT CONSTRUCTION.
- 6. ALL DISTURBED AREAS WHICH ARE NOT PAVED SHALL BE SEEDED, FERTILIZED AND MULCHED, HYDROSEEDED, OR SODDED AS REQUIRED, UNLESS NOTED OTHERWISE. SOD PINS SHALL BE USED FOR ALL SOD PLACED ON SLOPES STEEPER THAN 3:1. AREAS OF ESTABLISHED SOD OR GROUND COVER SHALL BE REPLACED IN KIND TO MATCH THE EXISTING CONDITIONS PRIOR TO CONSTRUCTION COMMENCEMENT.
- PERMANENT GRASSING SHALL BE INSTALLED AND MAINTAINED ON ALL EXPOSED SLOPES AND DISTURBED AREAS WITHIN 48 HOURS OF COMPLETING FINAL GRADING, AND AT ANY OTHER TIME AS NECESSARY, TO PREVENT EROSION, SEDIMENTATION, OR TURBID DISCHARGES. A VEGETATIVE COVER THAT STABILIZES AND PREVENTS EROSION SHALL BE ESTABLISHED WITHIN 60 DAYS OF PERMANENT GRASSING INSTALLATION. UPON ESTABLISHMENT OF A SUBSTANTIAL VEGETATIVE COVER, ALL TURBIDITY BARRIERS AND EROSION CONTROL MEASURES SHALL BE REMOVED.
- TEMPORARY SEDIMENT CONTROL MEASURES INCLUDE, BUT ARE NOT LIMITED TO: SILT FENCING; CONSTRUCTION OF SEDIMENT CHECK DAMS; CONSTRUCTION EXITS, FLOATING TURBIDITY CURTAINS, FILTER SOCKS; SEEDING AND MULCHING, ETC. PERMANENT SEDIMENT CONTROL MEASURES INCLUDE BUT ARE NOT LIMITED TO: PERMANENT GRASSING; EROSION BLANKETS; RIP RAP, ETC. MINIMUM STABILIZATION MEASURES ARE DETAILED ON THE CONSTRUCTION PLANS. THE CONTRACTOR SHALL INCLUDE ANY AND ALL MEASURES NECESSARY TO STABILIZE THE SITE, CONTROL EROSION, AND PREVENT SEDIMENT FROM ESCAPING THE SITE. THE CONTROL OF EROSION ON THE SITE COMPLY WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL REGULATIONS.
- CONSTRUCTION OPERATIONS SHALL BE SCHEDULED AND PERFORMED SO THAT PREVENTATIVE EROSION CONTROL MEASURES ARE IN PLACE PRIOR TO EXCAVATION. TEMPORARY STABILIZATION MEASURES SHALL BE IN PLACE IMMEDIATELY FOLLOWING CLEARING, BACKFILLING AND/OR GRADING OPERATIONS.
- 10. SPECIAL PRECAUTIONS WILL BE TAKEN IN THE USE OF CONSTRUCTION EQUIPMENT TO PREVENT SITUATIONS THAT PROMOTE EROSION.
- 11. CLEANUP WILL BE DONE IN A MANNER TO INSURE THAT EROSION CONTROL MEASURES ARE NOT DISTURBED.
- 12. THE PROJECT WILL BE CONTINUALLY INSPECTED FOR SOIL EROSION AND SEDIMENT CONTROL COMPLIANCE. DEFICIENCIES WILL BE CORRECTED BY THE CONTRACTOR WITHIN 24 HOURS.
- 13. TEMPORARY EROSION CONTROL MEASURES SHALL BE COMPLETELY REMOVED BY THE CONTRACTOR UPON ESTABLISHMENT OF PERMANENT CONTROL MEASURES OR WHEN DIRECTED BY THE OWNER.
- 14. THE CONTRACTOR SHALL COMPLETE SITE RESTORATION AS THE PROJECT PROGRESSES.
- 15. THE OWNER SHALL SEND A COPY OF THE FDEP/NPDES NOTICE OF INTENT TO THE LOCAL BUILDING DEPARTMENT UPON RECEIPT, AS APPLICABLE.
- 16. THE CONTRACTOR SHALL INSTALL PRIOR TO THE START OF CONSTRUCTION AND MAINTAIN DURING CONSTRUCTION ALL SEDIMENT CONTROL MEASURES AS REQUIRED TO RETAIN ALL SEDIMENTS ON SITE. IMPROPER SEDIMENT CONTROL MEASURES MAY RESULT IN A CODE ENFORCEMENT VIOLATION.
- 17. THE CONTRACTOR IS RESPONSIBLE FOR PREVENTING TRACKING OF SOIL FROM THE SITE ONTO ADJACENT ROADWAYS. IN ADDITION TO THE INSTALLATION OF A CONSTRUCTION EXIT THE CONTRACTOR WILL BE RESPONSIBLE FOR SWEEPING ROADWAYS AS REQUIRED.
- 18. CONTRACTOR SHALL TAKE ALL MEASURES NECESSARY TO CONTROL TURBIDITY IN SURROUNDING WATERS INCLUDING, BUT NOT LIMITED TO, THE INSTALLATION OF TURBIDITY BARRIERS AT ALL LOCATIONS WHERE THE POSSIBILITY OF TRANSFERRING SUSPENDED SOLIDS INTO THE RECEIVING BODY OF WATER EXISTS DUE TO THE PROPOSED WORK. TURBIDITY BARRIERS MUST BE MAINTAINED AT ALL LOCATIONS UNTIL CONSTRUCTION IS COMPLETED AND DISTURBED SOIL AREAS ARE STABILIZED. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR REMOVING THE BARRIERS AND ANY ACCUMULATED SILT AT THE COMPLETION OF CONSTRUCTION AND PERMANENT STABILIZATION. AT NO TIME SHALL THERE BE ANY OFF-SITE DISCHARGE WHICH VIOLATES THE WATER QUALITY STANDARDS OF THE FLORIDA ADMINISTRATIVE CODE.
- 19. THE CONTRACTOR IS RESPONSIBLE FOR THE CONTROL OF DUST AND OTHER AIRBORNE POLLUTANTS DURING CONSTRUCTION. DUST SHALL BE CONTROLLED BY WATERING OR OTHER APPROVED METHODS AT THE CONTRACTOR'S DISCRETION.

RO ARM IG & DR AR L OUR DIRT R

DRAWING C-003 170001-009 NUMBER L-6217

NUMBER

SHEET 03 of 34

	DATE  ON Correct (Pink Highlighter)  DATE
REMARK INCORPORATION (Blue Highlighter)	RIGINATOR VERIFICATION Correct (Pink Highlighter)
REMARK INCORPORA ORIGINATOR VERIFI	
DATE	
agrree or Remark)	
CHECKER (RP) (Red Pen X-Out to Disagrree or Remark) CHANGE INCORPORATION (Yellow HighLighter)	
PRODUCTION CHECKING COMPLETE, READY FOR SUBMITTAL REVIEW (RP)	
NATURE:	

UTILITY CONFLICT MATRIX								
Conflict #	Utility Owner	Station	Offset	Utility	Conflict Description	Recommended Resolution		
1	Molino Utilities	0+41	0'	Potable Water 8" PVC	Existing water main will be under new roadway	Locate and Protect		
2	Molino Utilities	0+41 to 21+64	Left of CL	2" Water Main		Move waterline out from under future asphalt and transfer water services to new line		
3	FPL/ATT	0+44	17' R	Utility Pole and Telephone Junction Box	Pole and TJB are within the clear zone	Relocate pole to right-of-way line (confirm)		
4	FPL	2+90	10' L	Utility Pole	Pole is within the roadway	Relocate pole to right-of-way line		
5	FPL	3+82	12' R	Utility Pole	Pole is within the roadway clear zone	Relocate pole to right-of-way line		
6	FPL	5+48	10' R	·	Pole is within the roadway	Relocate pole to right-of-way line		
7	ATT	5+58	10' R	Telephone Junction Box (TJB)		Relocate TJB to right-of-way line		
8	Molino Utilities	5+69	0'	Water Service and Meter	Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation		
9	FPL	7+29	10' R	Utility Pole		Relocate pole to right-of-way line Water Service Transfer, ensure that water		
10	Molino Utilities	7+73	0'	Water Service and Meter	Water service crosses proposed	service is below future swale/pipe bottom elevation		
11	FPL	8+35	11' R	Utility Pole	i	Relocate pole to right-of-way line		
12	Molino Utilities	9+84	0'		Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation		
13	FPL	10+82	13' R	Utility Pole	Pole is within the roadway clear	Relocate pole to right-of-way line		
14	Molino Utilities	11+10	0'	Water Service and Meter	Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation		
15	ATT	12+63	15' R	Telephone Junction Box (TJB)	TJB is within the roadway	Relocate TJB to right-of-way line		
16	Molino Utilities	14+24	O'	Water Service and Meter	Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation		
17	FPL	14+24	15' R	Utility Pole	Pole is within the roadway clear zone	Relocate pole to right-of-way line (confirm)		
18	Molino Utilities	16+77	O'	Water Service and Meter	Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation		
19	ATT	17+06	14' R	Telephone Junction Box (TJB)	TJB is within the roadway clear zone	Relocate TJB to right-of-way line (confirm)		
20	Molino Utilities	17+10	O'	Water Service and Meter	Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation		
21	Molino Utilities	17+56	O'		Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation		
22	FPL	17+85	14' R	Utility Pole	Pole is within the roadway clear	Relocate pole to right-of-way line (confirm)		
23	Molino Utilities	18+72	0'	Water Service and Meter	Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation		
24	Molino Utilities	19+41	0'		Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation		
25	Molino Utilities	20+61	O'	Water Service and Meter	Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation		
26	FPL	20+79	11' R	Utility Pole and Guy Anchor	Pole and guy are within the roadway	Relocate pole and guy to right-of-way line		
27	ATT	12+06	16' R	Telephone Junction Box (TJB)		Relocate TJB to right-of-way line		
28	Molino Utilities	21+30	0'	Water Service and Meter (3 EA)	Water service crosses proposed	Water Service Transfer, ensure that water service is below future swale/pipe bottom elevation (3 EA)		
29	Molino Utilities	21+37	6' L	Flush Stand	Flush Stand is located in the proposed driveway	Remove flush stand		

# FOUR STAR FARM ROAD DIRT ROAD PAVING & DRAINAGE BID ITEMS AND CONFLICT MATRIX



| ENCELLENCE IN ENGINEERING SERVICE | EXCELLENCE IN ENGINEERING SERVICE | BS74 Turkey Bluff Road | Navarre, Florida 32566 | Navarre, Florida 32566

DRAWING NUMBER C-004

PROJECT NUMBER 170001-009

SURVEY L-6217

SHEET 04 OF 34

DRAWING NUMBER C-005

NUMBER

170001-009

L-6217

SHEET 05 of 34

#### Four Star Farm Road (PD 02-03.79.68.2) CONSTRUCTION POLLUTION PREVENTION PLAN

This document is a summary of the complete pollution prevention plan indicated on and an integral part of the construction plans, specifications, and contract documents. Detailed requirements are indicated on the construction plans for the Four Star Road Dirt Road Paving and Drainage Project.

#### SITE DESCRIPTION

Project Name: Four Star Farm Road Dirt Road Paving and Drainage

Owner Name: Escambia County, Florida

Latitude 30° 43′ 3.63″ N Longitude 87° 23′ 1.40″ W

Owner Address: 3363 W. Park Place, Pensacola FL 32505

Project Address: Four Star Farm Road Molino, FL 32577

Project Contact: Mr. John Rosenau, Escambia County, DRP Program Manager

The project scope includes paving the existing 2-lane dirt road via the construction of a 2-lane 22-foot-wide asphalt roadway within the existing/new right-of-way of Four Star Farm Road. The new pavement will be complimented with drainage improvements to convey the runoff to the two new outfalls located along the roadway. Conveyances will include roadside swales as well as

inlets and piping systems and cross-drains.

**Runoff Coefficient**: 0.23 (Station 0+50 to 14+85) 0.29 (Station 18+75 to 23+76)

Total Site Area: 2.43 acres. Total Area Disturbed: 2.43 acres.

**Existing Soil Data**: Reference Project Geotechnical Report from Universal Engineering Sciences.

Receiving MS4: Escambia County, Florida

Lat/Long of Discharge Points:

Contributing

30° 42' 49.12" N 87° 23' 1.82" W 17.69 Acres Station 14+85 30° 42′ 39.98″ N 87° 23′ 1.99″ W 0.80 Acres

Station 23+76

Discharge

Page 1 of 6

#### SEQUENCE OF MAJOR CONSTRUCTION ACTIVITIES

- Contractor will mobilize and install silt fence, hay bales, straw wattles, check dams, inlet protection, and any other erosion & sediment control measures, as needed, in each area where work is currently being performed.
- Site clearing and demolition will be completed.
- Ditch bottom inlets and storm drainage will be constructed.
- Road paving will take place.
- Damaged roadways will be repaired, as required.

Upon completion of construction of all soil disturbing activities, and following the establishment of grassing and permanent erosion controls in each area, all temporary erosion control measures will be removed.

#### TIMING OF EROSION AND SEDIMENT CONTROL MEASURES

The temporary sediment control measures implemented, as needed, will be installed prior to clearing of any portions of the site in which work is currently being performed. Areas where construction activities are completed, or temporarily cease for more than 21 days, will be stabilized with a temporary seed and mulch within 14 days of the last disturbance. After the entire site is stabilized, any accumulated sediment will be removed as necessary.

Page 2 of 6

#### EROSION AND SEDIMENT CONTROLS

All controls shall be consistent with performance standards for erosion and sediment control and stormwater treatment set forth in section 62-40.432, Florida Administrative Code, the applicable Stormwater or Environmental Resource Permitting requirements of FDEP or a Water Management District, and the guidelines contained in the Florida Development Manual: A Guide to Sound Land and Water Management (DEP) 1988 and any subsequent

#### Stabilization Practices

Temporary sediment control measures may include, but are not limited to: silt fencing, hay bale barriers, construction entrances, construction of temporary sediment check dams, inlet protection and temporary seeding. Permanent sediment control measures include but are not limited to seeding and mulching or sodding areas disturbed by the proposed construction activity. While some stabilization practices are detailed on the construction plans, the Contractor shall include any measures necessary to prevent sediment from escaping the site and to comply with all applicable FDEP standards.

#### Structural Practices

Stormwater runoff shall continue to be directed to existing storm sewer systems and best management practices (BMPs) shall be implemented as needed to ensure that no sediment escapes the site.

#### Stormwater Management

This site is drained by surface sheet flow which is directed into existing curb inlets and storm sewer systems. Stormwater runoff generated by proposed construction activity will not be increased or changed from existing

#### **Other Control Measures**

Waste Materials: All waste materials will be collected and stored in secured metal dumpsters to be provided by a solid waste management company licensed in Escambia County, Florida. The dumpsters will meet all Escambia County and any State of Florida solid waste management regulations. All trash and construction debris from the site will be deposited in the dumpsters. Dumpsters will be emptied as required to prevent overflow. No construction waste materials will be buried or burned onsite. All personnel will be instructed regarding the correct procedure for waste disposal. Notices stating these practices will be posted in the construction office trailer, job board or at another easily accessible location.

Hazardous Waste: All hazardous waste materials will be disposed of as specified by EPA, Escambia County, State of Florida regulations, or by the manufacturer. The General Contractor will be responsible for ensuring that these practices are followed and that site personnel receive the needed instruction and training.

Offsite Vehicle Tracking: The paved streets adjacent to the site will be swept as required to remove any excess mud, dirt, or rock tracked from the site. Dump trucks hauling material from or to the construction site will be covered with a tarpaulin.

Page 3 of 6

#### MAINTENANCE AND INSPECTION PROCEDURES

- All control measures will be inspected at least once each week, at least 24 hours within any rainfall event, and within 8 hours following any storm event of 0.5 inches or greater.
- All measures will be maintained in good working order, if a repair is necessary, it will be initiated within 24 hours of being reported.
- Built up sediment will be removed from silt fence when it has reached one third the height of the fence. • Silt fence will be inspected for depth of sediment, tears, to see if the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.
- Earthen swales and berms will be inspected, and any damage or breeches will be promptly repaired.
- Temporary and permanent seeding will be inspected for bare spots, washouts, and healthy growth.
- A maintenance inspection report will be made after each inspection.
- The site superintendent will select individuals who will be responsible for inspections, maintenance, and repair activities, and filling out maintenance inspection reports.
- Personnel selected for inspection and maintenance responsibilities will be qualified accordingly and will be trained in all the inspection and maintenance practices necessary for keeping the erosion and sediment controls used onsite in good working order.
- All non-stormwater discharges from sources such as flushing, pavement or vehicle washdown, dewatering, or any other source will be directed to a temporary sediment basin prior to discharge.

#### INVENTORY FOR POLLUTION PROTECTION PLAN

The materials or substances below are expected to be onsite during construction.

- PVC Pipe
- Petroleum based products

■ DI Pipe, Valves and Fittings

■ Sand Clay Backfill Material

■ HDPE or Steel Casing Pipe

- Sand & Top Soil
- Cleaning solvents
- Graded Aggregate Silt Fencing
- Haybales and Hay Mulch
- Sodding and Grassing
- Asphalt
- Stone Rubble Rip-Rap
- Applicable Building Products

■ Gravel

Wood

Concrete

#### • An effort will be made to store only enough product and material onsite as required to do the job. • All materials stored onsite will be stored in a neat and orderly manner in their appropriate containers, and

other accidental exposure of materials or substances to stormwater runoff.

MATERIAL MANAGEMENT AND SPILL CONTROL PRACTICES

The following are spill control practices which will be used to properly cleanup and reduce the risk of spills or

- if possible, under a roof or within an enclosure.
- Products will be kept in their original containers with the original manufacturer's label. • Substances will not be mixed with one another unless recommended by the manufacturer.
- Whenever possible, all of a product will be used before disposing of a container.
- Manufacturer's recommendations for proper use and disposal will be followed.
- The site superintendent will inspect the job daily to ensure proper use and disposal of materials. Original labels and material safety data will be retained for all hazardous products.
- If surplus hazardous products must be disposed of, manufacturer's or local and state recommended methods for proper disposal will be followed.
- All paint containers will be tightly sealed and stored when not in use.
- Excess paint will be disposed of per the manufacturer's recommendations and applicable regulations. • All onsite vehicles will be monitored for leaks and receive regular preventative maintenance.
- Petroleum products will be stored in tightly sealed clearly labeled containers.
- Any asphalt substances used onsite will be applied according to the manufacturer's recommendations. Fertilizers will be applied only in the minimum amounts recommended by the manufacturer. Once applied, fertilizer will be worked into the soil to limit exposure to storm water. The contents of any partially used
- Concrete trucks will not be allowed to wash out or discharge surplus concrete or drum wash except in designated temporary areas bermed or otherwise protected from runoff.
- Manufacturer's recommended methods for spill cleanup will be clearly posted, and site personnel will be made aware of the procedures and the location of the information and cleanup supplies.
- Materials and equipment necessary for spill cleanup will be kept in the material storage area onsite.
- Equipment and materials will include but not be limited to: brooms, dust pans, mops, rags, gloves, goggles, cat litter, sand, sawdust, and plastic and metal containers specifically for this use.
- Any spills will be cleaned up immediately after discovery.

bags of fertilizer shall be transferred to a sealable container.

- Any spill areas will be kept well ventilated, and personnel will wear appropriate protective clothing & gear. All spills of toxic or hazardous substances will be reported to the appropriate state and/or local authority.
- The spill prevention plan will be adjusted to prevent reoccurrence of spills or contamination. • The site superintendent responsible for the day-to-day site operations, will be the spill prevention and
- cleanup coordinator. He will designate at least three other site personnel who will receive spill prevention and cleanup training.
- Notice of any spill will be made in accordance with any local, state, or federal requirements.

Page 5 of 6

#### CERTIFICATION OF COMPLIANCE WITH FEDERAL, STATE AND LOCAL REGULATIONS

The Stormwater Pollution Prevention Plan reflects Florida Department of Environmental Protection Agency requirements for storm water management and erosion and sediment control. To ensure compliance this plan was prepared according to the manual "Storm Water Management for Construction Activities" - publication number EPA 832-R-92-005 as published by the US Environmental Protection Agency.

#### POLLUTION PREVENTION PLAN CERTIFICATION


certify under penalty of law that this document and all attachments were prepared under my direction, or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.


Signed:	1	- 12	- <del> </del>				
Ву:	1 A 1	*	*	<b>*</b>	<u> </u>	* **	<u>.</u>
Date:	8-0-		· · · · · ·	10	à		•


#### **CONTRACTORS CERTIFICATION**


certify under penalty of law that I understand, and shall comply with, the terms and conditions of the State of Florida Generic Permit for Stormwater Discharge from Large and Small Construction Activities and this Stormwater Pollution Prevention Plan prepared thereunder."


Signature	For	Responsible For
,	•	























115

EXISTING 25' O/S LEFT GRADE

EXISTING 25' O/S RIGHT GRADE -

PROPOSED CENTERLINE GRADE PROPOSED RIGHT DITCH PROPOSED LEFT DITCH

EXISTING CENTERLINE GRADE ------

LEGEND:

20+00

\_\_\_\_\_

20+50


21+00


21+50


**PROFILE** 


PROJECT 170001-009 SCALE: HOR.: 1" = 20' VER.: 1" = 5' SURVEY L-6217 SHEET 14 OF 34

DRAWING NUMBER C-304











PROFILE SCALE: HOR.: 1" = 20' VER.: 1" = 5'

DRAWING NUMBER C-402 PROJECT 170001-009 SURVEY L-6217 SHEET 18 OF 34







PROFILE


SCALE: HOR.: 1" = 20'
VER.: 1" = 5'


DRAWING C-404


| DRAWING NUMBER | 170001-009
| SURVEY NUMBER | L-6217
| SHEET | 20 of 34






































DRAWING NUMBER C-702


NUMBER


NUMBER 170001-009

SHEET 30 of 34

L-6217







L-6217

