

BOARD OF COUNTY COMMISSIONERS ESCAMBIA COUNTY, FLORIDA

ENGINEERING DEPARTMENT CONSTRUCTION MANAGEMENT DIVISION

INDEX OF ROADWAY PLANS

SHEET DESCRIPTION

- KEY SHEET
- SUMMARY OF PAY ITEMS
- DRAINAGE MAP
- PROJECT LAYOUT
- TYPICAL SECTIONS
- GENERAL NOTES
- PLAN AND PROFILE
- 10-17 CROSS SECTIONS
- EROSION CONTROL SHEET

RESURFACING PLAN

PLANS PROPOSED FOR

RENEE TERRACE

DRAINAGE IMPROVEMENTS ENG 2106

ISSUE FOR CONSTRUCTION

PERDIDO BAY -MAVILLA STREET CACICA STREET ISLES DRIVE COUNTY ROAD 292A (INNERARITY POINT ROAD)

PROJECT AREA

FAIR OAK LANE

RENEE TERRACE

CORONADA BOULEVARD

COMMISSIONERS

DISTRICT ONE JEFF BERGOSH

DISTRICT TWO MIKE KOHLER

DISTRICT THREE

DISTRICT FOUR VACANT

DISTRICT FIVE STEVEN BARRY (CHAIRMAN)

LUMON MAY

OMER EACRET ECTION / TOWNSHIP / RANGE: 14, 15/3S/32W PROJECT ENGINEER: REG FLA ENG NO: PHILLIP J. WALKER MARCH 2024 (SEE EOR SEAL)

VICINITY MAP

PROJECT MANAGER:

PD 02-03.79.15.65.ENG

THESE PLANS HAVE BEEN PREPARED IN ACCORDANCE WITH THE LATEST ESCAMBIA COUNTY TECHNICAL SPECIFICATIONS.

ANY REFERENCE TO FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION, DIVISION 1, GENERAL REQUIREMENTS AND COVENANTS, SHALL BE EXCLUDED AND NOT APPLICAPABLE TO ANY SPECIFICATION REFERED HEREIN OR OTHERWISE LISTED IN THESE PLANS OR RELATED DOCUMENTS OR THE ESCAMBIA COUNTY TECHNICAL SPECIFICATIONS.

SUMMARY OF PAY ITEMS

1 Mobilization, 0 - 15 Miles	1 EA
2 Clearing and Grubbing (Including Trees UNDER 12" dia.)	2431 SY
3 Remove Tree, 13"-24"	6 EA
4 Replace Standard Mailbox with approved Heavy-Duty Plastic Mailbox w/ Rear Door and Post.	12 EA
5 Earthwork Excavation by machine	314 CY
6 Earthwork Excavate, Haul, and Install, On-site	9 CY
7 Dewatering, Trench and/or Pipe	824 LF
8 Dewatering Pump	4 Week
9 2" Type SP 12.5 Asphalt, over 1500sy	1704 SY
10 Asphalt Millings, Driveways	38 SY
11 Remove Existing Asphalt, 2" Average Depth	1704 SY
12 Saw cut Existing Asphalt	97 LF
13 6" Graded aggregate Base "Min. LBR 100 at 100% Modified Proctor",	1857 SY
14 Develop and provide and implement a MOT traffic safety plan, both map type and written type, by a Certified Work Zone Safety Traffic Supervisor	1 EA
15 FDOT Type B curb, FDOT Index 300	23 LF
16 FDOT Type F Curb and Gutter, FDOT Index 300	101 LF
17 County Type B Curb, Per County Detail	331 LF
18 4" Fiber Reinforced Concrete Driveway, over 50sy	179 SY
19 Ditch Bottom Inlet, Type C, 0'-6' depth	1 EA
20 Ditch Bottom Inlet, Type D, 0'-6' depth	2 EA
21 Ditch Bottom Inlet, Type E, 0'-6' depth	1 EA
22 Curb Inlet Top, Type 2	1 EA
23 Curb Inlet Top, Type 6	1 EA
24 Storm Manhole, 0-6ft depth	3 EA
25 14" X 23" ERCP Pipe, 0'-6' depth	824 LF
26 Class I Concrete for Endwalls (steel included)	1 CY
27 18" Depth Rip Rap Rubble w/ 4" Bedding Stone and Geotextile	33 SY
28 Silt Fence Type IV	1000 LF
29 Floating Turbidity Barrier	40 LF
30 Establish, quantify, and submit an approved erosion control plan prepared by a certified technician.	1 EA
31 Waterproof Jobsite Storage Board Container/Tube for project information, permits, SWPPP plans, etc.	1 EA
32 TIDAL CHECK VALVE 14"X23"	1 EA
33 Construct Stabilized Gravel Construction Entrance	100 SY
34 NPDES Construction General Permit, NOI, and NOT (including SWPPP and monitoring), for use only with disturbed areas over 1.0 acre	1 EA
35 Remove and Replace Unsuitable Materials	824 CY
36 Centipede Sod, Staked	691 SY
37 12" Stabilized Subgrade, over 1000sy	1857 SY
38 1' Ribbon Curb, Per County Detail	226 LF

PAY ITEM NOTES

- 1. THE COST ASSOCIATED WITH PAY ITEMS 2 & 3 SHALL INCLUDE ALL COSTS ASSOCIATED WITH TREE AND VEGETATION REMOVAL REQUIRED TO CONSTRUCT THE PROJECT. THE PROJECT HAS BEEN DESIGNED WITH THE INTENT TO AVOID IMPACTING TREES.
- 2. THE COST ASSOCIATED WITH PAY ITEM 11 SHALL INCLUDE ALL APPURTENANCES REQUIRED FOR RECONSTRUCTION OF RENEE TERRACE.
- 3. THE COST ASSOCIATED WITH PAY ITEM 20 SHALL INCLUDE ALL COSTS ASSOCIATED WITH THE MODIFIED S-102 SLOT.
- 4. THE COST ASSOCIATE WITH ITEM 26 SHALL INCLUDE ALL REINFORCING STEEL AND APPURTENANCES REQUIRED TO CONSTRUCT S-107.
- 5. THE COST ASSOCIATED WITH ITEM 27 SHALL INCLUDE ALL COSTS ASSOCIATED WITH THE REMOVAL, TEMPORARY STORAGE. AND REPLACEMENT OF EXISTING RIP-RAP WHICH IS IMPACTED BY CONSTRUCTION ACTIVITIES.
- 6. THE COST ASSOCIATED WITH ITEMS 28, 29, & 30 SHALL INCLUDE ALL COSTS ASSOCIATED WITH SEDIMENT BARRIER AND INLET PROTECTION NECESSARY TO PREVENT OFFSITE SEDIMENT TRANSPORT AS WELL AS PROTECT THE PROPOSED TRUNKLINE.
- 7. THE COST ASSOCIATED WITH ITEM 32 SHALL INCLUDE ALL COSTS ASSOCIATED WITH FURNISHING AND INSTALLING THE 14"x23" TIDAL CHECK VALVE. APPROVED PRODUCTS SHALL INCLUDE THE RED VALVE CHECKMATE VALVE OR EQUIVALENT WHICH IS APPROVED BY THE ENGINEER.
- 8. THE COST ASSOCIATED WITH ITEM 35 WILL REQUIRE PRIOR APPROVAL FOR USE FOR EACH SITUATION ENCOUNTERED.


REVISIONS DATE DESCRIPTION


PHILLIP J. WALKER P.E. LICENSE NUMBER 87701 HDR ENGINEERING, INC. 25 WEST CEDAR STREET, SUITE 200 PENSACOLA, FL 32502-5945



ESCAMBIA COUNTY ENGINEERING DEPARTMENT RENEE TERRACE DRAINAGE

SHEET NO.







TRAFFIC DATA


POSTED SPEED = 25 MPHNO COUNTS AVAILABLE


RECONSTRUCTION

2.0" SP-12.5 ASPHALT 6" GRADED AGGREGATE BASE (98% MODIFIED PROCTOR, LBR 100) 12" STABILIZATION (LBR 40)









TYPICAL SECTION 03 RENEE TERRACE STA. 18+12.89 TO STA. 18+71.22

TYPICAL SECTION 02 RENEE TERRACE STA. 13+08.00 TO STA. 13+20.00

REVISIONS DATE DESCRIPTION

PHILLIP J. WALKER P.E. LICENSE NUMBER 87701 HDR ENGINEERING, INC. 25 WEST CEDAR STREET, SUITE 200 PENSACOLA, FL 32502-5945



ESCAMBIA COUNTY ENGINEERING DEPARTMENT

RENEE TERRACE DRAINAGE *IMPROVEMENTS*

TYPICAL SECTIONS

SHEET NO.

5

3/14/2024

GENERAL NOTES:

- THE CONTRACTORS SHALL NOTIFY THE COUNTY DESIGN ENGINEER OR DESIGNEE 48 HOURS PRIOR TO CONSTRUCTION
- ALL CONDITIONS AND STIPULATIONS OF THE CONSTRUCTION PERMITS AND THE APPROVALS ISSUED BY THE ESCAMBIA COUNTY ENGINEER SHALL BE COMPLIED WITH IN EVERY DETAIL
- ALL ROADS DAMAGED BY CONSTRUCTION OPERATIONS ARE TO BE PATCHED OR RECONSTRUCTED AS DIRECTED BY THE COUNTY ENGINEER OR DESIGNEE.
- THE CONTRACTOR SHALL TAKE STEPS NECESSARY TO PREVENT EROSION AND ANY OFF SITE SEDIMENT TRANSPORT RESULTING FROM INCREASED RUNOFF DURING CONSTRUCTION BY PROVIDING SILT FENCE, FLOATING TURBIDITY BARRIER AND/OR STAKED HAY BALES AS REQUIRED BY THE FLORIDA STORMWATER, EROSION, AND SEDIMENT CONTROL INSPECTOR'S MANUAL, JULY 2018 EDITION, OR AS INDICATED ON THE PLANS. ALL EROSION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL ASSOCIATED DISTURBED AREAS ARE STABILIZED AS TO REDUCE SEDIMENT RUNOFF, UNLESS OTHERWISE DIRECTED BY THE ENGINEER OR DESIGNEE.
- ANY NECESSARY PERMITS WILL BE THE RESPONSIBILITY OF THE CONTRACTOR. ESCAMBIA COUNTY OR ITS DESIGNEE WILL ASSIST CONTRACTOR WITH REQUIRED PERMITS.
- THE CONTRACTOR IS CAUTIONED TO VISIT THE SITE AND FAMILIARIZE THEIR SELF WITH THE PROJECT PRIOR TO BIDDING AND/OR
- IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PRESERVE OR RELOCATE ALL BENCHMARKS (VERTICAL CONTROL) AS NEEDED DURING CONSTRUCTION. ALL PUBLIC OR PRIVATE CORNER MONUMENTATION SHALL BE PROTECTED. IF A PUBLIC OR PRIVATE CORNER MONUMENTATION IS IN DANGER OF BEING DESTROYED AND HAS NOT BEEN PROPERLY REFERENCED, THE CONTRACTOR SHALL NOTIFY THE ENGINEER OR DESIGNEE IMMEDIATELY. ANY ESCAMBIA COUNTY HARN/GPS NETWORK MONUMENTS OR BUREAU OF SURVEY AND MAPPING GPS NETWORK MONUMENTS WITHIN THE LIMITS OF CONSTRUCTION SHALL BE PROTECTED. IF A HARN/GPS NETWORK MONUMENTS OR BUREAU OF SURVEY AND MAPPING GPS NETWORK MONUMENTS ARE DISTURBED OR DESTROYED THE CONTRACTOR SHALL BE RESPONSIBLE FOR RELACEMENT REPLACEMENT OF THE MONUMENTS AND HAVE THE MONUMENTS POSITION DETERMINED BY A FLORIDA LICENSED PROFESSIONAL SURVEYOR AND MAPPER USING GUIDELINES AS ESTABLISHED BY NATIONAL GEODETIC SURVEY FOR BLUE BOOKING AND APPROVAL.
- EXISTING DRAINAGE FEATURES WITHIN CONSTRUCTION LIMITS SHALL REMAIN UNLESS OTHERWISE NOTED.
- THE CONTRACTOR SHALL MATCH EXISTING CONDITIONS AT THE BEGINNING AND END OF CONSTRUCTION AS DIRECTED BY THE COUNTY ENGINEER OR DESIGNEE.
- EXISTING STREETS AND DRIVES SHALL BE MAINTAINED TO LOCAL TRAFFIC AND PROPERTY OWNERS.
- ALL MATERIALS, TESTING, AND CONSTRUCTION METHODS SHALL CONFORM TO THE ESCAMBIA COUNTY TECHNICAL SPECIFICATIONS, LATEST EDITION.
- ANY REFERENCE TO FDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION, DIVISION 1, GENERAL REQUIREMENTS AND COVENANTS, SHALL BE EXCLUDED AND NOT APPLICABLE TO ANY SPECIFICATION REFERRED HEREIN OR OTHERWISE LISTED IN THESE PLANS OR RELATED DOCUMENTS OR THE ESCAMBIA COUNTY TECHNICAL SPECIFICATIONS.
- CONTRACTOR SHALL COMPLY WITH ALL F.D.E.P. AND ARMY CORP. OF ENGINEERS REQUIREMENTS. THE PROJECT IS PERMITTED BY 13. NWFWMD (GEN-033-314020-1)
- ONLY ACCESS TO THE EASEMENTS AS SHOWN ARE GUARANTEED BY THE COUNTY. PRIVATE R/W REQUIRED BY THE CONTRACTOR TO FACILITATE CONSTRUCTION SHALL BE ACQUIRED BY THE CONTRACTOR WITH NO ADDITIONAL COMPENSATION OR ASSISTANCE FROM THE
- 15. IN THE EVENT THAT SURVEY MONUMENTATION OR REFERENCE POINTS ARE MISSING OR HAVE BEEN DESTROYED, PLEASE CONTACT:

JOE BARRETT, PSM ESCAMIBA COUNTY ENGINEERING DEPARTMENT 3363 WEST PARK PLACE PENSACOLA, FLORIDA 32505 PH (850) 595-3440

REVISIONS

DESCRIPTION

DATE

- DIRECT SPECIAL ATTENTION TO THE PROTECTION OF ALL GEODETIC MONUMENTS, HORIZONTAL OR VERTICAL, AND PUBLIC LAND SURVEY CORNERS LOCATED WITHIN THE PROJECT, IF ANY GEODETIC MONUMENT OR PUBLIC LAND SURVEY CORNER, LOCATED WITHIN THE PROJECT, IS AT RISK OF BEING DAMAGEDOR DESTROYED, IMMEDIATELY NOTIFY THE COUNTY ENGINEER OR DESIGNEE. IN ADDITION, CONTACT JOE BARRETT, ESCAMBIA COUNTY SURVEYOR, TO OBTAIN APPROVAL TO LOCATE AND REPLACE ANY DAMAGED OR DESTROYED GEODETIC MONUMENTS OR PUBLIC LAND SURVEY CORNERS UNDER THE DIRECTION OF A PROFESSIONAL SURVEYOR AND MAPPER REGISTERED IN THE STATE OF FLORIDA.
- 17. VEGETATION ON R/W AND EASEMENTS SHALL BE RESTORED TO ORIGINAL CONDITION UNLESS OTHERWISE NOTED ON THE PLAN SHEETS. COST OF SAID RESTORATION SHALL BE CONSIDERED INCIDENTAL TO OTHER PAY ITEMS.
- ONLY TREES WHICH ARE IN DIRECT CONFLICT WITH THE PROPOSED IMPROVEMENTS SHALL BE REMOVED UNLESS OTHERWISE NOTED IN THE PLANS. JIMMIE JARRATT, THE ESCAMBIA COUNTY ARBORIST, SHALL BE NOTIFIED AT (850) 595-3535, 48 HOURS PRIOR TO ANY TREE IMPACTS NOT PREVIOUSLY
- ALL COMPACTED FILL SHALL BE PLACED IN 4" LIFTS FOR HAND POWERED TAMPERS AND 8" LIFTS FOR HEAVY EQUIPMENT OPERATED
- PIPE LENGTHS SHOWN IN THE PLANS DO NOT INCLUDE THE LENGTH OF PIPE THAT MUST BE INSTALLED WITH THE MITERED END SECTION. THEREFORE, ALL PIPES LENGTHS ASSOCIATED WITH MITERED END SECTIONS SHALL BE PAID FOR IN THE UNIT COST OF THE MITERED END SECTION.
- IF ARCHAEOLOGICAL MATERIAL/PREHISTORIC ARTIFACTS SUCH AS POTTERY OR CERAMICS, STONE TOOLS OR METAL IMPLEMENTS, OR ANY OTHER PHYSICAL REMAINS THAT COULD BE ASSOCIATED WITH NATIVE AMERICAN CULTURES, OR EARLY COLONIAL OR AMERICAN SETTLEMENT ARE ENCOUNTERED AT ANY TIME, THE PROJECT SHOULD CEASE ALL ACTIVITIES INVOLVING SUBSURFACE DISTURBANCE IN THE IMMEDIATE VICINITY OF SUCH DISCOVERIES. THE APPLICANT/RECIPIENT, OR OTHER DESIGNEE, SHOULD CONTACT THE FLORIDA DEPARTMENT OF STATE, DIVISION OF HISTORICAL RESOURCES, THE STATE HISTORIC PRESERVATION OFFICER (SHPO) AND THE DSH/FEMA REGION IV ENVIRONMENTAL OFFICER AND FDEM STATE ENVIRONMENTAL LIAISON OFFICER FOR FURTHER GUIDANCE. PROJECT ACTIVITIES SHOULD NOT RESUME WITHOUT VERBAL AND/OR WRITTEN AUTHORIZATION FROM THE DIVISION OF HISTORICAL
- IN THE EVENT THAT UNMARKED HUMAN REMAINS ARE ENCOUNTERED DURING PERMITTED ACTIVITIES, ALL WORK MUST STOP 22. IMMEDIATELY AND THE PROPER AUTHORITIES NOTIFIED IN ACCORDANCE WITH F.S. 872.05.

FINAL MAILBOX LOCATION'S MUST FOLLOW USPS GUIDANCE AND SHOULD BE NEAR THE EXISTING MAILBOX LOCATION OR TO SUIT OWNER

UTILITY NOTES:

- THE LOCATION SHOWN FOR EXISTING UNDERGROUND UTILITIES IS APPROXIMATE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK IN EACH AREA. THE CONTRACTOR AGREES TO BE COMPLETELY RESPONSIBLE FOR ALL DAMAGES WHICH MIGHT OCCUR BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ALL UTILITIES
- UTILITY OWNERS SHALL BE NOTIFIED AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION SO THAT THE UTILITY OWNER CAN SPOT VERIFY AND/OR EXPOSE THEIR UTILITIES. KNOWN UTILITY OWNERS ACCORDING TO THE SUNSHINE ONE

WATER/SEWER - EMERALD COAST UTILITY AUTHORITY MR. JACOB KEARLEY PH: (850) 969-5823 JACOB.KEARLEY@ECUA.FL.GOV

COX COMMUNICATION MR. TROY YOUNG PH: (850) 857-4510 TROY.YOUNG@COX.COM

NATURAL GAS - PENSACOLA ENERGY MR. ANDREW BRISKE PH: (850) 324-1852 ABRÌSKE@CITYOFPENSACOLA.COM

SUNSHINE STATE ONE-CALL 7200 LAKE ELLENOR DRIVE, SUITE 200 ORLANDO, FL. 32809 PH: (800) 432-4770 ELECTRIC - FLORIDA POWER & LIGHT MR. STEPHEN HARRIS PH: (850) 516-8499 STEPHEN.HARRIS@FPL.COM

TELEPHONE - AT&T FLORIDA MR. TOM MANNING PH: (850) 463-5176 TM2709@ATT.COM

- CONTRACTOR IS TO USE CAUTION WHEN WORKING IN OR AROUND AREAS OF OVERHEAD POWER LINES AND UNDERGROUND UTILITIES.
- UTILITIES TO REMAIN AND BE PROTECTED DURING CONSTRUCTION. NECESSARY REPAIRS SHALL BE CONSIDERED INCIDENTAL TO OTHER PAY ITEMS AND SHALL BE TO THE SATISFACTION OF UTILITY OWNERS.
- WATER SERVICE LINES SHALL BE LOCATED AND PROTECTED.

ESCAMBIA COUNTY ENGINEERING DEPARTMENT

RENEE TERRACE DRAINAGE *IMPROVEMENTS*

GENERAL NOTES

SHEET NO.

6

PENSACOLA, FL 32502-5945


PHILLIP J. WALKER


P.E. LICENSE NUMBER 87701


25 WEST CEDAR STREET, SUITE 200


HDR ENGINEERING, INC.


3/14/2024 12:36:30 PM





























SITE-SPECIFIC EROSION AND SEDIMENT CONTROL PLAN

THE CONTRACTOR'S PROFESSIONAL ENGINEER (PE), OR CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC) WILL PREPARE AND SUBMIT A SITE-SPECIFIC EROSION AND SEDIMENT CONTROL PLAN TO ESCAMBIA COUNTY FOR REVIEW AND APPROVAL PRIOR TO ANY WORK BEING PERFORMED. THE EROSION AND SEDIMENT CONTROL PLAN SHALL FOLLOW GUIDELINES DOCUMENTED IN THE STATE OF FLORIDA, EROSION AND SEDIMENT CONTROL - DESIGNER AND REVIEWER MANUAL, DATED JUNE 2007, UPDATED 2013 (http://www.fdot.govroadway/drainage/files/Erosion-Sediment-Control.pdf).

AT A MINIMUM, THE EROSION AND SEDIMENT CONTROL PLANS FOR THIS PROJECT REQUIRE SEDIMENT BARRIER TO BE PLACED WHERE THERE IS POTENTIAL FOR TURBID STORMWATER RUNOFF TO DISCHARGE OFF-SITE. INLET PROTECTION IS REQUIRED FOR ALL INLETS THAT COULD RECEIVE RUNOFF FROM DISTURBED AREAS. ARTIFICIAL COVERINGS AND TEMPORARY SLOPE DRAINS ARE REQUIRED IN AREAS WITH HIGH SLOPES. RUNOFF CONTROL STRUCTURES WILL BE REQUIRED WITHIN ALL CHANNELS. A SOIL TRACKING PREVENTION DEVICE SHALL BE INSTALLED AT POINTS OF EGRESS FROM UN-STABLIZED AREAS OF THE PROJECT TO PUBLIC ROADS WHERE OFF-SITE TRACKING OF MUD COULD OCCUR.

PAY PARTICULAR ATTENTION TO THE PROTECTION OF UPLAND BUFFERS, NON-IMPACTED WETLANDS, AND SURFACE WATERS ADJACENT TO THE LIMITS OF WORK TO PREVENT TURBID DISCHARGES TO THESE AREAS.

THE MEASURES LISTED ABOVE AND SHOWN ON THE PLANS ARE THE MINIMUM REQUIREMENTS WITH ADDITIONAL CONTROLS TO BE UTILIZED AS NEEDED, DEPENDENT UPON ACTUAL SITE CONDITIONS AND CONSTRUCTION OPERATIONS AND PHASING

1. SITE DESCRIPTION:

CONSTRUCTION ACTIVITY INCLUDES NEW CONSTRUCTION, STORM SEWER, DITCH GRADING, AND SEDIMENT BASIN GRADING

5991 RENEE TERRACE, PENSACOLA, FL 32507

CONSTRUCTION OF STORMWATER OUTFALL SYSTEM TO REDUCE THE FREQUENCY OF CLOSED BASIN FLOODING AND IMPROVE LOCAL CONVEYANCE.

THE MAJOR SOIL DISTURBING ACTIVITIES INCLUDE STORM DRAIN, DRIVEWAY, AND ROADWAY RECONSTRUCTION.

TOTAL AREA TO BE DISTURBED:

RUNOFF COEFFICIENTS:

C = 0.60 (BEFORE)

C = 0.75 (DURING)

DATE

(2) ESTIMATES OF SIZE OF PROJECT AREA FOR EACH OUTFALL. PERDIDO BAY. STORM DRAIN SYSTEM - TOTAL AREA 1.66 ACRES

(3) LOCATIONS OF OUTFALLS:

OUTFALL TO PERDIDO BAY: LAT N30° 18' 59.47", LONG. W87° 26' 59.48"

(4) DESCRIPTION OF SOIL OR QUALITY OF DISCHARGE: SOILS ARE PRIMARILY RESOTA SAND.

TEMPORARY EROSION CONTROL MEASURES ARE SHOWN ON THE EROSION CONTROL PLANS AND PERMANENT EROSION CONTROL MEASURES ARE SHOWN IN THE CONSTRUCTION PLANS.

a. EROSION AND SEDIMENT CONTROLS:

(1) STABILIZATION PRACTICES:

_____X__TEMPORARY SODDING <u>X</u> ARTIFICIAL COVERING X BUFFER ZONES ___TEMPORARY GRASSING

X PERMANENT PLANTING, SODDING, OR SEEDING PRESERVATION OF NATURAL RESOURCES TEMPORARY MULCHING

-LOCATION OF ARTIFICIAL COVERING IS TO BE DETERMINED BASED ON SITE CONDITIONS -THIS LIST MAY NOT INCLUDE ALL MEASURES BASED ON ACTUAL SITE CONDITIONS

STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICAL, BUT IN NO CASE MORE THAN 14 DAYS, IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED.

THE CONTRACTOR IS ALSO RESPONSIBLE FOR DOCUMENTING THIS PORTION OF THE SWPPP IN THE EROSION CONTROL PLAN SUBMITTED TO THE COUNTY.

(2) STRUCTURAL PRACTICES:

_SEDIMENT TRAPS SAND BAGGING X SEDIMENT BARRIER ____ SEDIMENT BASINS __ SYNTHETIC BALES STORM INLET SEDIMENT TRAP STONE OUTLET STRUCTURES __DIVERSION, INTERCEPTOR, OR PERIMETER DITCHES _____CURBS AND GUTTERS ____PIPE SLOPE DRAINS X_STORM SEWERS X VELOCITY CONTROL DEVICES

FLUMES X ROCK BEDDING AT CONSTRUCTION EXIT TIMBER BEDDING AT CONSTRUCTION EXIT

_RUNOFF CONTROL STRUCTURE X INLET PROTECTION

X WATTLES LOCATIONS OF STORM DRAINS, AND RIP RAP ARE SHOWN ON THE CONSTRUCTION

X RIPRAP

___ FLOATING TURBIDITY BARRIER

PLANS. THIS LIST MAY NOT INCLUDE ALL CONTROL MEASURES. ACTUAL SITE CONDITIONS MAY REQUIRE ADDITIONAL CONTROL MEASURES.

SEDIMENT BARRIER WILL BE USED TO PROTECT ALL UNDISTURBED WETLANDS.

THE CONTRACTOR IS ALSO RESPONSIBLE FOR DOCUMENTING THIS PORTION OF THE SWPPP IN THE EROSION CONTROL PLAN SUBMITTED TO THE COUNTY.

b. DESCRIPTION OF SEDIMENT BASINS:

c. OTHER CONTROLS

(1) WASTE DISPOSAL:

THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DOCUMENTING THIS PORTION OF THE SWPPP IN THE EROSION CONTROL PLAN SUBMITTED TO THE COUNTY

(2) OFFSITE VEHICLE TRACKING:

- X HAUL ROADS DAMPENED FOR DUST CONTROL
- X LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- X EXCESS DIRT ON ROAD REMOVED DAILY
- X STABILIZED CONSTRUCTION ENTRANCES

THE CONTRACTOR IS ALSO RESPONSIBLE FOR DOCUMENTING THIS PORTION OF THE SWPPP IN THE EROSION CONTROL PLAN SUBMITTED TO THE COUNTY.

THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DOCUMENTING THIS PORTION OF THE SWPPP IN THE EROSION CONTROL PLAN SUBMITTED TO THE COUNTY.

(4) FERTILIZERS AND PESTICIDES:

FERTILIZER WILL BE APPLIED ACCORDING TO APPLICABLE SUBSECTIONS OF THE ESCAMBIA COUNTY GENERAL PAVING & DRAINAGE TECHNICAL SPECICATIONS. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DOCUMENTING THE USE OF PESTICIDES IN THE EROSION CONTROL PLAN SUBMITTED TO

(5) TOXIC SUBSTANCES (INCLUDING SPILL REPORTING):

THE CONTRACTOR IS RESPONSIBLE FOR DOCUMENTING THIS PORTION OF THE SWPPP IN THE EROSION CONTROL PLAN SUBMITTED TO THE COUNTY. IF CONTAMINATED SOIL OR GROUNDWATER IS ENCOUNTERED, CONTACT THE COUNTY PROJECT MANAGER IMMEDIATELY.

d. FEDERAL, STATE, AND LOCAL PLANS, AND PERMITS:

- NORTHWEST FLORIDA WATER MANAGEMENT DISTRICT, 1/2 GENERAL PERMIT (403.814 (12) F.S)
- FDEP NPDES GENERIC PERMIT FOR STORMWATER DISCHARGE FROM CONSTRUCTION SITE,
- (CH 62-621 FAC) TO BE OBTAINED BY THE CONTRACTOR
- THERE ARE NO WETLANDS IN THE PROJECT LIMITS

3. MAINTENANCE:

MAINTENANCE OF PERMANENT AND TEMPORARY FEATURES SHALL BE DONE IN ACCORDANCE WITH THE ESCAMBIA COUNTY GENERAL PAVING & DRAINAGE TECHNICAL SPECIFICATIONS

THE CONTRACTOR IS ALSO RESPONSIBLE FOR DOCUMENTING THIS PORTION OF THE SWPPP IN THE EROSION CONTROL PLAN SUBMITTED TO THE COUNTY.

4. INSPECTION:

THE CONTRACTOR IS SOLELY RESPONSIBLE FOR INSPECTIONS OF EROSION CONTROL FEATURES. QUALIFIED PERSONNEL SHALL INSPECT THE FOLLOWING ITEMS AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.25 INCHES OR GREATER. WHERE SITES HAVE BEEN FINALLY STABILIZED, INSPECTIONS SHALL BE CONDUCTED AT LEAST ONCE

- -POINTS OF DISCHARGE FROM THE PROJECT SITE
- -DISTURBED AREAS OF THE SITE THAT HAVE NOT BEEN FINALLY STABILIZED
- -AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION
- -SEDIMENT BASINS
- -LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE

5. NON-STORMWATER ACTIVITIES:

THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL DEWATERING PERMITS AND IDENTIFYING ALL ANTICIPATED NON-STORMWATER DISCHARGES.

REVISIONS



PHILLIP J. WALKER P.E. LICENSE NUMBER 87701 HDR ENGINEERING, INC. 25 WEST CEDAR STREET, SUITE 200 PENSACOLA, FL 32502-5945



ESCAMBIA COUNTY ENGINEERING DEPARTMENT

RENEE TERRACE DRAINAGE *IMPROVEMENTS*

STORM WATER POLLUTION PREVENTION PLAN

SHEET NO.

18

