


FILE NAME: 21-210 COVER.DWG



construction. This DO approval does not constitute approval by any other gency. All additional state/federal permits shall be provided to the county prior to approval of a final plat or the issuance of state/federal permits shall be provided to the county prior to approval of a final plat or the issuance of a uilding permit.

VICINITY MAP N.T.S.



Hendry


Broward

	INDEX TO SHEETS
1	COVER SHEET
CE2	DEVELOPMENT PLAN
CE3	DRAINAGE PLAN
CE4	GRADING PLAN KEY PLAN
CE5-11	GRADING PLAN
CE12	EROSION CONTROL PLAN
CE13	ENVIRONMENTALLY SENSITIVE AREAS
CE14	EROSION CONTROL DETAILS
CE15-19	DETAILS AND TYPICAL SECTIONS
CE20	POND SECTIONS
CE21	SPECIFICATIONS


NOTE:

DRAWING PREPARED IN AN 11X17 FORMAT. THE SCALE OF THESE PLANS MAY HAVE CHANGED DUE TO REPRODUCTION.

ISSUE DATE: 07/28/22



FPL SPARKLEBERRY SOLAR **ENERGY CENTER**



FPL SPARKLEBERRY SOLAR ENERGY CENTER ESCAMBIA COUNTY, FL

OWNER

FLORIDA POWER AND LIGHT COMPANY

PROJECT

FPL SPARKLEBERRY SOLAR ENERGY CENTER LOCATION: APPROXIMATELY 1.5 MILES SOUTH WEST OF THE COUNTY ROAD 97 AND PILGRIM TRAIL INTERSECTION.

SITE COVERAGE

PERVIOUS/IMPERVIOUS TABLE					
DESCRIPTION	SQ.FT. ACREAGE		% OF SITE		
INVERTER	23,000.00	0.53	0.09%		
VAULT	682.00	0.01	0.003%		
TOTAL IMPERVIOUS	23,682.00	0.54	0.093%		
ACCESS ROAD	587,006.42	13.48	2.44%		
SOLAR COLLECTOR YARD	93,000.00	2.13	0.38%		
TOTAL SEMI IMPERVIOUS	680006.42	15.61	2.82%		
TOTAL PERVIOUS	20,813,920.48	536.54	97.08%		
PROJECT AREA	21,516,926.90	552.68	100.00%		
PROJECT AREA (FENCED)	20,721,747.84	475.71	81.66%		

NOTES:

1. SERVICE PATHS HAVE BEEN ANALYZED AS 16' WIDE.

- 2. ALL DISTURBED AREAS SHALL BE SEEDED UNLESS SPECIFIED OTHERWISE.
- 3. ALL WETLANDS, WETLAND BUFFERS RIVERINE SETBACKS/ SHORELINE PROTECTION ZONES, & VEGETATED NATURAL BUFFERS SHALL REMAIN IN THEIR NATURAL, VEGETATED STATE AT ALL TIMES.
- 4. ALL ADEQUATE TREE PROTECTION MEASURES AND BARRICADES SHALL BE PROPERLY INSTALLED PRIOR TO SITE DISTURBANCE, INSPECTED REGULARLY, AND MAINTAINED IN GOOD WORKING ORDER UNTIL PROJECT IS COMPLETE AND SITE BECOMES STABILIZED.
- 5. PER ESCAMBIA COUNTY'S LAND DEVELOPMENT CODE, ALL PROTECTED TREE REMOVAL, LAND CLEARING, PLACEMENT OF FILL MATERIAL ONSITE, CUTTING, GRADING, EXCAVATING, BERMING, OR ANY OTHER LAND DISTURBING ACTIVITIES THAT MAY ALTER LAND TOPOGRAPHY OR VEGETATIVE COVER SHALL BE PERMITTED OR OTHERWISE APPROVED IN WRITING BY THE COUNTY PRIOR TO INITIATION OF SUCH SITE WORK.

NSIST MAIN FEMA	SURFACING ACCESS PATHS : STABILIZED AGGREGATE BASE INVERTER : AGGREGATE SURFACE SOLAR COLLECTOR YARD : AGGREGATE SURFACE OPEN SPACE : GRASSED AREA JUL 28	202
TED I 100 PPER	JAMES P. TERPENING JR, P.E. FL. REG. NO. 24276	_
	DEVELOPMENT PLAN	

CE2





2: \Proi-2021\21-210 FPL - Sparkleherry Salar Energy Center\Eng\21-210 Rase dwg Plotted: 6 /20 /2022 11: 38 AM By KITHSIPL LINICAMA


	N
Q Q	300 600
	FEET
POND BRANCH <u>LEGEND</u>	
VIA SHEET FLOW	PROJECT BOUNDARY FENCE LINE
	CONVEYANCE SWALE
	BASIN LINE OFFSITE BASIN LINE
	FLOOD ZONE LINE
	INVERTER (IMPERVIOUS)
	TURN-AROUND (SEMI- IMPERVIOUS) SERVICE PATHS
	SEMI-IMPERVIOUS)
	WETLAND REQUIRED 25' BUFFER
	RETENTION AREA
OUTFALL TO POND BRANCH	VEGETATED NATURAL BUFFER
VIA SHEET FLOW	PV MODULE
WATER CROSSING	FEMA FLOOD PLAIN
	BASIN OUTFALL
CONVEYANCE SWALE	OFFSITE CONTRIBUTING FLOW
	PROPOSED PIPES
▲ -	CHECK DAM
NOTES: 1. ALL WETLANDS, WETLAND BU SHORELINE PROTECTION ZON BUFFERS SHALL REMAIN IN AT ALL TIMES.	
FILL MATERIAL ONSITE, CUTT BERMING, OR ANY OTHER LA MAY ALTER LAND TOPOGRAP	LAND CLEARING, PLACEMENT OF ING, GRADING, EXCAVATING, ND DISTURBING ACTIVITIES THAT PHY OR VEGETATIVE COVER SHALL E APPROVED IN WRITING BY THE
OUTFALL TO POND BRANCH VIA SHEET FLOW	
	JUL 28 2022
2	LICENSE TER
	JAMES P. TERPENING JA P.E. FL. REG. NO. 24276
DRAINAGE PLA	SORIDA SHEET
	CE3





FPL SPARKLEBERRY SOLAR ENERGY CENTER
















\Proj-2021\21-210 FPL - Sparkleberry Solar Energy Center\Eng\21-210 Base.dwg Plotted: 6/28/2022 5:43 PM Bv: KITHSIRI UDUGAMA







: \Proi-2021\21-210 FPL - Sparkleberry Solar Energy Center\Eng\21-210 Base.dwg Plotted: 6/29/2022 11:34 AM By: KITHSIR! UDUGAMA



	TABLE1-	TREE SURVAY		
TREE ID	SCIENTIFIC NAME	DBH (IN)		
T-1 <mark></mark>	18 SOUTHERN RED OAK QUERCUS FALCATA			
T-2 🚫	WATER OAK	QUERCUS NIGRA	20.	
T-3	SOUTHERN MAGNOLIA	MAGNOLIA GRANDIFLORA	14.	
T-4	SOUTHERN MAGNOLIA	MAGNOLIA GRANDIFLORA	16.	
T-5	SOUTHERN MAGNOLIA	MAGNOLIA GRANDIFLORA	16.	
T-6	SWEETGUM	LIQUIDAMBAR STYRACIFLUA	12.	
T-7	LAUREL OAK	QUERCUS LAURIFOLIA	15.	
T-8	SWEETGUM	LIQUIDAMBAR STYRACIFLUA	12.	
T-9	WATER OAK	QUERCUS NIGRA	16.	
T-10	WATER OAK	QUERCUS NIGRA	13.	
T-11	SOUTHERN RED OAK	QUERCUS FALCATA	29.	
T-12	SWEETGUM	LIQUIDAMBAR STYRACIFLUA	12.	
T-13	WATER OAK	QUERCUS NIGRA	15.	
T-14🚫	WATER OAK	QUERCUS NIGRA	16.	
T-15🚫	SOUTHERN RED OAK	QUERCUS FALCATA	15.	
T-16	WATER OAK	QUERCUS NIGRA	12.	
T-17	WATER OAK	QUERCUS NIGRA	12.	
T-18	WATER OAK	QUERCUS NIGRA	14.	


*SEE TREE SURVEY BY GOLDER ON 6-12-2021 FOR TREE IDS TOTAL DBH (IN) EQUALS 306.4 INCHES.

TABLE 2 - WETLAND					
WL & SW ID WL & SW TYPE WL & SW SIZE WETL (FLUCFCS) (ac.) IMPACT				WL & SW BUFFER (ac.)	WETLAND SETBACK (ft)
WELAND 1 630.00		25.93	0.00	3.13	25.0
WELAND 2	WELAND 2 641.00 2		0.00	1.1	25.0
WELAND 3	630.00	0.29	0.00	0.16	25.0
WETLAND 4	641.00	0.05	0.00	0.16	25.0
	TOTAL	28.83	0.00	4.55	

NOTES:


- 1. ALL WETLANDS, WETLAND BUFFERS RIVERINE SETBACKS/ SHORELINE PROTECTION ZONES, & VEGETATED NATURAL BUFFERS SHALL REMAIN IN THEIR NATURAL, VEGETATED STATE AT ALL TIMES.
- 2. ALL ADEQUATE TREE PROTECTION MEASURES AND BARRICADES SHALL BE PROPERLY INSTALLED PRIOR TO SITE DISTURBANCE, INSPECTED REGULARLY, AND MAINTAINED IN GOOD WORKING ORDER UNTIL PROJECT IS COMPLETE AND SITE BECOMES STABILIZED.
- 3. PER ESCAMBIA COUNTY'S LAND DEVELOPMENT CODE, ALL PROTECTED TREE REMOVAL, LAND CLEARING, PLACEMENT OF FILL MATERIAL ONSITE, CUTTING, GRADING, EXCAVATING, BERMING, OR ANY OTHER LAND DISTURBING ACTIVITIES THAT MAY ALTER LAND TOPOGRAPHY OR VEGETATIVE COVER SHALL BE PERMITTED OR OTHERWISE APPROVED IN WRITING BY THE COUNTY PRIOR TO INITIATION OF SUCH SITE WORK.
- 4. ALL GOPHER TORTOISE HAVE BEEN RELOCATED FROM THE PROJECT AREA UNDER PERMIT No. GTC-22-00225
- 5. ALL WETLANDS, TREES, AND LAND USE BOUNDARIES DEPICTED ON THIS SHEET HAVE BEEN DELINEATED BY GOLDER.
- 6. 93" OF PROTECTED TREES PROPOSED FOR REMOVAL FOR THIS PROJECT X .5 (REPLACEMENT RATIO) = 47 CALIPER INCHES (CI'S) REQUIRED TO BE REPLACED/ MITIGATED. 47 CI'S/2.5 CI'S REQUIRED FOR EACH REPLACEMENT TREE=19 TREES 19 X \$350 EACH PER TREE PER ESCAMBIA COUNTY'S LAND DEVELOPMENT CODE & CURRENT FEE SCHEDULE = \$6,650. A CONTRIBUTION TO ESCAMBIA COUNTY'S TREE RESTORATION FUND IN THIS AMOUNT SHALL BE MADE PRIOR TO THE RELEASE FOR THE PROJECT'S DEVELOPMENT ORDER (DO) PARKER TERPEN


~	H	JUL	28.	JAMES PESTERPE FL. REG. MONT	NUNGE JR, P.E.
	ENVIRONMENTALLY SE		TIN	F ARFAS	SHEET NO.
					CE13




BEST MANAGEMENT PRACTICES (BMPS) WILL BE IMPLEMENTED DURING THE CONSTRUCTION PHASE AND DURING THE OPERATION PHASE TO ENSURE THE SITE IS STABILIZED WITH PERMANENT VEGETATIVE COVER. PRIOR TO CONSTRUCTION, A STORMWATER POLLUTION PREVENTION PLAN (SWPPP) WILL BE DEVELOPED THAT WILL INCLUDE IMPLEMENTATION OF SPECIFIC BMPS FOR GRASSING DISTRIBUTED BARE SOIL AND BARE SPOT AREAS, COMPLETING INSPECTIONS OF DISTURBED AREAS AND RE-GRASSING, IF NECESSARY TO ACHIEVE STABILIZATION. VEGETATION WILL BE ESTABLISHED BY SEEDING/FERTILIZATION, HYDROSEEDING, AND/OR SODDING. SEED BLENDS WILL INCLUDE MIXTURES OF BAHIA, MILLET, AND/OR RYEGRASS (BASED ON SEASONAL VARIABILITY AND MATERIAL AVAILABILITY). THROUGH INSPECTIONS AND IMPLEMENTATION OF BMPS TO ESTABLISH VEGETATION WITHIN THE PANEL AREAS AND VNB AREAS, SITE CONDITIONS REPRESENTATIVE OF THE DESIGN POST-DEVELOPMENT LAND COVER CONDITIONS WILL BE ACHIEVED. THE REQUEST TO CONVERT THE SITE FROM CONSTRUCTION PHASE TO OPERATION PHASE WILL NOT BE SUBMITTED TO FDEP UNTIL FINAL STABILIZATION IS ACHIEVED ACROSS THE SITE (70% VEGETATION DENSITY OR GREATER). AT A MINIMUM, THE OPERATION & MAINTENANCE PROCEDURES INCLUDED IN THE STORMWATER MANAGEMENT PLAN WILL BE FOLLOWED DURING THE OPERATION PHASE TO ENSURE THE SITE STORMWATER MANAGEMENT BMPS ARE FUNCTIONING AS PERMITTED AND DESIGNED, AND CORRECTIVE ACTIONS (INCLUDING STABILIZATION) ARE TAKEN NECESSARY.


JUL 28 JUL 28 NO.2427 JAMES P. TERPEN FL. REG. NO. 2427	
SWPP DETAILS	SHEET NO.
SMIT DETAILS	CE14









V BY:



2: \Proi-2021\21-210 FPL - Sparkleberry Solar Fneray Center\Fna\21-210 Details.dwa Plotted: 6/27/2022 4:26 PM By: KITHSIRI UDUGAMA





			NO	ITES:
			1.	THE PROJECT ENGINEER (ENGINEER OF RECORD) SHALL PROVIDE TO ESCAMBIA COUNTY "AS-BUILT" RECORD DRAWINGS FOR VERIFICATION AND APPROVAL BY ESCAMBIA COUNTY ONE WEEK PRIOR TO REQUESTING A FINAL INSPECTION AND CERTIFICATE OF OCCUPANCY, OR PROVIDE "AS-BUILT" CERTIFICATION THAT THE PROJECT CONSTRUCTION ADHERES TO THE PERMITTED PLANS AND SPECIFICATIONS. THE "AS-BUILT" CERTIFICATION OR THE "AS-BUILT" RECORD DRAWINGS MUST BE SIGNED, SEALED AND DATED BY A REGISTERED FLORIDA PROFESSIONAL ENGINEER
			2.	ALL ASPECTS OF THE STORMWATER/DRAINAGE COMPONENTS AND/OR TRANSPORTATION COMPONENTS SHALL BE COMPLETED PRIOR TO ISSUANCE OF A FINAL A FINAL CERTIFICATE OF OCCUPANCY.
			3.	NO DEVIATIONS OR REVISIONS FROM THESE PLANS BY THE CONTRACTOR SHALL BE ALLOWED WITHOUT PRIOR APPROVAL FROM BOTH THE DESIGN ENGINEER AND THE ESCAMBIA COUNTY. ANY DEVIATIONS MAY RESULT IN DELAYS IN OBTAINING A CERTIFICATE OF OCCUPANCY.
			4.	THE CONTRACTOR SHALL INSTALL PRIOR TO THE START OF CONSTRUCTION AND MAINTAIN DURING CONSTRUCTION ALL SEDIMENT CONTROL MEASURES ARE REQUIRED TO RETAIN ALL SEDIMENTS ON THE SITE. IMPROPER SEDIMENT CONTROL MEASURES MAY RESULT IN CODE ENVIRONMENT VIOLATION.
			5.	RETENTION/DETENTION AREAS SHALL BE SUBSTANTIALLY COMPLETE PRIOR TO ANY CONSTRUCTION ACTIVITIES THAT MAY INCREASE STORM WATER RUNOFF RATES. THE CONTRACTOR SHALL CONTROL STORMWATER DURING ALL PHASES OF CONSTRUCTION AND TAKE ADEQUATE MEASURES TO PREVENT THE EXCAVATED POND FROM BLINDING DUE TO SEDIMENTS.
LIN Dy. NIII			6.	ALL DISTURBED AREAS WHICH ARE NOT PAVED SHALL BE STABILIZED WITH SEEDING, FERTILIZER AND MULCH, HYDROSEED AND/OR SOD.
	1		7.	DEVELOPER/CONTRACTOR SHALL RESHAPE PER PLAN SPECIFICATIONS, CLEAN OUT ACCUMULATED SILT, AND STABILIZE RETENTION/DETENTION POND(S) AT THE END OF CONSTRUCTION WHEN ALL DISTURBED AREAS HAVE BEEN STABILIZED AND PRIOR TO REQUEST FOR INSPECTION.
AL-ZIU DELUISUNA			8.	CONTRACTOR SHALL MAINTAIN RECORD DRAWINGS DURING CONSTRUCTION WHICH SHOW "AS-BUILT" CONDITIONS OF ALL WORK INCLUDING PIPING, DRAINAGE STRUCTURES, TOPO OF POND(S), OUTLET STRUCTURES, DIMENSIONS, ELEVATIONS, GRADING ETC. RECORD DRAWINGS SHALL BE PROVIDED TO THE ENGINEER OF RECORD PRIOR TO THE REQUESTING FINAL INSPECTION.
			9.	"THE OWNER OR HIS AGENT SHALL ARRANGE/SCHEDULE WITH THE COUNTY A FINAL INSPECTION OF THE DEVELOPMENT UPON COMPLETION AND ANY INTERMEDIATE INSPECTIONS AT (850) 595-3472. AS-BUILT CERTIFICATION IS REQUIRED PRIOR TO REQUEST FOR FINAL INSPECTION/APPROVAL."
	DATE	BY	REV	REVISIONS DESCRIPTION
Ini N		•		•

VProi-2021/21-210 FPL - Sparkleberry Solar Energy Center/Eng/21-210 Details.dwg Plotted: 6/27/2022 4:27 PM By: KITHSIRI UDUGA

NOTES:

- 10. NOTIFY SUNSHINE UTILITIES 48 HOURS IN ADVANCE PRIOR TO DIGGING WITHIN RIGHT-OF-WAY; 1-800-432-4770.
- 11. ANY DAMAGE TO EXISTING ROADS DURING CONSTRUCTION WILL BE REPAIRED BY THE DEVELOPER PRIOR TO FILAN : AS-BUILT" SIGN OFF FROM THE COUNTY.



FLORIDA POWER & LIGHT COMPANY

PROJECT NAME

FPL SPARKLEBERRY SOLAR ENERGY CENTER

