AGENCY & UTILITY CONTACTS:

LOCAL GOVERNMENT

ESCAMBIA COUNTY 3363 WEST PARK PLACE PENSACOLA, FLORIDA 32505 PHONE: 850-595-3475

WATER SERVICES:

MOLINO UTILITIES 1640 MOLINO ROAD MOLINO, FLORIDA 32577 PHONE: 850-587-5538

TELEPHONE:

BELLSOUTH 605 W. GARDEN STREET PENSACOLA, FLORIDA 32501 PHONE: 850-436-1662

POWER:

ESCAMBIA RIVER ELECTRIC COOP P.O. BOX 428 JAY, FLORIDA 32565 PHONE: 800-235-3848

GAS:

ENERGY SERVICES OF PENSACOLA 1625 ATWOOD DRIVE PENSACOLA, FLORIDA 32504 PHONE: 850-474-5322

CABLE:

COX COMMUNICATIONS 2205 LAVISTA AVE. PENSACOLA, FLORIDA 32504 PHONE: 850-477-2695

SAFETY NOTICE TO CONTRACTOR:

IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR SHALL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. ANY CONSTRUCTION OBSERVATION BY THE ENGINEER OF THE CONTRACTOR'S PERFORMANCE IS NOT INTENDED TO INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES, IN, ON OR NEAR THE CONSTRUCTION SITE.

WARRANTY/DISCLAIMER

THE DESIGNS REPRESENTED IN THESE PLANS ARE IN ACCORDANCE WITH ESTABLISHED PRACTICES OF CIVIL ENGINEERING FOR THE DESIGN FUNCTIONS AND USES INTENDED BY THE OWNER AT THIS TIME. HOWEVER, NEITHER THE ENGINEER NOR ITS PERSONNEL CAN OR DO WARRANT THESE DESIGNS OR PLANS AS CONSTRUCTED EXCEPT IN THE SPECIFIC CASES WHERE THE ENGINEER INSPECTS AND CONTROLS THE PHYSICAL CONSTRUCTION ON A CONTEMPORARY BASIS AT THE SITE.

LEGAL DESCRIPTION:

AS PROVIDED BY EMC SURVEYOR ON 01/27/2022: ALL OF THAT TRACT OR PARCEL OF LAND LYING AND BEING IN SECTION 16, TOWNSHIP 2 NORTH, RANGE 31 WEST IN ESCAMBIA COUNTY, FLORIDA AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS

COMMENCE AT A RAIL ROAD SPIKE FOUND AT THE SOUTHEAST CORNER OF SECTION 16. TOWNSHIP 2 NORTH, RANGE 31 WEST IN ESCAMBIA COUNTY, FLORIDA AND GO NORTH 02 DEGREES 50 MINUTES 31 SECONDS WEST FOR A DISTANCE OF 50.00 FEET TO THE INTERSECTION OF THE EAST LINE OF SECTION 16 AND THE NORTHERN RIGHT-OF-WAY LINE OF BARRINEAU PARK ROAD (100' R/W): THENCE LEAVING THE EASTERN LINE OF SECTION 16 GO NORTH 87 DEGREES 06 MINUTES 18 SECONDS WEST ALONG THE NORTHERN RIGHT-OF-WAY LINE OF BARRINEAU PARK ROAD FOR A DISTANCE OF 32.68 FEET TO A 1/2" REBAR FOUND CAPPED; THENCE GO NORTH 87 DEGREES 06 MINUTES 18 SECONDS WEST ALONG THE NORTHERN RIGHT-OF-WAY LINE OF BARRINEAU PARK ROAD FOR A DISTANCE OF 2,228.16 FEET TO A 5/8" REBAR SET CAPPED LB8367 SAID POINT BEING THE POINT OF BEGINNING.

FROM SAID POINT OF BEGINNING CONTINUE ALONG THE NORTHERN RIGHT-OF-WAY LINE OF BARRINEAU PARK ROAD NORTH 87 DEGREES 06 MINUTES 18 SECONDS WEST FOR A DISTANCE OF 255.00 FEET TO A 1/2" REBAR FOUND CAPPED AT THE INTERSECTION OF THE NORTHERN RIGHT-OF-WAY LINE OF BARRINEAU PARK ROAD AND THE EASTERN RIGHT-OF-WAY LINE OF U.S. HIGHWAY 29/STATE ROAD 95 (200' R/W); THENCE GO NORTH 02 DEGREES 41 MINUTES 17 SECONDS EAST ALONG THE EASTERN RIGHT-OF-WAY LINE OF U.S. HIGHWAY 29/STATE ROAD 95 FOR A DISTANCE OF 255.00 FEET TO A 1/2" REBAR FOUND STAMPED PITTMAN; THENCE LEAVING THE EASTERN RIGHT-OF-WAY LINE OF U.S. HIGHWAY 29/STATE ROAD 95 GO SOUTH 87 DEGREES 06 MINUTES 18 SECONDS EAST ALONG A COMMON PROPERTY LINE WITH CHARLES B. LURIE PROPERTY FOR A DISTANCE OF 255.00 FEET TO A 1/2" REBAR FOUND STAMPED PITTMAN; THENCE GO SOUTH 02 DEGREES 41 MINUTES 17 SECONDS WEST ALONG A COMMON PROPERTY LINE WITH CHARLES B. LURIE PROPERTY FOR A DISTANCE OF 255.00 FEET TO A 5/8" REBAR SET CAPPED LB8367 ON THE NORTHERN RIGHT-OF-WAY LINE OF BARRINEAU PARK ROAD AND THE POINT OF BEGINNING.

SAID TRACT CONTAINS 1.493 ACRES ~ 65,024 SQ.FT.

THE ABOVE-DESCRIBED TRACT OF LAND IS THE SAME PROPERTY AS DESCRIBED IN OFFICIAL RECORD BOOK 5859, PAGES 459-460 AND IS CONTIGUOUS WITH NO GAPS OR GORES.

LAND DISTURBANCE NOTE:

ALL LAND DISTURBING ACTIVITIES, INCLUDING TREE REMOVAL, SHALL ONLY COMMENCE AFTER PROPER PERMITS ARE OBTAINED FROM ESCAMBIA COUNTY FOR THIS ACTIVITY.

FLOOD ZONE NOTE:

<u>∕2</u>∖


THE SUBJECT PROPERTY AS SHOWN HEREON IS LOCATED IN FLOOD ZONE X. (MINIMAL RISK AREAS OUTSIDE THE 1-PERCENT AND .2-PERCENT ANNUAL CHANCE FLOODPLAINS. NO BFES OR BASE FLOOD DEPTHS ARE SHOWN WITHIN THESE ZONES), AS DETERMINED FROM THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP OF ESCAMBIA COUNTY, FLORIDA, COMMUNITY 120080, FIRM MAP PANEL NUMBERS 12033C0240G, MAP REVISION (DATED SEPTEMBER 29, 2006. PRELIM MAPS JANUARY 27, 2017, MAP PANEL NUMBER 12033C0290I.

FEM	A FLOOD INS	JRANCE	RATE MAP I	NFORMA	TION
THE PARCEL SHO DETAILED BY FE	own for develop Ma firm (flood in	MENT IS LOC SURANCE RA	ATED WITHIN TH	IE FOLLOWIN	g flood zone(s) as Ribed Below:
FLOOD ZONE(S)	COMMUNITY NO	MAP NO	PANEL NO	SUFFIX	MAP REVISION DATE
х	120080	12033C	0240	G	SEPT 29, 2006
X	120080	12033C	0290	J	JAN 27, 2017

SIGNAGE NOTE: ROADWAY: HIGHWAY 29 CLASSIFICATION: ARTERIAL PROPERTY FRONTAGE: 255 LF BUILDING FRONTAGE AT GRADE: 140.8 LF BLDG SETBACK FROM HIGHWAY 29 R/W: ~57 LF

PER 5-8.8(c)(2)a. EITHER ONE FREESTANDING SIGN A MAXIMUM OF 32 SF IN AREA AND SIX FEET IN HEIGHT, OR A MAXIMUM OF 2 SF OF WALL SIGN AREA PER LINEAL FOOT OF BUILDING FRONTAGE AT GRADE (140.8LFx2SF/LF=281SF). SEE EXEMPTIONS IN SECTION 5-8.6.

A VALID ESCAMBIA COUNTY SIGN PERMIT MUST BE OBTAINED PRIOR TO ERECTING, CONSTRUCTING, ALTERING, OR RELOCATING ANY SITE SIGNAGE.






STORE # 24239

4430 N HIGHWAY 29

ESCAMBIA COUNTY, FLORIDA

APRIL 29, 2022 **REVISED MAY 25, 2022**



VICINITY MAP APPROXIMATE SCALE: 1" ~ 200'

OWNER/DEVELOPER:



Teramore Development, LLC P.O. Box 6460 Thomasville, GA 31758 (229) 516-4289

ENGINEER OF RECORD:



Bell Engineering Services, LLC Jennifer D. Bell, P.E. (FL #64666) Pensacola, Florida 32503 (850) 723-7185 EB 00029198

SITE I PROPERTY PROPERTY

Approved ESCAMBIA.COUNTY DRC PLAN REVIEW 6/1/2022 as been reviewed in accordance with the requirements of applicable Escambia County Regulations and Ordinances, and does not in any way relieve the submitting Architect, Engineer, Surveyor or other signatory from responsibility of details as drawn. A Development Order (DO) must be obtained through the Development Review Process prior to the commencement of construction. This DO approval does not onstitute approval by any other agency. All additional state/federal ermits shall be provided to the county prior to approval of a final plat or he issuance of state/federal permits shall be provided to the county prior pproval of a final plat or the issuance of a building per


DRAWING INDEX

C1.0
C1.1
C1.2
C2.0
C2.1
C3.0
C3.1
C4.0
C5.0

EXISTING SITE, DEMOLITION & EROSION CONTROL PLAN GENERAL NOTES, TREE TABLE & EROSION CONTROL DETAILS NPDES - STORMWATER POLLUTION PREVENTION PLAN SITE LAYOUT & DIMENSION PLAN MISCELLANEOUS SITE DETAILS **GRADING & DRAINAGE PLAN GRADING & DRAINAGE DETAILS** UTILITY PLAN LANDSCAPE PLAN

SITE INFORMATION	J:							
PROPERTY REFERENCE NO:	16-2N-31-4000-000-007							
PROPERTY ADDRESS:	4430 N HIGHWAY 29							
PROPERTY AREA:	1.493 ACRES (65,024 SF)							
PROJECT AREA:	1.493 ACRES (65,024 SF)							
FLOOD MAP:	FLOOD ZONE "X", MAP #12033C0240-G, DATED 09-29-2006 FLOOD ZONE "X", MAP #12033C0290-J, DATED 01-27-2017							
PROPERTY ZONING:	RMU (RURAL MIXED-USE)							
FUTURE LAND USE:	RC (RURAL COMMUNITY)							
PROPOSED ACTIVITY:	RETAIL – THIS PROJECT RECEIVED CONDITIONAL USE TO ALLOW A RETAIL BUILDING GREATER THAN 6,000 SF IN RMU ZONING FROM ESCO BOARD OF ADJUSTMENTS ON 04/20/22. SEE CONDITIONAL USE CASE # CU-2022-05.							
REQUIRED BUILDING SETBACKS RMU (PER LDC SECTION 3-2.4):	FRONT YARD – 40' SIDE YARD – 5' (OR 10% OF LOT WIDTH @ ROW, NTE 15) NIFER D REAR YARD – 40'							
	DATE # REVISION DESCRIPTION							
	DATE # REVISION DESCRIPTION DA							
	05/25/22 ESCO DEVELOPMENT REVIEW							

BELL ENGINEERING SERVICES PROJECT#: 2022007



1. ALL WORK IN THE RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH THE LATEST EDITION OF THE FOLLOWING: STANDARD PLANS FOR ROAD & BRIDGE CONSTRUCTION, THE PLANS PREPARATION MANUAL (PPM), AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).

2. PRIOR TO STARTING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONFIRMING THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED AND THOROUGHLY REVIEWED ALL PLANS AND OTHER DOCUMENTS APPROVED BY ALL OF THE PERMITTING AGENCIES.

3. THE LOCATION OF UNDERGROUND FACILITIES SHOWN ON THESE PLANS IS BASED ON INFORMATION PROVIDED BY THE UTILITIES AND SHALL BE CONSIDERED APPROXIMATE. IT SHALL BE THE CONTRACTOR'S FULL RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES TO LOCATE THEIR FACILITIES PRIOR TO STARTING CONSTRUCTION. NO ADDITIONAL COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR DAMAGE AND REPAIR TO THESE FACILITIES CAUSED BY HIS WORK FORCE.

4. THE CONTRACTOR SHALL NOTIFY THE SUPERINTENDENTS OF THE WATER, SANITARY SEWER, GAS, TELEPHONE, CABLE TELEVISION, AND POWER COMPANIES 10 DAYS IN ADVANCE THAT HE INTENDS TO START WORK IN A SPECIFIED AREA. THE OWNER DISCLAIMS ANY RESPONSIBILITY FOR THE SUPPORT AND PROTECTION OF SEWERS. DRAINS, WATER PIPES, GAS PIPES, CONDUITS OF ANY KIND, UTILITIES OR OTHER STRUCTURES OWNED BY THE CITY, COUNTY, STATE OR BY PRIVATE OR PUBLIC UTILITIES LEGALLY OCCUPYING ANY STREET, ALLEY, PUBLIC PLACE OR RIGHT-OF-WAY.

5. ALL SITE CLEARING SHALL INCLUDE THE LOCATION AND REMOVAL OF ALL UNDERGROUND STRUCTURES. WHICH ARE NOT IN SERVICE AS NECESSARY FOR THE INSTALLATION OF PROPOSED IMPROVEMENTS. THESE INCLUDE PIPES, VALVES, DRAINAGE 4. THIS MAP OR PLAT HAS BEEN CALCULATED FOR CLOSURE AND STRUCTURES, ETC., AS INDICATED ON THE CONTRACT PLANS. CONTRACTOR SHALL NOTIFY THE PROJECT OWNER AND ENGINEER OF ALL DISCOVERED UNDERGROUND STRUCTURES WHICH ARE IN CONFLICT WITH THE INSTALLATION OF THE PROPOSED IMPROVEMENTS AND ARE NOT INDICATED ON THE CONTRACT PLANS OR LOCATED IN THE FIELD BY UTILITIES IN ACCORDANCE WITH GENERAL NOTES.

6. THE RELOCATION OF OBSTRUCTIONS OWNED BY PRIVATE PROPERTY OWNERS, SUCH AS MAIL BOXES, SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR WHO MUST COORDINATE WITH THE PROPERTY OWNER.

7. THE CONTRACTOR SHALL PLACE AND MAINTAIN ADEQUATE BARRICADES, CONSTRUCTION SIGNS, FLASHING LIGHTS, TORCHES, RED LANTERNS AND GUARDS DURING AL PHASES OF CONSTRUCTION, IN ACCORDANCE WITH APPLICABLE FDOT INDEX.

8. ALL AREAS NOT PAVED OR DISTURBED DURING CONSTRUCTION SHALL BE STABILIZED BY SEEDING AND MULCHING OR SODDING. SEED AND MULCH OR SOD SHALL BE PLACED, WATERED, FERTILIZED WITH APPROPRIATE SOIL AMENDMENTS IN ACCORDANCE WITH THE FDOT STANDARD SPECIFICATIONS AND THESE CONSTRUCTION DOCUMENTS.

9. ALL EXCESS MATERIAL SHALL BE HAULED AWAY AND DISPOSED OF APPROPRIATELY 8. THIS PROPERTY IS IN FLOOD ZONE "X" AS PER FLOOD AT THE CONTRACTOR'S EXPENSE.

10. ALL CONSTRUCTION AROUND TREES SHALL BE DONE IN A MANNER TO MINIMIZE DAMAGE TO THE TREE AND ITS ROOT SYSTEM.

11. THE CONTRACTOR SHALL VISIT THE SITE TO FAMILIARIZE HIMSELF WITH EXISTING CONDITIONS AND THE EXTENT OF CLEARING AND GRUBBING REQUIRED.

12. ALL DIMENSIONS AND GRADES SHOWN ON THE PLANS SHALL BE FIELD VERIFIED 9. THERE IS NO EVIDENCE OF RECENT EARTH MOVING WORK, BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY THE BUILDING CONSTRUCTION, OR BUILDING ADDITIONS. ENGINEER IF ANY DISCREPANCIES EXIST PRIOR TO PROCEEDING WITH CONSTRUCTION FOR NECESSARY PLAN OR GRADE CHANGES. NO EXTRA COMPENSATION SHALL BE PAID 10. THERE ARE NO PROPOSED CHANGES IN STREET RIGHT OF TO THE CONTRACTOR FOR WORK HAVING TO BE REDONE DUE TO DIMENSIONS OR GRADES SHOWN INCORRECTLY ON THESE PLANS IF SUCH NOTIFICATION HAS NOT BEEN CONSTRUCTION OR REPAIRS. GIVEN.

13. THE CONTRACTOR IS TO COORDINATE WITH THE RESPONSIBLE UTILITY PROVIDER FOR PROTECTION/HOLDING OF UTILITY POLES, GUY WIRES, AND GUY ANCHORS IN AREAS OF CONSTRUCTION. THE CONTRACTOR SHALL INCLUDE THE COST OF PROTECTING UTILITY POLES IN THEIR OVERALL PRICE TO THE OWNER.

14. DAMAGE TO EXISTING ROADS DURING CONSTRUCTION SHALL BE REPAIRED BY THE 13. THE PROPERTY HAS DIRECT ACCESS TO US HIGHWAY 29 AND CONTRACTOR PRIOR TO FINAL "AS-BUILT" SIGN-OFF FROM THE COUNTY.

IS FOUND TO BE ACCURATE WITHIN ONE FOOT IN 1,020,000,000

NECESSARY. ANY AND ALL UTILITIES

DISCRETION OF THEIR PROSPECTIVE

3. NO DEMOLITION DEBRIS WILL BE

STOCKPILED OR GATHERED ON THE

SEE ASSOCIATED BOUNDARY/TOPO SURVEY PROVIDED BY EMC

, THIS SURVEY WAS MADE USING A GEOMAX ZOOM 90 ROBOTIC

TOTAL STATION TO OBTAIN LINEAR AND ANGULAR MEASUREMENTS.

3. THE FIELD DATA UPON WHICH THIS MAP OR PLAT IS BASED

AN ANGULAR ERROR OF 0 DEGREES 00 MINUTES AND 01

HAS A CLOSURE PRECISION OF ONE FOOT IN 21,724 FEET AND

SECONDS PER ANGLE POINT, AND WAS ADJUSTED USING COMPASS

PROJECT SITE OR ADJACENT PROPERTIES,

WITHOUT PRIOR AUTHORIZATION OF THE

OWNERS.

OWNER.

ENGINEERING

FEET.

SURVEYOR NOTES (MODIFIED):

1. TOTAL AREA IN TRACT 1 = 1.493 AC

ENCOUNTERED DURING DEMOLITION WILL BE

PROTECTED AND/OR RELOCATED AT THE

5. THERE IS NO KNOWN NATIONAL GEODETIC SURVEY MONUMENT WITHIN 500 FEET OF ANY POINT ON THE PROPERTY PLATTED, OR ANY POINT OF REFERENCE THEREON.

6. CERTAIN DATA SHOWN ON THIS PLAT WAS OBTAINED UTILIZING GPS (GLOBAL POSITIONING SYSTEMS). IT INCLUDES: BASIS OF BEARINGS, HORIZONTAL CONTROL, AND VERTICAL CONTROL. THE EQUIPMENT USED TO OBTAIN THIS DATA WAS A CHAMPION PRO GPS RECEIVER WITH A CARLSON RT3 DATA COLLECTOR.

7. THE HORIZONTAL DATUM AS REFERENCED HEREIN IS BASED ON THE NORTH AMERICAN DATUM OF 1983(NAD83). THE VERTICAL DATUM (ELEVATIONS) SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988(NAVD88). BOTH DATUMS REFERENCED ABOVE WERE ESTABLISHED ON SITE USING SAID THE FLORIDA PREEMINENT REAL TIME GPS NETWORK USING GEIOD12B.

INSURANCE RATE MAP FOR ESCAMBIA COUNTY, FLORIDA, AND INCORPORATED AREAS, PANEL 240 OF 606, AS SHOWN ON MAP NUMBER 12033C0240G, WITH AN EFFECTIVE DATE OF SEPTEMBER 29, 2006.


ZONE "X" DENOTES AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN.

WAY LINES, EVIDENCE OF RECENT STREET OR SIDEWALK

11. UTILITY LOCATE TICKET NO. 00000 010200734-000 AND 00000 010200674-000, DATED: JANUARY 10, 2022.

12. THERE WERE NO WETLANDS DELINEATED AT THE TIME OF SURVEY.

BARRINEAU PARK ROAD.



GENERAL NOTES FOR SOIL EROSION AND SEDIMENT CONTROL:

. ALL EROSION AND SEDIMENT CONTROL PRACTICES TO BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCE, OR IN THEIR PROPER SEQUENCE, AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED.

2. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 30 DAYS, AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, WILL IMMEDIATELY RECEIVE A TEMPORARY SEEDING. IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER, THE DISTURBED AREAS WILL BE MULCHED WITH STRAW, OR EQUIVALENT MATERIAL, AT A RATE OF TWO (2) TONS PER ACRE, ACCORDING TO STATE STANDARDS.

3. PERMANENT VEGETATION TO BE SEEDED OR SODDED ON ALL EXPOSED AREAS WITHIN TEN (10) DAYS AFTER GRADING. MULCH TO BE USED AS NECESSARY FOR PROTECTION UNTIL SEEDING IS ESTABLISHED. NEWLY PLACED SOD/SEED IN RIGHT OF WAY SHALL BE WATERED UNTIL PERMANENT VEGETATIVE COVER IS ESTABLISHED.

4. ALL WORK AND MATERIALS TO BE IN ACCORDANCE WITH THE FDOT "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", LATEST EDITION.

*5. A BITUMINOUS CONCRETE BASE COURSE WILL BE APPLIED IMMEDIATELY FOLLOWING ROUGH GRADING AND INSTALLATION OF IMPROVEMENTS IN ORDER TO STABILIZE STREETS, ROADS, DRIVEWAYS AND PARKING AREAS. IN AREAS WHERE NO UTILITIES ARE PRESENT, THE BITUMINOUS CONCRETE BASE SHALL BE INSTALLED WITHIN 15 DAYS OF THE PRELIMINARY GRADING.

*6. IMMEDIATELY FOLLOWING INITIAL DISTURBANCE OR ROUGH GRADING, ALL CRITICAL AREAS SUBJECT TO EROSION (I.E. STEEP SLOPES AND ROADWAY EMBANKMENTS) WILL RECEIVE A TEMPORARY SEEDING IN COMBINATION WITH STRAW MULCH OR A SUITABLE EQUIVALENT, AT A THICKNESS OF TWO (2) TO FOUR (4) INCHES MIXED WITH THE TOP TWO (2) INCHES OF SOIL, ACCORDING TO STATE STANDARDS.

*7. ANY STEEP SLOPES RECEIVING PIPELINE INSTALLATION WILL BE BACKFILLED AND STABILIZED DAILY, AS THE INSTALLATION PROCEEDS (I.E. SLOPES GREATER THAN 3:1).

*8. A CRUSHED LIMEROCK, VEHICLE WHEEL-CLEANING BLANKET SHALL BE INSTALLED AT THE CONTRACTOR'S STAGING YARD AND/OR STOCKPILE AREAS TO PREVENT OFF-SITE TRACKING OF SEDIMENT BY CONSTRUCTION VEHICLES ONTO PUBLIC ROADS. BLANKET SHALL BE 15FT. X 50FT. X 6IN. (MINIMUM), CRUSHED LIMEROCK 2 1/2 INCHES IN DIAMETER. SAID BLANKET SHALL BE UNDERLAIN WITH A FOOT CLASS 3 SYNTHETIC FILTER FABRIC AND MAINTAINED IN GOOD ORDER.

9. AT THE TIME WHEN THE SITE PREPARATION FOR PERMANENT VEGETATIVE STABILIZATION IS GOING TO BE ACCOMPLISHED, ANY SOIL THAT WILL NOT PROVIDE A SUITABLE ENVIRONMENT TO SUPPORT ADEQUATE VEGETATIVE GROUND COVER, SHALL BE REMOVED OR TREATED IN SUCH A WAY THAT WILL PERMANENTLY ADJUST THE SOIL CONDITIONS AND RENDER IT SUITABLE FOR VEGETATIVE GROUND COVER. IF THE REMOVAL OR TREATMENT OF THE SOIL WILL NOT PROVIDE SUITABLE CONDITIONS, NON-VEGETATIVE MEANS OF PERMANENT GROUND STABILIZATION WILL HAVE TO BE EMPLOYED.

*10. CONDUIT OUTLET PROTECTION MUST BE INSTALLED AT ALL REQUIRED OUTFALLS PRIOR TO THE DRAINAGE SYSTEM BECOMING OPERATIONAL.

11. UNFILTERED DEWATERING IS NOT PERMITTED. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS DURING ALL DEWATERING OPERATIONS TO MINIMIZE SEDIMENT TRANSFER.

12. SHOULD THE CONTROL OF DUST AT THE SITE BE NECESSARY, THE SITE WILL BE SPRINKLED UNTIL THE SURFACE IS WET, TEMPORARY VEGETATION COVER SHALL BE ESTABLISHED OR MULCH SHALL BE APPLIED IN ACCORDANCE WITH STATE STANDARDS FOR EROSION CONTROL.

13. ALL SOIL WASHED, DROPPED, SPILLED OR TRACKED OUTSIDE THE LIMIT OF DISTURBANCE OR ONTO PUBLIC RIGHTS-OF-WAY WILL BE REMOVED IMMEDIATELY

14. THE PROPERTY OWNER SHALL BE RESPONSIBLE FOR ANY EROSION OR SEDIMENTATION THAT MAY OCCUR BELOW STORMWATER OUTFALLS OR OFFSITE AS A RESULT OF CONSTRUCTION OF THE PROJECT.

15. ALL SOIL STOCKPILES ARE TO BE TEMPORARILY STABILIZED IN ACCORDANCE WITH SOIL EROSION AND SEDIMENT CONTROL NOTE NUMBER 2 (ABOVE).

16. THE SITE SHALL AT ALL TIMES BE GRADED AND MAINTAINED SUCH THAT ALL STORMWATER RUNOFF IS DIVERTED TO SOIL EROSION AND SEDIMENT CONTROL FACILITIES.

17. ALL SEDIMENTATION STRUCTURES SHALL BE INSPECTED AND MAINTAINED REGULARLY.

18. ALL CATCH BASIN INLETS SHALL BE PROTECTED WITH HAY BALES AS SHOWN ON DETAIL. 19. THE CONTRACTOR SHALL PREPARE A PLAN FOR THE PROPER DEWATERING AND DOWNSTREAM SILTATION PROTECTION OF EACH STREAM CROSSING PRIOR TO EXCAVATING THE STREAM BED. PLAN SHALL BE FORWARDED TO THE ENGINEER FOR APPROVAL. THE ENGINEER SHALL BE NOTIFIED FOR INSPECTION PRIOR TO EACH STREAM CROSSING CONSTRUCTION.

20. ANY AREAS USED FOR THE CONTRACTOR'S STAGING, INCLUDING BUT NOT LIMITED TO, TEMPORARY STORAGE OF STOCKPILED MATERIALS (E.G. CRUSHED STONE, QUARRY PROCESS STONE, SELECT FILL, EXCAVATED MATERIALS, ETC.), SHALL BE ENTIRELY PROTECTED BY A SILT FFNCF ALONG THE LOW ELEVATION SIDE TO CONTROL SEDIMENT RUNOFF.

* WHERE APPLICABLE

- -

TEMPORARY SEEDING DETAILS:

SEED BED PREPARATION:

SOIL TO BE THOROUGHLY PULVERIZED BY DISK-HARROWING AND BE LOOSE AND REASONABLY SMOOTH. APPLY FERTILIZER AT A RATE OF 260 LBS/ACRE OF 16-16-16 OR EQUIVALENT, APPLY DOLOMITIC LIMESTONE AT A RATE OF 800 TO 1000 LBS./ACRE TO PROVIDE A SOIL pH OF 5.5 TO 6.5, LIME & FERTILIZER TO BE WORKED INTO THE TOPSOIL TO A DEPTH OF 4". ADD SANDY LOAM TOPSOIL TO A MINIMUM OF TWO (2) INCHES WHERE REQUIRED.

SEED MIXTURE:

CONSISTING OF ANNUAL RYE (LOLIUM MULTIFLORUM) AT A RATE OF 174 LBS/ACRE.

PERMANENT SEEDING DETAILS:

SEED BED PREPARATION:

SOIL TO BE THOROUGHLY PULVERIZED BY DISK-HARROWING AND BE LOOSE AND REASONABLY SMOOTH. APPLY FERTILIZER AT A RATE OF 260 LBS/ACRE OF 16-16-16 OR EQUIVALENT, APPLY DOLOMITIC LIMESTONE AT A RATE OF 800 TO 1000 LBS./ACRE TO PROVIDE A SOIL pH OF 5.5 TO 6.5, LIME & FERTILIZER TO BE WORKED INTO THE TOPSOIL TO A DEPTH OF 4". ADD SANDY LOAM TOPSOIL TO A MINIMUM OF TWO (2) INCHES WHERE REQUIRED.

SEED MIXTURE CONSISTING OF	RATE PL	JRITY	GERMINATION
ARGENTINE BAHIA	260 LBS/AC.	95%	80%
PENSACOLA BAHIA	260 LBS/AC.	95%	40%(MIN.)-80%(TOTAL)

SODDING:

SOD SHALL BE WELL ROOT MATTED CENTIPEDE OR BAHIA GRASS COMMERCIALLY CUT TO A MINIMUM DIMENSION OF 12" x 24" A MAXIMUM OF 72 HOURS PRIOR TO PLACEMENT. SOD SHALL BE LIVE, FRESH AND UNINJURED, REASONABLY FREE OF WEEDS AND OTHER GRASSES, WITH A HEAVY SOIL MAT ADHERING TO THE ROOT SYSTEM. SOD SHALL BE GROWN, CUT, AND SUPPLIED BY A STATE CERTIFIED GROWER. NEWLY PLACED SOD/SEED IN RIGHT OF WAY SHALL BE WATERED UNTIL PERMANENT VEGETATIVE COVER IS ESTABLISHED.

TRAFFIC CONTROL STANDARDS:

1. CONSTRUCTION TRAFFIC SHALL BE RESTRICTED TO ONSITE ACCESS BY MEANS SO DESIGNATED BY THE ENGINEER, POLICE/SHERIFF DEPARTMENT, LOCAL GOVERNMENT ROADS DEPARTMENT, AND/OR THE FLORIDA DEPARTMENT OF TRANSPORTATION.

2. TRAFFIC DURING WET WEATHER SHALL BE MINIMIZED AND APPROPRIATE ROADWAY AND SITE CLEAN-UP SHALL BE PROVIDED BY THE CONTRACTOR AS SOON AS WEATHER CONDITIONS PERMIT.

TREE PROTECTION:

1. DAMAGED TRUNKS OR EXPOSED ROOTS WILL BE PAINTED IMMEDIATELY WITH A GOOD GRADE OF "TREE PAINT"

2. TREE LIMB REMOVAL, WHERE NECESSARY, WILL BE DONE FLUSH TO TRUNK OR MAIN BRANCH AND THAT AREA PAINTED IMMEDIATELY WITH A GOOD GRADE OF TREE PAINT.

DUST CONTROL

1. ALL AREAS OF CLEARING AND EMBANKMENT AS WELL AS CONSTRUCTION HAUL ROADS SHALL BE TREATED AND MAINTAINED IN SUCH A MANNER AS TO MINIMIZE ANY DUST GENERATION.

2. DISTURBED AREAS SHALL BE MAINTAINED IN A ROUGH GRADED CONDITION AND TEMPORARILY SEEDED AND/OR MULCHED UNTIL PROPER WEATHER CONDITIONS EXIST FOR THE ESTABLISHMENT OF PERMANENT VEGETATION COVER.

3. IN EVENT OF EMERGENCY CONDITIONS, TILLAGE WILL BE SATISFACTORY FREE BEFORE SOIL BLOWING STARTS.

4. CALCIUM CHLORIDE MAY BE APPLIED TO UNPAVED ROADWAY AREAS, ONLY, SUBJECT TO THE ENGINEER'S APPROVAL AND CONFORMANCE WITH FDOT STANDARD SPECIFICATIONS, LATEST EDITION.

PROPOSED SEQUENCE OF CONSTRUCTION:

THIS PROJECT SHALL CONSIST OF THE CONSTRUCTION OF SANITARY SEWERS OR WATER MAINS BY THE MOLINO WATER WORKS OR ITS CONTRACTOR WITHIN PUBLIC RIGHTS OF WAY. THE CONSTRUCTION SHOULD PROCEED IN THE FOLLOWING MANNER:

1. INSTALLATION OF ALL SEDIMENT AND EROSION CONTROL DEVICES THAT CAN BE PLACED PRIOR TO ANY MAJOR SOIL DISTURBANCES.


2. CLEAR AND REMOVE ALL EXISTING VEGETATION IN THOSE AREAS WHERE NECESSARY. ALL REMAINING VEGETATION TO BE PROPERLY PROTECTED AND TO REMAIN IN ITS NATURAL STATE. TOPSOIL IN AREAS TO BE DISTURBED TO BE STRIPPED TO A MINIMUM DEPTH OF SIX (6) INCHES AND STOCKPILED SEPARATELY FROM FROM OTHER EXCAVATED SOIL(S)

3. IMMEDIATE INSTALLATION OF ALL REMAINING SEDIMENT AND EROSION CONTROL DEVICES.

4. INITIATE CONSTRUCTION OF SANITARY SEWER AND/OR WATER MAIN.

5. UPON COMPLETION OF CONSTRUCTION ACTIVITIES, PROVIDE RESTORATION, FINE GRADE REMAINDER OF SITE, RESPREAD STOCKPILED TOPSOIL AND STABILIZE WITH PERMANENT VEGETATIVE COVER AND LANDSCAPING.


6. REMOVAL OF APPROPRIATE TEMPORARY SEDIMENT AND EROSION CONTROL DEVICES.




3' APART, BUT NOT TO EXCEED 6'.

DEPLOY IN A MANNER THAT SUIT FENCES WILL ACT AS A ACROSS PERMANENT FLOWING WATERCOURSES. SILT FENCES ARE TO BE USED AT UPLAND LOCATIONS AND TURBIDITY BARRIERS USED AT PERMANENT BODIES OF WATER.


> SILT FENCE APPLICATIONS N.T.S.






ALL PROTECTED TREES AS SHOWN ON THE PLANS TO REMAIN ARE TO BE PROTECTED DURING CONSTRUCTION. THE CONTRACTOR SHALL INSTALL ORANGE CONSTRUCTION FENCING AT THE DRIP LINE OF EACH PROTECTED TREE BEFORE WORKING IN THE VICINITY OF THE TREE. BARRICADES SHALL ALSO BE PROPERLY INSTALLED AND MAINTAINED IN GOOD WORKING ORDER UNTIL SITE BECOMES STABILIZED.





STRAW BALE DETAIL

N.T.S.



DESCRIPTION:

FILTER BAGS WILL BE USED AS AN EFFECTIVE FILTER MEDIUM TO CONTAIN SAND, SILT AND FINES WHEN TRENCH DEWATERING. THE WETLAND FILTER BAG CONTAINS THESE MATERIALS WHILE ALLOWING THE WATER TO FLOW THROUGH THE FABRIC.

INSTALLATION:


WETLAND FILTER BAGS MAY REPLACE HAY BALE CORRALS DURING TRENCH DEWATERING, AT THE DISCRETION OF THE ENGINEER INSPECTOR. TO INSURE PROPER INSTALLATION, FILTER BAGS WILL BE PLACED ON RELATIVELY FLAT TERRAIN FREE OF BRUSH AND STUMPS TO AVOID RUPTURES AND PUNCTURES. PROPER INSTALLATION REQUIRES CUTTING A SMALL HOLE IN THE CORNER OF THE BAG, INSERTING THE PUMP DISCHARGE HOSE, AND THEN SECURING THE DISCHARGE HOSE TO THE BAG WITH A HOSE CLAMP. FILTER BAGS WILL BE PLACED AS FAR AWAY FROM FLOWING STREAMS AND WETLANDS AS POSSIBLE.

MAINTENANCE:

PRIOR TO REMOVING A BAG FROM THE HOSE, THE BAG WILL BE TIED OFF BELOW THE END OF THE HOSE ALLOWING THE BAG TO DRAIN. DRAINAGE WILL NOT BE ALLOWED THROUGH THE INLET HOLE. TO AVOID RUPTURE, THE BAGS WILL BE ATTENDED AND PUMPING RATES MONITORED. ONCE THE BAG IS INFLATED TO A HEIGHT OF 4 FEET, PUMPING WILL STOP TO AVOID RUPTURE. FILTER BAGS USED DURING CONSTRUCTION WILL BE BUNDLED AND REMOVED FOR PROPER DISPOSAL.

SPECIFICATION:

FILTER BAGS ARE CONSTRUCTED OF NON-WOVEN GEOTEXTILE FABRIC. A MAXIMUM OF ONE SIX INCH DISCHARGE HOSE WILL BE ALLOWED PER FILTER BAG. BAG CAPACITY WILL BE EXCEEDED BEYOND 2,000 GALLONS PER MINUTE. TYPICAL BAG DIMENSIONS ARE 15 FEET BY 13.25 FEET. TO HELP PREVENT PUNCTURES, GEOTEXTILE FABRIC WILL BE PLACED BENEATH THE FILTER BAG WHEN USED IN WOODED LOCATIONS. UNATTENDED FILTER BAGS WILL BE ENCIRCLED WITH A HAY BALE OR SILT FENCE CORRAL. HOSE CLAMPS WILL BE USED TO SECURE THE DISCHARGE HOSE, WIRE OR STRING WILL NOT BE USED.



STORM WATER POLLUTION PREVENTION PLAN

1.0 BACKGROUND & REQUIREMENTS:

1.1 Introduction:

The referenced support documentation for this Storm Water Pollution Prevention Plan (SWPPP) is the United States Environmental Protection Agency's (EPA) Storm Water Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices Summary Guidance (EPA 833-R-92-001) and Storm Water Management for Construction Activities, Developing Pollution Prevention Plans and Best Management Practices (EPA 832-R-92-005). This SWPPP is designed to protect onsite and adjacent natural resources, including but not limited to, wetlands, marshes, bayous and bays, while preserving wildlife and archeological resources.

An ERP application (10/2) was made in April 2022.

1.2 Notice of Intent (NOI):

Rule 62-621.300(4), FAC requires the construction operator of a site that disturbs one or more acres to obtain coverage from the Generic Permit for Stormwater Discharge from Large and Small Construction Activities. The contractor is required to submit a Notice of Intent to Use Generic Permit for Stormwater Discharge from Large and Small Construction Activities (FDEP Form 62-621.300(4)(b)) along with the appropriate application fee to the following address 48 hours prior to commencing construction:

> NPDES Stormwater Notices Center, MS # 2510 Florida Department of Environmental Protection 2600 Blair Stone Road Tallahassee, Florida 32399-2400

This form can be obtained from FDEP's website (www.dep.state.fl.us) or by contacting FDEP. Please note that the current application fee is \$250; however, this fee is subject to change without notice. Always refer to the most current version of Rule 62-4.050(4)(d), FAC to confirm the amount before submitting payment. If construction activity exceeds five years, the contractor must re-apply for coverage.

1.3 Stormwater Pollution Prevention Plan (SWPPP):

The contractor is required to certify this Stormwater Pollution Prevention Plan (SWPPP) below prior to submitting the NOI. This SWPPP is not required to be submitted with the NOI, but is required to be kept on site during all phases of construction. Because erosion and sediment controls and construction methods vary significantly from contractor to contractor, the contractor can propose alternative methods to this SWPPP that are equal or better at controlling erosion and sedimentation. At a minimum, the contractor must follow the erosion control plan specified in the construction plans and documents. Any modifications to this SWPPP must be documented and kept with the plan as part of the records keeping process to be in full compliance with the CGP.

1.4 Contractor's Certification:

- -

~ *

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Print & Sign Name

Company & Address

Name & Title (Print)

Date Signature

Responsibilities (General Contractor, Site Contractor, Subcontractor, Other):

1.5 Notice of Termination (NOT):

The contractor is required to submit a Notice of Termination of Generic Permit Coverage (FDEP Form 62-621.300(6)) upon construction completion to discontinue permit coverage. The NOT is to be submitted to the following address:

> NPDES Stormwater Notices Center, MS # 2510 Florida Department of Environmental Protection 2600 Blair Stone Road Tallahassee, Florida 32399-2400

This form can be obtained from FDEP's website (www.dep.state.fl.us) or by contacting FDEP. The NOT can not be submitted until all disturbed soils at the construction site have been finally stabilized and temporary erosion and sediment control measures have been REMOVED or will be REMOVED at an appropriate time. Final stabilization means that all soil disturbing activities at the site have been completed and that a uniform perennial vegetative cover with a density of 70 percent of the cover for unpaved areas and areas not covered by permanent structures has been established, or equivalent stabilization measures have been employed. If construction activity exceeds five years, the contractor must re-apply for coverage.

1.6 Application Information:

Project Address:

Latitude: Longitude: Water Management District: Northwest Florida (NWFWMD) MS4 Operator Name: FDOT

2.0 SITE DESCRIPTION:

2.1 Nature of Construction Activities:

This project involves the construction of a 10,670 sf Dollar General Store. Construction includes paved parking, utilities and stormwater management

2.2 Sequence of Major Soil Disturbing Activities:

The following sequence of major activities shall be followed unless the contractor can propose an alternative that is equal to or better at controlling erosion and sedimentation. The detailed sequence for the entire project can vary significantly from contractor to contractor. The contractor is responsible for documenting any changes.

- 1. Clear, grub and perform all demolition work.
- 2. Complete rough grading of the pond and direct all stormwater runoff to the pond(s).
- 3. Construct all underground utilities and storm drain system.
- 7. Complete stormwater ponds.

2.3 Area Estimates:

Onsite Area:	
Offsite Area:	
Total Area:	
Area to be Disturbed:	

2.4 Runoff Data:

- Runoff Coefficients (c):
 - Before: Total Composite c = 0.20
 - During: Varies between 0.20 and 0.95
 - After: Varies between 0.20 and 0.95
 - Total Composite c = 0.55

Soils Data:

prepared by Universal Engineering.

Drainage Areas for Each Outfall: Total Area flowing to Pond Outfall Location 'c' coefficient Pine Barren Creek 2.08 ac 0.55

2.5 Site Map:

The construction plans are to be used as the site maps. The location of the required information is described below. The sheet numbers for all the items discussed below are identified on the Cover Sheet of the construction plans. • Drainage Patterns: All drainage patterns are shown on the Grading & Drainage

- Plans.
- Grading & Drainage Plan.
- features are shown above or below ground will be disturbed.
- areas used for staging and materials storage.
- · Locations of Controls: All proposed temporary controls and existing permanent contractor's responsibility to indicate the location of any other controls on the plans that are used during construction.
- the contractor's responsibility to indicate the location on the plans of all temporary stabilization practices used during construction. Surface Waters: N/A
- Discharge Points: NW corner of property to allow discharge to flow to historical discharge location (eventual outfall to Cowdevil Creek).
- 2.6 Receiving Waters:
- FDOT MS4 drainage system eventual outfall to Cowdevil Creek.

4430 N. HIGHWAY 29 MOLINO, FLORIDA 32577 Escambia County, Florida 30° 40' 51.38" N 87° 21' 2.15" W

Receiving Water Name: Eventual outflow to a tributary of Cowdevil Creek

4. Construct roads (subgrade, curb & gutter, base, pavement, sidewalks, and landscaping).

1.49 acres 0.00 acres 1.49 acres 1.49 acres

For detailed soils information, refer to the Geotechnical Services Report

 Approximate Slopes: Approximate slopes are shown on the Grading & Drainage Plan. Pond side slopes are shown on the pond cross-sections, located on the

· Areas of Soil Disturbance: All demolition is shown on the Existing Site Conditions and Demolition and Erosion Control Plan Sheet. All proposed construction is shown on the remaining plans. Any areas where demolition work or permanent

· Areas not to be Disturbed: Any areas not showing demolition work or permanent features are assumed not to be disturbed. It will be the contractor's responsibility to indicate on the plans any of these areas that do get disturbed as well as any

controls are shown on the Existing Site, Demolition and Erosion Control Plan. All proposed permanent controls are shown on the remaining plans. It will be the

• Areas to be Stabilized: Permanent stabilization is shown on the plans. It will be

3.0 CONTROLS: 3.1 Erosion and Sediment Controls: 7.1 Records: All erosion and sediment controls specified on the Demolition and Erosion Control Plan Sheets, and the Erosion Control Details shall be installed prior to any construction or demolition. Silt fencing and staked hay bales shall be installed along down-gradient limits. Temporary seeding and mulching shall be applied after 14-day intervals of ceased disturbance activities that will exceed 20-day periods. Graded areas shall be stabilized with permanent seeding, mulching, and fertilizing, or sodding within five days of final grading. Landscaping, including sodding, shall be installed by an experienced Landscape Contractor. Proposed disturbed areas will not exceed 8 acres in any drainage area. 3.2 Stormwater Management: Proposed stormwater management facilities for this site includes a shallow dry

retention pond with a bottom filter system - discharge to FDOT R/W drainage system. The system has been designed to accommodate the entire developed site. The proposed stormwater management facilities meet all stormwater treatment requirements and all rate control requirements set forth by the local and state regulatory agencies.

3.3 Other Controls:

Waste Disposal: The contractor is responsible for all waste disposal from the site. The contractor shall employ waste disposal practices that meet all local, state, and federal guidelines and prevent discharge of solid materials to waters of the United States. The Contractor is responsible for documenting this portion of the SWPPP.

Offsite Vehicle Tracking: If off site tracking of sediments by construction vehicles occurs, the contractor is required to install a Soil Tracking Prevention Device (STPD) as per FDOT Standard Index 106 at all exits to the site where sediment tracking is occurring. The Contractor is also responsible for documenting this portion of the SWPPP.

4.0 MAINTENANCE:

Controls shall be kept in full operating condition throughout all phases of construction until all disturbed areas are completely stabilized. Maintenance, repair records and repair requests shall be documented. Repairs and deficiencies shall be completed as soon as possible and within seven days after inspection. Any required changes that are not covered in the SWPPP shall also be made as soon as possible within seven days and documented.

5.0 INSPECTIONS:

Qualified personnel shall inspect the following items, but not limited to, at least once every seven calendar days and within 24 hours of the end of a storm that is 0.25 inches or greater. Where sites have been finally stabilized, inspections shall be conducted at least once every month.

- · Points of discharge to waters of the United States.
- Points of discharge to municipal separate storm sewer systems.
- Disturbed areas of the site that have not been finally stabilized.
- · Areas used for storage of materials that are exposed to precipitation.
- Structural controls.
- Stormwater management systems.
- Locations where vehicles enter or exit the site.

6.0 NON-STORMWATER DISCHARGES:

The Contractor shall be responsible for reporting any hazardous substance spills that may equal or exceed a Reportable Quantity (RQ). Refer to EPA's List of Hazardous Substances and Reportable Quantities (EPA 40 CFR 302.4 & 117). This list can be obtained from EPA's website (www.epa.gov) or by contacting EPA. If an RQ release does occur the Contractor shall perform the following procedures:

- Notify the National Response Center immediately at 800-424-8802.
- Provide written description of the release within 14 days providing dates, cause and prevention methods to the regional EPA office.
- · Modify the SWPPP as necessary to address added prevention methods.

· Address any changes in design, construction operations or maintenance, which has an effect on the potential for discharge of pollutants.

7.0 IMPLEMENTATION CHECKLIST:

The Contractor shall maintain records of construction activities including, but not limited to:

Dates when major grading activities occur.

Dates when construction activities temporarily cease on a portion of the site.

Dates when construction activities permanently cease on a portion of the site.

· Dates when stabilization measures are initiated on the site.

7.2 Inspection Reports:

The Contractor shall prepare inspection reports summarizing the following, but not limited to:

Name of inspector.

Qualifications of inspector.

Measures/areas inspected.

· Observed conditions.

· Changes necessary to the SWPPP.

7.3 Releases of Reportable Quantities of Oil or Hazardous Materials:

The Contractor shall report any releases of reportable quantities of oil or hazardous materials if they occur as per the measures outlined in Section 6.0 of the SWPPP.

7.4 SWPPP Modification:

The Contractor shall modify the SWPPP as necessary to:

 Comply with minimum permit requirements when notified by FDEP that the plan does not comply.

Prevent reoccurrence of reportable quantity releases of hazardous material or oil.

8.0 TERMINATION CHECKLIST:


The following items shall be complete before submitting the NOT:

All soil disturbing activities are complete.


 Temporary erosion and sediment control measures have been REMOVED or will be REMOVED at an appropriate time.


 All areas of the construction site not otherwise covered by permanent pavement or structure have been stabilized with uniform perennial vegetative cover with a density of 70% or equivalent measures have been employed.







- -









~ .

~.

